

Schedule of Items

Proposal ID: C0000101243C01

Oversight/State Project No.: (NFO) 0604-020-640, B693, C501

Order No.: I61

Federal Project No.: BR-5A27(395)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING (CONSTRUCTION)	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	1,433.000 CY				
0050	303 305	00140 BORROW EXCAVATION	35.000 CY				
0060	303	00155 GEOTEXTILE (EMBANKMENT STABILIZATION)	1,870.000 SY				
0070	305	00355 GEOTEXTILE (SUBGRADE STABILIZATION)	630.000 SY				
0080	302	00700 POST INSTALLATION INSPECTION	32.000 LF				
0090	302	01156 STORM SEWER PIPE 15"	32.000 LF				
0100	302	06150 15" END SECTION ES-1 OR 2	4.000 EA				
0110	302	06765 DROP INLET DI-2C,L=6'	4.000 EA				
0120	308 309	10128 AGGR. BASE MATL. TY. I NO. 21B	2,420.000 TON				
0130	308	10250 AGGR. MATERIAL AGGR. MATERIAL NO. 3 STONE	1,103.000 TON				

Schedule of Items

Proposal ID: C0000101243C01

Oversight/State Project No.: (NFO) 0604-020-640, B693, C501

Order No.: I61

Federal Project No.: BR-5A27(395)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	308	10250 AGGR. MATERIAL AGGR. MATERIAL NO. 57 STONE	397.000 TON	_____	_____	_____	_____
0150	315	10608 ASPHALT CONCRETE TY. SM-12.5D	513.000 TON	_____	_____	_____	_____
0160	315	10610 ASPHALT CONCRETE TY. IM-19.0A	153.000 TON	_____	_____	_____	_____
0170	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	2,519.000 SY	_____	_____	_____	_____
0180	315	10642 ASPHALT CONCRETE TY. BM-25.0A	257.000 TON	_____	_____	_____	_____
0190	502	12030 STD. CURB CG-3	44.000 LF	_____	_____	_____	_____
0200	502	12032 RADIAL CURB CG-3	8.000 LF	_____	_____	_____	_____
0210	502	12700 STD. COMB. CURB & GUTTER CG-7	613.000 LF	_____	_____	_____	_____
0220	502	12710 RADIAL COMB. CURB & GUTTER CG-7	8.000 LF	_____	_____	_____	_____
0230	505	13323 GUARDRAIL GR-2A	1,549.000 LF	_____	_____	_____	_____
0240	505	13345 ALTERNATE BREAKAWAY CABLE TERMINAL (GR-9)	4.000 EA	_____	_____	_____	_____
0250	505	13383 FIXED OBJECT ATTACH. GR-FOA-1 TY. I	4.000 EA	_____	_____	_____	_____

Schedule of Items

Page: 4

Proposal ID: C0000101243C01

Oversight/State Project No.: (NFO) 0604-020-640, B693, C501

Order No.: I61

Federal Project No.: BR-5A27(395)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	512 ATTD	24265 MAINTENANCE OF TRAFFIC VA STRUCTURE NO. 6004	LUMP SUM	LUMP SUM			
0270	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	2,080.000 HR				
0280	ATTD	24355 POLICE PATROL UNIFORM FLAGGER	80.000 HR				
0290	508	24430 DEMOLITION OF PAVEMENT (FLEXIBLE)	336.000 SY				
0300	510	24600 REMOVE EXISTING GUARDRAIL	1,845.000 LF				
0310	ATTD	25574 CONTRACT NBIS ACCESS, UNDER BRIDGE STRUCTURE 30028	1.000 DAY				
0320	414	26117 DRY RIPRAP CL. AI	494.000 TON				
0330	414	26127 DRY RIPRAP CL.I 26"	780.000 TON				
0340	603	27102 REGULAR SEED	110.000 LB				
0350	603	27103 OVERSEEDING	69.000 LB				
0360	603	27215 FERTILIZER(15-30-15)	0.100 TON				
0370	603	27250 LIME	1.000 TON				
0380	303	27415 CHECK DAM(ROCK) TY. II	8.000 EA				

Schedule of Items

Page: 5

Proposal ID: C0000101243C01

Oversight/State Project No.: (NFO) 0604-020-640, B693, C501

Order No.: I61

Federal Project No.: BR-5A27(395)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	303	27422 DEWATERING BASIN	2.000 EA	_____	_____	_____	_____
0400	303	27430 SILTATION CONTROL EXCAVATION	816.000 CY	_____	_____	_____	_____
0410	303	27461 INLET PROTECTION TYPE B	4.000 EA	_____	_____	_____	_____
0420	303	27505 TEMP. SILT FENCE	4,620.000 LF	_____	_____	_____	_____
0430	ATTD	27525 TURBIDITY CURTAIN, PERVIOUS	3,590.000 LF	_____	_____	_____	_____
0440	510 ATTD	50902 TRAFFIC SIGN REMOVE AND DISPOSE OF GROUND MOUNTED SIGN STRUCTURE AND SIGN PANEL	3.000 EA	_____	_____	_____	_____
0450	703	51910 SAW CUT	1,687.000 LF	_____	_____	_____	_____
0460	704	54020 TYPE A PAVEMENT LINE MARKING 4"	5,723.000 LF	_____	_____	_____	_____
0470	512	54105 ERADICATION OF EXIST. PAVEMENT MARKING	800.000 LF	_____	_____	_____	_____
0480	ATTD	60420 CONCRETE LIGHTWEIGHT, LOW CRACKING BRIDGE	81.200 CY	_____	_____	_____	_____
0490	404	60490 BRIDGE DECK GROOVING	229.000 SY	_____	_____	_____	_____
0500	406	61712 CORROSION RESISTANT REINF. STEEL CL. II	9,060.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101243C01

Oversight/State Project No.: (NFO) 0604-020-640, B693, C501

Order No.: I61

Federal Project No.: BR-5A27(395)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	410	62046 RAILING, BR27D 3 RAILS	126.000 LF	_____	_____	_____	_____
0520	405	62535 BRIDGE SUPERSTRUCTURE PRESTRESSED CONC. SLAB 4'X21"X(+55-60) (LIGHTWEIGHT 120 PCF)	9.000 EA	_____	_____	_____	_____
0530	ATTD	62537 BRIDGE SUPERSTRUCTURE ECC FOR SHEAR KEYS	480.000 LF	_____	_____	_____	_____
0540	305	64005 SELECT MATL. TY. I MIN. CBR-30	706.000 TON	_____	_____	_____	_____
0550	401	64011 STRUCTURE EXCAVATION	531.000 CY	_____	_____	_____	_____
0560	401	64032 GEOCOMPOSITE WALL DRAIN	34.000 SY	_____	_____	_____	_____
0570	401	64036 PIPE UNDERDRAIN 6"	98.000 LF	_____	_____	_____	_____
0580	ATTD	64102 DYNAMIC PILE TEST (END BEARING PILES)	2.000 EA	_____	_____	_____	_____
0590	403	64112 STEEL PILES 12"	336.000 LF	_____	_____	_____	_____
0600	403	64765 PILE POINT FOR 12" STEEL PILE	12.000 EA	_____	_____	_____	_____
0610	404	65013 CONCRETE CLASS A3	36.000 CY	_____	_____	_____	_____
0620	ATTD	65095 CONCRETE PILE WELL	6.000 CY	_____	_____	_____	_____

Schedule of Items

Page: 7

Proposal ID: C0000101243C01

Oversight/State Project No.: (NFO) 0604-020-640, B693, C501

Order No.: I61

Federal Project No.: BR-5A27(395)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0630	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	4,760.000 LB	_____	_____	_____	_____
0640	414	66127 DRY RIPRAP CL.I 26"	380.000 TON	_____	_____	_____	_____
0650	413	67900 DISM.& REM. EX. STR. 6004	LUMP SUM	LUMP SUM		_____	_____
0660	413	68476 ENV.& WORK. PROTECTION STR 6004	LUMP SUM	LUMP SUM		_____	_____
0670	413	68490 DISPOSAL OF MATERIAL STR 6004	LUMP SUM	LUMP SUM		_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____