

Schedule of Items

Proposal ID: C00104688M01

Oversight/State Project No.: (NFO)0200-051-S74,M501

Order No.: J33

Federal Project No.: HSIP-051-6(016)

Contractor: _____

SECTION: 0100

ALL PROJECT ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING (CONSTRUCTION)	LUMP SUM	LUMP SUM			
0030	303	00118 EXCAVATION UNDERCUT	5.000 CY				
0040	ATTD	00125 GRADING	LUMP SUM	LUMP SUM			
0050	302 504	00525 CONCRETE CLASS A3 MISC.	1.000 CY				
0060	308 309	10100 AGGR. MATL. NO. 21B	65.000 TON				
0070	315	10610 ASPHALT CONCRETE TY. IM-19.0A	20.000 TON				
0080	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	180.000 SY				
0090	315	10636 ASPHALT CONCRETE TY. SM-9.5D	15.000 TON				
0100	315	11070 SAW-CUT ASPH CONC FULL DEPTH	312.000 LF				
0110	502	12600 STD. COMB. CURB & GUTTER CG-6	85.000 LF				
0120	502	12710 RADIAL COMB. CURB & GUTTER CG-7	40.000 LF				
0130	ATTD	13108 CG-12 DETECTABLE WARNING SURFACE	16.000 SY				

Schedule of Items

Proposal ID: C00104688M01

Oversight/State Project No.: (NFO)0200-051-S74,M501

Order No.: J33

Federal Project No.: HSIP-051-6(016)

Contractor: _____

SECTION: 0100

ALL PROJECT ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	145.000 SY	_____	_____	_____	_____
0150	504	13222 HYDRAULIC CEMENT CONC. SIDEWALK 7"	25.000 SY	_____	_____	_____	_____
0160	ATTD	14120 REMOVAL OF COMB. CURB AND GUTTER	130.000 LF	_____	_____	_____	_____
0170	ATTD	14440 SAW CUT SIDEWALK	10.000 LF	_____	_____	_____	_____
0180	ATTD	14450 SAW CUT CURB, GUTTER AND ENTRANCES	266.000 LF	_____	_____	_____	_____
0190	515	16523 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	45.000 SY	_____	_____	_____	_____
0200	502	21020 MEDIAN STRIP MS-1	24.000 SY	_____	_____	_____	_____
0210	ATTD	24265 MAINTENANCE OF TRAFFIC ..	LUMP SUM	LUMP SUM		_____	_____
0220	508	24420 DEMOLITION OF PAVEMENT (RIGID)	8.000 SY	_____	_____	_____	_____
0230	508	24430 DEMOLITION OF PAVEMENT (FLEXIBLE)	45.000 SY	_____	_____	_____	_____
0240	603	27102 REGULAR SEED	10.000 LB	_____	_____	_____	_____
0250	603	27215 FERTILIZER(15-30-15)	0.100 TON	_____	_____	_____	_____
0260	603	27250 LIME	0.100 TON	_____	_____	_____	_____

Schedule of Items

Page: 4

Proposal ID: C00104688M01

Oversight/State Project No.: (NFO)0200-051-S74,M501

Order No.: J33

Federal Project No.: HSIP-051-6(016)

Contractor: _____

SECTION: 0100

ALL PROJECT ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	303	27461 INLET PROTECTION TYPE B	2.000 EA	_____	_____	_____	_____
0280	510	41977 ADJUST EXIST. WATER METER BOX	4.000 EA	_____	_____	_____	_____
0290	701	50108 SIGN PANEL	91.000 SF	_____	_____	_____	_____
0300	700	50434 SIGN POST STP-1 2 1/2"	125.000 LF	_____	_____	_____	_____
0310	700	50490 CONCRETE FOUNDATION STP-1	5.000 EA	_____	_____	_____	_____
0320	PLAN	50617 RELOC. EXIST. SIGN STRUCT. TY. WP-1	2.000 EA	_____	_____	_____	_____
0330	PLAN	50759 RELOC. EXIST. SIGN PANEL TY. SP-1	2.000 EA	_____	_____	_____	_____
0340	700	50902 TRAFFIC SIGN (SOLAR POWERED RRFB)	2.000 EA	_____	_____	_____	_____
0350	704	54032 TYPE B CLASS I PAVE. LINE MARKING 4"	200.000 LF	_____	_____	_____	_____
0360	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	130.000 LF	_____	_____	_____	_____
0370	704	54217 SNOW PLOW. RAISED PAVE. MARKER ASPH.CONC	18.000 EA	_____	_____	_____	_____
Section: 0100				Total:		_____	_____
				Total Bid:		_____	_____