

Schedule of Items

Proposal ID: C000104959M01

Oversight/State Project No.: (NFO)0147-964-865, M501

Order No.: J49

Federal Project No.: CM-5A27(399)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING (CONSTRUCTION)	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	98.000 CY				
0050	303 305	00140 BORROW EXCAVATION	110.000 CY				
0060	302	00700 POST INSTALLATION INSPECTION	90.000 LF				
0070	302	01186 STORM SEWER PIPE 18"	90.000 LF				
0080	302	06815 DROP INLET DI-3A	1.000 EA				
0090	308 309	10128 AGGR. BASE MATL. TY. I NO. 21B	35.000 TON				
0100	315	10610 ASPHALT CONCRETE TY. IM-19.0A	21.000 TON				
0110	315	10636 ASPHALT CONCRETE TY. SM-9.5D	5.000 TON				
0120	315	11070 SAW-CUT ASPH CONC Saw Cut 6" Depth	481.000 LF				
0130	502	12020 STD. CURB CG-2	37.000 LF				

Schedule of Items

Proposal ID: C000104959M01

Oversight/State Project No.: (NFO)0147-964-865, M501

Order No.: J49

Federal Project No.: CM-5A27(399)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	502	12113 RADIAL MED. CURB MC-1	17.900 LF	_____	_____	_____	_____
0150	502	12600 STD. COMB. CURB & GUTTER CG-6	283.800 LF	_____	_____	_____	_____
0160	502	12610 RADIAL COMB. CURB & GUTTER CG-6	111.400 LF	_____	_____	_____	_____
0170	ATTD	13108 CG-12 DETECTABLE WARNING SURFACE	17.780 SY	_____	_____	_____	_____
0180	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	446.000 SY	_____	_____	_____	_____
0190	ATTD	14120 REMOVAL OF COMB. CURB AND GUTTER	70.000 LF	_____	_____	_____	_____
0200	ATTD	14450 SAW CUT CURB, GUTTER AND ENTRANCES	70.000 LF	_____	_____	_____	_____
0210	ATTD	24265 MAINTENANCE OF TRAFFIC ...	LUMP SUM	LUMP SUM	_____	_____	_____
0220	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	360.000 HR	_____	_____	_____	_____
0230	508	24410 DEMOLITION OF PAVEMENT	78.400 SY	_____	_____	_____	_____
0240	ATTD	24503 REMOVE EXIST. REMOVE AND DISPOSE OF EXIST. SIGNAL EQUIP.	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C000104959M01

Oversight/State Project No.: (NFO)0147-964-865, M501

Order No.: J49

Federal Project No.: CM-5A27(399)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	ATTD	24503 REMOVE EXIST. REMOVE AND SALVAGE OF EXIST. SIGNAL EQUIP.	LUMP SUM	LUMP SUM			
0260	504	25000 HANDRAIL HR-1	65.000 LF				
0270	601	27000 SELECTIVE TREE REMOVAL TRIMMING AND CLEANUP	0.100 ACRE				
0280	602	27012 TOPSOIL CLASS A 2"	0.030 ACRE				
0290	603	27102 REGULAR SEED	69.000 LB				
0300	603	27103 OVERSEEDING	43.000 LB				
0310	603	27215 FERTILIZER(15-30-15)	0.060 TON				
0320	603	27250 LIME	0.760 TON				
0330	303	27284 EROSION CONTROL MULCH	375.000 SY				
0340	303	27415 CHECK DAM(ROCK) TY. II	3.000 EA				
0350	303	27451 INLET PROTECTION TYPE A	10.000 EA				
0360	303	27461 INLET PROTECTION TYPE B	10.000 EA				
0370	303	27505 TEMP. SILT FENCE	957.000 LF				
0380	510	41977 ADJUST EXIST. WATER METER BOX	1.000 EA				

Schedule of Items

Proposal ID: C000104959M01

Oversight/State Project No.: (NFO)0147-964-865, M501

Order No.: J49

Federal Project No.: CM-5A27(399)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	510	42765 ADJUST EXIST FRAME & COVER	2.000 EA	_____	_____	_____	_____
0400	701	50108 SIGN PANEL	193.810 SF	_____	_____	_____	_____
0410	700	50434 SIGN POST STP-1 2 1/2"	190.000 LF	_____	_____	_____	_____
0420	510 ATTD	50902 TRAFFIC SIGN RELOCATE EXISTING GROUND MOUNTED SIGN PANEL	2.000 EA	_____	_____	_____	_____
0430	510 ATTD	50902 TRAFFIC SIGN REMOVE & DISPOSE OF EXIST. GROUND MOUNTED SIGN STRUCTURE AND SIGN PANEL	6.000 EA	_____	_____	_____	_____
0440	703	51163 FLASHER	1.000 EA	_____	_____	_____	_____
0450	700	51170 ELECTRICAL SERVICE SE-5	1.000 EA	_____	_____	_____	_____
0460	703	51184 TRAFFIC SIGNAL HEAD SECTION 12" LED	39.000 EA	_____	_____	_____	_____
0470	703	51198 PEDESTRIAN ACTUATION PA-2	4.000 EA	_____	_____	_____	_____
0480	703	51199 PEDESTRIAN ACTUATION PA-3	4.000 EA	_____	_____	_____	_____
0490	700	51208 PEDESTAL POLE PF-2 8'	4.000 EA	_____	_____	_____	_____
0500	700	51212 PEDESTAL POLE PF-2 12'	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000104959M01

Oversight/State Project No.: (NFO)0147-964-865, M501

Order No.: J49

Federal Project No.: CM-5A27(399)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	700	51238 CONCRETE FOUNDATION SIGNAL POLE PF-8	36.000 CY	_____	_____	_____	_____
0520	700	51240 CONCRETE FOUNDATION PF-2	6.000 EA	_____	_____	_____	_____
0530	700	51248 CONC. FOUNDATION CONCRETE FOUNDATION CF-4	1.000 EA	_____	_____	_____	_____
0540	700	51248 CONC. FOUNDATION CONCRETE FOUNDATION STP-1 TY. E	2.000 EA	_____	_____	_____	_____
0550	ATTD	51248 CONC. FOUNDATION CONCRETE FOUNDATION, STP-1 TY. A	10.000 EA	_____	_____	_____	_____
0560	ATTD	51541 DETECTOR CAMERA	4.000 EA	_____	_____	_____	_____
0570	703	51541 DETECTOR INDUCTIVE LOOP AMPLIFIER	4.000 EA	_____	_____	_____	_____
0580	ATTD	51541 DETECTOR VIDEO DETECTION (2 INPUTS)	2.000 EA	_____	_____	_____	_____
0590	700	51602 14/4 CONDUCTOR CABLE	1,075.000 LF	_____	_____	_____	_____
0600	700	51607 14/7 CONDUCTOR CABLE	1,440.000 LF	_____	_____	_____	_____
0610	700	51614 CONDUCTOR CABLE CONDUCTOR CABLE 16/3	880.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000104959M01

Oversight/State Project No.: (NFO)0147-964-865, M501

Order No.: J49

Federal Project No.: CM-5A27(399)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0620	ATTD	51614 CONDUCTOR CABLE CONDUCTOR CABLE COAXIAL	880.000 LF	_____	_____	_____	_____
0630	ATTD	51614 CONDUCTOR CABLE EMERGENCY PREEMPTION DETECTOR CABLE	645.000 LF	_____	_____	_____	_____
0640	700	51615 14/1 ENCLOSED COND. CABLE	1,970.000 LF	_____	_____	_____	_____
0650	700	51700 14/2 CONDUCTOR CABLE SHIELDED	2,100.000 LF	_____	_____	_____	_____
0660	703	51834 HANGER ASSEMBLY SMB-2, ONE WAY	2.000 EA	_____	_____	_____	_____
0670	703	51835 HANGER ASSEMBLY SMB-2, TWO WAY	4.000 EA	_____	_____	_____	_____
0680	703	51840 HANGER ASSEMBLY SM-3. ONE WAY	11.000 EA	_____	_____	_____	_____
0690	703	51912 SAW CUT 3/8"	590.000 LF	_____	_____	_____	_____
0700	703	51913 SAWCUT 5/8"	85.000 LF	_____	_____	_____	_____
0710	ATTD	51960 INSTALL INSTALL LUMINAIRE ARM	4.000 EA	_____	_____	_____	_____
0720	510 ATTD	51960 INSTALL INSTALL MAST ARM	4.000 EA	_____	_____	_____	_____
0730	ATTD	51960 INSTALL INSTALL SIGNAL POLE	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000104959M01

Oversight/State Project No.: (NFO)0147-964-865, M501

Order No.: J49

Federal Project No.: CM-5A27(399)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0740	510 ATTD	51963 REMOVE REMOVE EXISTING JUNCTION BOX OR MANHOLE	8.000 EA	_____	_____	_____	_____
0750	512	52000 TRAFFIC SIGNALIZATION TEMPORARY TRAFFIC CONTROL SIGNAL	LUMP SUM	LUMP SUM		_____	_____
0760	ATTD	52002 TRAFFIC SIGNALIZATION AUXILIARY OPTICAL PREEMPTION DETECTOR	2.000 EA	_____	_____	_____	_____
0770	703 ATTD	52002 TRAFFIC SIGNALIZATION CONTROLLER AND CABINET	1.000 EA	_____	_____	_____	_____
0780	ATTD	52002 TRAFFIC SIGNALIZATION EMERGENCY PREEMPTION 3-WAY	1.000 EA	_____	_____	_____	_____
0790	ATTD	52002 TRAFFIC SIGNALIZATION EXTERNAL 8 BATTERY PACK	1.000 EA	_____	_____	_____	_____
0800	ATTD	52002 TRAFFIC SIGNALIZATION INTEGRAL GENERATOR CONNECTION	1.000 EA	_____	_____	_____	_____
0810	ATTD	52002 TRAFFIC SIGNALIZATION MODEM	1.000 EA	_____	_____	_____	_____
0820	ATTD	52002 TRAFFIC SIGNALIZATION UNINTERRUPTIBLE POWER SUPPLY	1.000 EA	_____	_____	_____	_____
0830	ATTD	52002 TRAFFIC SIGNALIZATION UNINTERRUPTIBLE POWER SUPPLY CABINET	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000104959M01

Oversight/State Project No.: (NFO)0147-964-865, M501

Order No.: J49

Federal Project No.: CM-5A27(399)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0840	703 ATTD	52404 PEDESTRIAN SIGNAL HEAD SP-9	6.000 EA	_____	_____	_____	_____
0850	704	54032 TYPE B CLASS I PAVE. LINE MARKING 4"	245.000 LF	_____	_____	_____	_____
0860	ATTD	54100 PAVEMENT MARKING PAVEMENT MARKING THERMOPLASTIC, 12"	56.000 LF	_____	_____	_____	_____
0870	ATTD	54100 PAVEMENT MARKING PAVEMENT MARKING THERMOPLASTIC, 24"	425.000 LF	_____	_____	_____	_____
0880	ATTD	54101 PAVEMENT MARKING YIELD LINE MESSAGE MARKING 36"	12.000 EA	_____	_____	_____	_____
0890	512	54105 ERADICATION OF EXIST. PAVEMENT MARKING	430.000 LF	_____	_____	_____	_____
0900	700	55080 8 CONDUCTOR CABLE	1,530.000 LF	_____	_____	_____	_____
0910	705	55352 CONTROL CENTER CCW-1 TYPE C	1.000 EA	_____	_____	_____	_____
0920	705	55504 LUMINAIRE 400 WATT H.P.S.	4.000 EA	_____	_____	_____	_____
0930	700	55587 JUNCTION BOX JB-S2	8.000 EA	_____	_____	_____	_____
0940	700	55588 JUNCTION BOX JB-S3	2.000 EA	_____	_____	_____	_____
0950	700	56014 ELECT. SER. GRD. ELECTRODE(10')	5.000 EA	_____	_____	_____	_____

Schedule of Items

Page: 10

Proposal ID: C000104959M01

Oversight/State Project No.: (NFO)0147-964-865, M501

Order No.: J49

Federal Project No.: CM-5A27(399)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0960	700	56021 1" PVC CONDUIT	60.000 LF	_____	_____	_____	_____
0970	700	56050 BORED CONDUIT 2"	1,260.000 LF	_____	_____	_____	_____
0980	700	56051 BORED CONDUIT 3"	385.000 LF	_____	_____	_____	_____
0990	700	56053 2" PVC CONDUIT	420.000 LF	_____	_____	_____	_____
1000	700	56054 3" PVC CONDUIT	50.000 LF	_____	_____	_____	_____
1010	700	56200 TRENCH EXCAVATION ECI-1	415.000 LF	_____	_____	_____	_____
1020	ATTD	70515 ENVIR. PROTECTION DISPOSAL OF CONTAMINATED GROUNDWATER	210.000 GAL	_____	_____	_____	_____
1030	ATTD	70525 ENVIR. PROTECTION DISPOSAL OF PETROLEUM CONTAMINATED SOIL	64.000 TON	_____	_____	_____	_____
Section: 1				Total:		_____	
				Total Bid:		_____	