Proposal ID: C000103210C01 **Oversight/State Project No.:** (NFO)0220-011-743,C501,D623-4
Order No.: J48 **Federal Project No.:** HSIP-5128(345)

Contractor: _____

SECTION: 0001 ALL PROJECT ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0020	517	00101 CONSTRUCTION SURVEYING (CONSTRUCTION)	LUMP SUM	LUMP SUM		_____	_____
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM		_____	_____
0040	303	00120 REGULAR EXCAVATION	6,573.000 CY	_____	_____	_____	_____
0050	303 305	00140 BORROW EXCAVATION	59,893.000 CY	_____	_____	_____	_____
0060	303	00155 GEOTEXTILE (EMBANKMENT STABILIZATION)	8,222.000 SY	_____	_____	_____	_____
0070	303	00212 MINOR STRUCTURE EXCAV. BOX CULVERT	896.000 CY	_____	_____	_____	_____
0080	302	00506 BEDDING MATL. AGGR. NO. 21B	115.000 TON	_____	_____	_____	_____
0090	302	00506 BEDDING MATL. AGGR. NO. 57 STONE	27.000 TON	_____	_____	_____	_____
0100	302	00522 CONCRETE CLASS A4 BOX CULVERT	54.000 CY	_____	_____	_____	_____
0110	302	00523 PRECAST BOX CULVERT DOUBLE 5' X 5'	80.000 LF	_____	_____	_____	_____
0120	302	00523 PRECAST BOX CULVERT DOUBLE 6' X 5'	63.000 LF	_____	_____	_____	_____
0130	302 504	00525 CONCRETE CLASS A3 MISC.	20.000 CY	_____	_____	_____	_____

Proposal ID: C000103210C01 **Oversight/State Project No.:** (NFO)0220-011-743,C501,D623-4
Order No.: J48 **Federal Project No.:** HSIP-5128(345)

Contractor: _____

SECTION: 0001 ALL PROJECT ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0140	ATTD	00529 FLOWABLE BACKFILL	10.000 CY	_____	_____	_____	_____
0150	302 406	00540 REINF. STEEL	6,778.000 LB	_____	_____	_____	_____
0160	302	00571 ENDWALL PIPE GRATE EW-11 TYPE I	35.000 LF	_____	_____	_____	_____
0170	302	00574 ENDWALL GRATE & FRAME EW-11A	1.000 EA	_____	_____	_____	_____
0180	501	00591 COMB. UNDERDRAIN CD-2	72.000 LF	_____	_____	_____	_____
0190	501	00595 OUTLET PIPE	48.000 LF	_____	_____	_____	_____
0200	302	00596 ENDWALL EW-12	4.000 EA	_____	_____	_____	_____
0210	302	00700 POST INSTALLATION INSPECTION	468.000 LF	_____	_____	_____	_____
0220	302	01180 18" PIPE	122.000 LF	_____	_____	_____	_____
0230	302	01181 JACKED & BORED 18" PIPE	65.000 LF	_____	_____	_____	_____
0240	302	01182 18" CONC. PIPE	101.000 LF	_____	_____	_____	_____
0250	302	01240 24" PIPE	154.000 LF	_____	_____	_____	_____
0260	302	01241 JACKED & BORED 24" PIPE	65.000 LF	_____	_____	_____	_____
0270	302	01242 24" CONC. PIPE	30.000 LF	_____	_____	_____	_____

Proposal ID: C000103210C01 **Oversight/State Project No.:** (NFO)0220-011-743,C501,D623-4
Order No.: J48 **Federal Project No.:** HSIP-5128(345)

Contractor: _____

SECTION: 0001 ALL PROJECT ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0280	302	01300 30" PIPE	77.000 LF	_____	_____	_____	_____
0290	PLAN	02093 SPEC. DESIGN INTERMITTENT SHOULDER RUMBLE STRIP	9,430.000 LF	_____	_____	_____	_____
0300	PLAN	02093 SPEC. DESIGN MODIFIED CENTERLINE RUMBLE STRIPES	4,715.000 LF	_____	_____	_____	_____
0310	PLAN	02093 SPEC. DESIGN MODIFIED CENTERLINE RUMBLE STRIPS	625.000 LF	_____	_____	_____	_____
0320	PLAN	02096 SPEC. DESIGN TEMPORARY SHORING	1,493.000 SY	_____	_____	_____	_____
0330	302	06180 18" END SECTION ES-1 OR 2	3.000 EA	_____	_____	_____	_____
0340	302	06740 DROP INLET DI-1	3.000 EA	_____	_____	_____	_____
0350	302	09056 MANHOLE MH-1 OR 2	69.000 LF	_____	_____	_____	_____
0360	302	09057 FRAME & COVER MH-1	5.000 EA	_____	_____	_____	_____
0370	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	18.000 TON	_____	_____	_____	_____
0380	414	09150 EROSION CONTROL STONE CLASS I, EC-1	428.100 TON	_____	_____	_____	_____
0390	414	09152 EROSION CONTROL STONE CLASS II, EC-1	195.000 TON	_____	_____	_____	_____

Proposal ID: C000103210C01 **Oversight/State Project No.:** (NFO)0220-011-743,C501,D623-4
Order No.: J48 **Federal Project No.:** HSIP-5128(345)

Contractor: _____

SECTION: 0001 ALL PROJECT ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0400	303	09250 SLOPE DRAIN	13.000 EA	_____	_____	_____	_____
0410	308 309	10065 AGGR. MATL. NO. 1	12,732.000 TON	_____	_____	_____	_____
0420	308 309	10100 AGGR. MATL. NO. 21B	115.000 TON	_____	_____	_____	_____
0430	308 309	10128 AGGR. BASE MATL. TY. I NO. 21B	7,642.000 TON	_____	_____	_____	_____
0440	ATTD	10498 PAVEMENT ASPHALT PAVEMENT GROOVING 7"	9,250.000 LF	_____	_____	_____	_____
0450	315	10607 ASPHALT CONCRETE TY. SM-12.5A	35.000 TON	_____	_____	_____	_____
0460	315	10611 ASPHALT CONCRETE TY. IM-19.0D	2,216.000 TON	_____	_____	_____	_____
0470	515	10631 FLEXIBLE PAVE. PLANING DEEP MILLING	3,187.000 SY	_____	_____	_____	_____
0480	315	10636 ASPHALT CONCRETE TY. SM-9.5D	1,634.000 TON	_____	_____	_____	_____
0490	315	10642 ASPHALT CONCRETE TY. BM-25.0A	6,554.000 TON	_____	_____	_____	_____
0500	703	11070 SAW-CUT ASPH CONC SAW CUT	2,698.000 LF	_____	_____	_____	_____
0510	505	13312 GUARDRAIL TERMINAL GR-7 (NCHRP 350)	3.000 EA	_____	_____	_____	_____

Proposal ID: C000103210C01 **Oversight/State Project No.:** (NFO)0220-011-743,C501,D623-4
Order No.: J48 **Federal Project No.:** HSIP-5128(345)

Contractor: _____

SECTION: 0001 ALL PROJECT ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0520	505	13320 GUARDRAIL GR-2	6,283.000 LF	_____	.____	_____	.____
0530	505	13345 ALTERNATE BREAKAWAY CABLE TERMINAL (GR-9)	8.000 EA	_____	.____	_____	.____
0540	505	13355 GUARDRAIL GR-10	75.000 LF	_____	.____	_____	.____
0550	505	13392 FIXED OBJECT ATTACH. GR-FOA-2 TY. I	2.000 EA	_____	.____	_____	.____
0560	502	13461 MEDIAN BARRIER MB-7E	111.000 LF	_____	.____	_____	.____
0570	502	13462 MEDIAN BARRIER MB-7F	130.000 LF	_____	.____	_____	.____
0580	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	8,689.000 LF	_____	.____	_____	.____
0590	512	13630 IMPACT ATTENUATOR SERVICE TYPE I-A	17.000 EA	_____	.____	_____	.____
0600	507	23560 TEMP. SAFETY FENCE 4'	180.000 LF	_____	.____	_____	.____
0610	511	24100 ALLAYING DUST	194.000 HR	_____	.____	_____	.____
0620	512	24160 CONSTRUCTION SIGNS	4,894.000 SF	_____	.____	_____	.____
0630	512	24260 CR. RUN AGGR. NO. 25 OR 26	79.000 TON	_____	.____	_____	.____
0640	512	24272 TRUCK MOUNTED ATTENUATOR	992.000 HR	_____	.____	_____	.____

Proposal ID: C000103210C01 **Oversight/State Project No.:** (NFO)0220-011-743,C501,D623-4
Order No.: J48 **Federal Project No.:** HSIP-5128(345)

Contractor: _____

SECTION: 0001 ALL PROJECT ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0650	512	24278 GROUP 2 CHANNELIZING DEVICES	18,660.000 DAY	_____	_____	_____	_____
0660	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	19,296.000 HR	_____	_____	_____	_____
0670	512	24282 FLAGGER SERVICE	824.000 HR	_____	_____	_____	_____
0680	512	24288 WARNING LIGHT TY. B	4,500.000 DAY	_____	_____	_____	_____
0690	508	24430 DEMOLITION OF PAVEMENT (FLEXIBLE)	13,251.000 SY	_____	_____	_____	_____
0700	510	24600 REMOVE EXISTING GUARDRAIL	5,918.000 LF	_____	_____	_____	_____
0710	514	25506 FIELD OFFICE TY.II	22.000 MO	_____	_____	_____	_____
0720	414	26116 DRY RIPRAP CL. AI	310.000 SY	_____	_____	_____	_____
0730	602	27012 TOPSOIL CLASS A 2"	1.000 ACRE	_____	_____	_____	_____
0740	603	27102 REGULAR SEED	4,834.000 LB	_____	_____	_____	_____
0750	603	27103 OVERSEEDING	1,343.000 LB	_____	_____	_____	_____
0760	603	27104 LEGUME SEED	286.000 LB	_____	_____	_____	_____
0770	603	27105 LEGUME OVERSEEDING	179.000 LB	_____	_____	_____	_____
0780	603	27215 FERTILIZER(15-30-15)	3.000 TON	_____	_____	_____	_____

Proposal ID: C000103210C01 **Oversight/State Project No.:** (NFO)0220-011-743,C501,D623-4
Order No.: J48 **Federal Project No.:** HSIP-5128(345)

Contractor: _____

SECTION: 0001 ALL PROJECT ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0790	603	27250 LIME	43.000 TON	_____.	____	_____.	____
0800	ATTD.	27275 EROSION CONTROL TEMPORARY SILT FENCE TYPE B	12,992.000 LF	_____.	____	_____.	____
0810	606	27321 PROTECTIVE COVERING EC-2	1,454.000 SY	_____.	____	_____.	____
0820	606	27325 SOIL STABILIZATION MAT EC-3 TYPE A	231.000 SY	_____.	____	_____.	____
0830	303	27410 CHECK DAM, ROCK TY. I	11.000 EA	_____.	____	_____.	____
0840	303	27415 CHECK DAM(ROCK) TY. II	166.000 EA	_____.	____	_____.	____
0850	303	27422 DEWATERING BASIN	6.000 EA	_____.	____	_____.	____
0860	303	27430 SILTATION CONTROL EXCAVATION	2,748.000 CY	_____.	____	_____.	____
0870	608	27440 MOWING	100.000 HR	_____.	____	_____.	____
0880	303	27505 TEMP. SILT FENCE	396.000 LF	_____.	____	_____.	____
0890	308	27552 NO. 57 STONE ..	114.000 TON	_____.	____	_____.	____
0900	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	670.000 CY	_____.	____	_____.	____

Proposal ID: C000103210C01 **Oversight/State Project No.:** (NFO)0220-011-743,C501,D623-4
Order No.: J48 **Federal Project No.:** HSIP-5128(345)

Contractor: _____

SECTION: 0001 ALL PROJECT ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0910	ATTD	38953 LANDSCAPE NONTIDAL WETLAND TEMPORARY IMPACT RESTORATION	LUMP SUM	LUMP SUM		_____	. _____
0920	701	50108 SIGN PANEL	22.400 SF	_____	. _____	_____	. _____
0930	700	50430 SIGN POST STP-1 2"	36.000 LF	_____	. _____	_____	. _____
0940	700	50434 SIGN POST STP-1 2 1/2"	40.000 LF	_____	. _____	_____	. _____
0950	700	50490 CONCRETE FOUNDATION STP-1	9.000 EA	_____	. _____	_____	. _____
0960	PLAN	50759 RELOC. EXIST. SIGN PANEL TY. SP-1	5.000 EA	_____	. _____	_____	. _____
0970	PLAN	50867 REMOVE-DISPOSE SIGN STRUCT. TY. WP-1	11.000 EA	_____	. _____	_____	. _____
0980	ATTD	54100 PAVEMENT MARKING THERMO. MARK. W/ RETRO-REFLECT OPTICS BEAD PKG. 6" YELLOW (10' LINE, 30' SPACE)	175.000 LF	_____	. _____	_____	. _____
0990	ATTD	54100 PAVEMENT MARKING THERMO. MARK. W/ RETRO-REFLECT OPTICS BEAD PKG. 8" YELLOW (10' LINE, 30' SPACE)	4,105.000 LF	_____	. _____	_____	. _____
1000	ATTD	54100 PAVEMENT MARKING THERMOPLASTIC LINE MARKING WITH RETRO-REFLECTIVE OPTICS BEAD PACKAGE 6" WHITE	9,430.000 LF	_____	. _____	_____	. _____

Proposal ID: C000103210C01 **Oversight/State Project No.:** (NFO)0220-011-743,C501,D623-4
Order No.: J48 **Federal Project No.:** HSIP-5128(345)

Contractor: _____

SECTION: 0001 ALL PROJECT ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
1010	ATTD	54100 PAVEMENT MARKING THERMOPLASTIC LINE MARKING WITH RETRO-REFLECTIVE OPTICS BEAD PACKAGE 6" YELLOW	175.000 LF	_____	. _____	_____	. _____
1020	ATTD	54100 PAVEMENT MARKING THERMOPLASTIC LINE MARKING WITH RETRO-REFLECTIVE OPTICS BEAD PACKAGE 8" YELLOW	4,520.000 LF	_____	. _____	_____	. _____
1030	512	54105 ERADICATION OF EXIST. PAVEMENT MARKING	6,970.000 LF	_____	. _____	_____	. _____
1040	704	54217 SNOW PLOW. RAISED PAVE. MARKER ASPH.CONC	116.000 EA	_____	. _____	_____	. _____
1050	512	54510 CONSTR.PAVE.MARK. (TY.D,CL.I)4"	44,672.000 LF	_____	. _____	_____	. _____
1060	413	67900 DISM.& REM. EX. STR. NO. 1075	LUMP SUM	LUMP SUM		_____	. _____
1070	413	67900 DISM.& REM. EX. STR. NO. 1076	LUMP SUM	LUMP SUM		_____	. _____
1080	414	69627 DRY RIPRAP CL. I	578.000 TON	_____	. _____	_____	. _____

Section: 0001 **Total:** _____ . _____

Total Bid: _____ . _____