

Schedule of Items

Proposal ID: C000102948M01

Oversight/State Project No.: (NFO)0199-047-642,M501

Order No.: L65

Federal Project No.: CM-5A03(845)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0030	303	00120 REGULAR EXCAVATION	382.000 CY				
0040	303 305	00140 BORROW EXCAVATION	134.000 CY				
0050	302 504	00525 CONCRETE CLASS A3 MISC.	0.300 CY				
0060	302	01120 12" PIPE	24.000 LF				
0070	302	01156 STORM SEWER PIPE 15"	36.000 LF				
0080	302	06819 DROP INLET DI-3B,L=8'	1.000 EA				
0090	302	07004 DROP INLET DI-3F,L=6'	60.000 EA				
0100	302	09057 FRAME & COVER MH-1	1.000 EA				
0110	308 309	10128 AGGR. BASE MATL. TY. I NO. 21B	285.000 TON				
0120	310	10417 TACK COAT	581.000 GAL				
0130	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	56.000 SY				
0140	315	10635 ASPHALT CONC.TY. SM-9.5A	61.000 TON				

Schedule of Items

Proposal ID: C000102948M01

Oversight/State Project No.: (NFO)0199-047-642,M501

Order No.: L65

Federal Project No.: CM-5A03(845)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	315	10642 ASPHALT CONC. BASE COURSE TY. BM-25.0A	115.000 TON	_____	_____	_____	_____
0160	2016	11070 SAW-CUT ASPH CONC FULL DEPTH	711.000 LF	_____	_____	_____	_____
0170	502	12020 STD. CURB CG-2	70.000 LF	_____	_____	_____	_____
0180	502	12022 RADIAL CURB CG-2	15.000 LF	_____	_____	_____	_____
0190	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	9.400 TON	_____	_____	_____	_____
0200	511	24100 ALLAYING DUST	8.000 HR	_____	_____	_____	_____
0210	512	24160 TEMPORARY (CONSTRUCTION) SIGN	538.000 SF	_____	_____	_____	_____
0220	512	24272 TRUCK MOUNTED ATTENUATOR	344.000 HR	_____	_____	_____	_____
0230	512	24278 GROUP 2 CHANNELIZING DEVICES	3,386.000 DAY	_____	_____	_____	_____
0240	512	24281 ELECTRONIC ARROW BOARD	344.000 HR	_____	_____	_____	_____
0250	508	24430 DEMOLITION OF PAVEMENT (FLEXIBLE)	141.000 SY	_____	_____	_____	_____
0260	510	24503 REMOVE EXIST. AND DISPOSE SIGNAL EQUIPMENT	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C000102948M01

Oversight/State Project No.: (NFO)0199-047-642,M501

Order No.: L65

Federal Project No.: CM-5A03(845)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	602	27012 TOPSOIL CLASS A 2"	0.130 ACRE	_____	_____	_____	_____
0280	603	27102 REGULAR SEED	25.000 LB	_____	_____	_____	_____
0290	603	27103 OVERSEEDING	16.000 LB	_____	_____	_____	_____
0300	603	27230 FERTILIZER (NITROGEN - N)	12.000 LB	_____	_____	_____	_____
0310	603	27231 FERTILIZER (PHOSPHOROUS - P)	0.500 LB	_____	_____	_____	_____
0320	603	27232 FERTILIZER (POTASSIUM - K)	12.000 LB	_____	_____	_____	_____
0330	606	27321 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 4	180.000 SY	_____	_____	_____	_____
0340	303	27415 CHECK DAM(ROCK) TY. II	2.000 EA	_____	_____	_____	_____
0350	303	27430 SILTATION CONTROL EXCAVATION	16.000 CY	_____	_____	_____	_____
0360	303	27461 INLET PROTECTION TYPE B	3.000 EA	_____	_____	_____	_____
0370	701	50108 SIGN PANEL	22.000 SF	_____	_____	_____	_____
0380	700	50430 SIGN POST STP-1, 2", 14 GAUGE	32.000 LF	_____	_____	_____	_____
0390	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	10.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000102948M01

Oversight/State Project No.: (NFO)0199-047-642,M501

Order No.: L65

Federal Project No.: CM-5A03(845)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	700	50488 CONCRETE FOUNDATION STP-1, TYPE D	3.000 EA	_____	_____	_____	_____
0410	700	50489 CONCRETE FOUNDATION STP-1, TYPE E	1.000 EA	_____	_____	_____	_____
0420	700	50902 TRAFFIC SIGN REMOVE/DISPOSE EXISTING G/M SIGN STR. AND SIGN PANEL	3.000 EA	_____	_____	_____	_____
0430	703	51184 TRAFFIC SIGNAL HEAD SECTION 12" LED	10.000 EA	_____	_____	_____	_____
0440	700	51541 DETECTOR INDUCTIVE LOOP (RACK MTD DUEL CHAN. CARD)	1.000 EA	_____	_____	_____	_____
0450	700	51602 14/4 CONDUCTOR CABLE	1,066.000 LF	_____	_____	_____	_____
0460	700	51607 14/7 CONDUCTOR CABLE	100.000 LF	_____	_____	_____	_____
0470	700	51614 CONDUCTOR CABLE EMERGENCY PREEMPTION DETECTOR CABLE	433.000 LF	_____	_____	_____	_____
0480	700	51615 14/1 ENCLOSED COND. CABLE	1,574.000 LF	_____	_____	_____	_____
0490	700	51700 14/2 CONDUCTOR CABLE SHIELDED	898.000 LF	_____	_____	_____	_____
0500	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000102948M01

Oversight/State Project No.: (NFO)0199-047-642,M501

Order No.: L65

Federal Project No.: CM-5A03(845)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	703	51912 LOOP SAW CUT 3/8"	528.000 LF	_____	_____	_____	_____
0520	703	51913 LOOP SAWCUT 5/8"	55.000 LF	_____	_____	_____	_____
0530	700	51961 MODIFY MODIFY EXISTING JUNCTION BOX	3.000 EA	_____	_____	_____	_____
0540	700	51962 RELOCATE RELOCATE MAST ARM SIGN	1.000 EA	_____	_____	_____	_____
0550	ATT	51965 INSTALL INSTALL / REMOVE TEMPORARY SIGN ON MAST ARM	LUMP SUM	LUMP SUM	_____	_____	_____
0560	ATT	51965 INSTALL INSTALL / REMOVE TEMPORARY SIGNAL HEAD	LUMP SUM	LUMP SUM	_____	_____	_____
0570	ATT	51965 INSTALL INSTALL / REMOVE TEMPORARY VIDEO DETECTION CAMERA WITH CABLE	LUMP SUM	LUMP SUM	_____	_____	_____
0580	ATT	51965 INSTALL RELOCATE SIGNAL CABLES	LUMP SUM	LUMP SUM	_____	_____	_____
0590	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	1,415.000 LF	_____	_____	_____	_____
0600	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	80.000 LF	_____	_____	_____	_____
0610	512	54105 ERADICATION OF EXIST. LINEAR PVMT MARKING	1,170.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000102948M01

Oversight/State Project No.: (NFO)0199-047-642,M501

Order No.: L65

Federal Project No.: CM-5A03(845)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0620	512	54106 ERADICATION OF EXIST. NONLINEAR PVMT MRKG	345.000 SF	_____	_____	_____	_____
0630	512	54512 TYPE D, CLASS II TEMP. PVMT MRKG 4"	1,134.000 LF	_____	_____	_____	_____
0640	704	54575 PVMT SYMB MRKG (SGL TURN ARROW) TY B, CL II	5.000 EA	_____	_____	_____	_____
0650	704	54578 PVMT SYMB MRKG (DBL TURN ARROW THRU/LT OR RT) TY B, CL II	2.000 EA	_____	_____	_____	_____
0660	700	55587 JUNCTION BOX JB-S2	3.000 EA	_____	_____	_____	_____
0670	700	56021 1" PVC CONDUIT	38.000 LF	_____	_____	_____	_____
0680	700	56051 BORED CONDUIT 3"	303.000 LF	_____	_____	_____	_____
0690	700	56200 TRENCH EXCAVATION ECI-1	20.000 LF	_____	_____	_____	_____
Section: 1				Total:		_____	_____
				Total Bid:		_____	_____