

Schedule of Items

Proposal ID: C00104666M01B

Oversight/State Project No.: (NFO)0250-043-797, M501

Order No.: M08

Federal Project No.: HSIP-5A27(394)

Contractor: _____

SECTION: 1

RTE 250 - SIX SIGNALS (COMBINED)

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING (CONSTRUCTION)	LUMP SUM	LUMP SUM			
0030	303	00125 GRADING	LUMP SUM	LUMP SUM			
0040	302	09057 FRAME & COVER MH-1	2.000 EA				
0050	308 309	10128 AGGR. BASE MATL. TY. I NO. 21B	410.000 TON				
0060	315	10610 ASPHALT CONCRETE TY. IM- 19.0A	36.000 TON				
0070	315	10636 ASPHALT CONC.TY. SM-9.5D	23.000 TON				
0080	315	10643 ASPHALT CONC. BASE COURSE TY. BM-25.0D	49.000 TON				
0090	502	12020 STD. CURB CG-2	26.000 LF				
0100	502	12030 STD. CURB CG-3	5.000 LF				
0110	502	12600 STD. COMB. CURB & GUTTER CG-6	227.000 LF				
0120	ATTD 502	12720 COMB. CURB & GUTTER HENRICO CO. CURB & GUTTER	247.000 LF				
0130	502	12940 ENTRANCE GUTTER CG-9D	94.000 SY				

Schedule of Items

Proposal ID: C00104666M01B

Oversight/State Project No.: (NFO)0250-043-797, M501

Order No.: M08

Federal Project No.: HSIP-5A27(394)

Contractor: _____

SECTION: 1

RTE 250 - SIX SIGNALS (COMBINED)

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	504	13108 CG-12 DETECTABLE WARNING SURFACE	39.000 SY	_____	_____	_____	_____
0150	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	518.000 SY	_____	_____	_____	_____
0160	ATTD	14120 REMOVAL OF COMB. CURB AND GUTTER	505.000 LF	_____	_____	_____	_____
0170	ATTD	14440 SAW CUT SIDEWALK	128.000 LF	_____	_____	_____	_____
0180	502	21020 MEDIAN STRIP MS-1	17.000 SY	_____	_____	_____	_____
0190	502	21215 MEDIAN STRIP MS-2	30.000 LF	_____	_____	_____	_____
0200	512	24160 TEMPORARY (CONSTRUCTION) SIGN	540.000 SF	_____	_____	_____	_____
0210	512	24272 TRUCK MOUNTED ATTENUATOR	300.000 HR	_____	_____	_____	_____
0220	512	24278 GROUP 2 CHANNELIZING DEVICES	6,300.000 DAY	_____	_____	_____	_____
0230	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	500.000 HR	_____	_____	_____	_____
0240	512	24281 ELECTRONIC ARROW BOARD	80.000 HR	_____	_____	_____	_____
0250	512	24360 SAFETY UNIFORM FLAGGERS	24.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00104666M01B

Oversight/State Project No.: (NFO)0250-043-797, M501

Order No.: M08

Federal Project No.: HSIP-5A27(394)

Contractor: _____

SECTION: 1

RTE 250 - SIX SIGNALS (COMBINED)

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	508	24430 DEMOLITION OF PAVEMENT (FLEXIBLE)	71.000 SY	_____	_____	_____	_____
0270	ATTD	24825 MODIFY EXIST. CONTROLLER CABINET	5.000 EA	_____	_____	_____	_____
0280	504	25004 HANDRAIL HR-1 TYPE III	70.000 LF	_____	_____	_____	_____
0290	602	27012 TOPSOIL CLASS A 2"	0.060 ACRE	_____	_____	_____	_____
0300	603	27102 REGULAR SEED	10.000 LB	_____	_____	_____	_____
0310	603	27104 LEGUME SEED	10.000 LB	_____	_____	_____	_____
0320	603	27230 FERTILIZER (NITROGEN - N)	7.500 LB	_____	_____	_____	_____
0330	603	27231 FERTILIZER (PHOSPHOROUS - P)	15.000 LB	_____	_____	_____	_____
0340	603	27232 FERTILIZER (POTASSIUM - K)	7.500 LB	_____	_____	_____	_____
0350	603	27250 LIME	0.060 TON	_____	_____	_____	_____
0360	606	27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	50.000 SY	_____	_____	_____	_____
0370	303	27430 SILTATION CONTROL EXCAVATION	40.000 CY	_____	_____	_____	_____
0380	303	27451 INLET PROTECTION TYPE A	14.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00104666M01B

Oversight/State Project No.: (NFO)0250-043-797, M501

Order No.: M08

Federal Project No.: HSIP-5A27(394)

Contractor: _____

SECTION: 1

RTE 250 - SIX SIGNALS (COMBINED)

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	303	27505 TEMP. SILT FENCE TYPE A	1,100.000 LF	_____	_____	_____	_____
0400	701	50108 SIGN PANEL	103.000 SF	_____	_____	_____	_____
0410	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	144.000 LF	_____	_____	_____	_____
0420	700	50486 CONCRETE FOUNDATION STP-1, TYPE B	12.000 EA	_____	_____	_____	_____
0430	ATTD	50617 RELOC. EXIST. SIGN STRUCT. TY. WP-1	1.000 EA	_____	_____	_____	_____
0440	ATTD	50759 RELOC. EXIST. SIGN PANEL TY. SP-1	7.000 EA	_____	_____	_____	_____
0445	700	51170 ELECTRICAL SERVICE SE-5	1.000 EA	_____	_____	_____	_____
0450	703	51184 TRAFFIC SIGNAL HEAD SECTION 12" LED	17.000 EA	_____	_____	_____	_____
0480	700	51210 PEDESTAL POLE PF-2 10'	15.000 EA	_____	_____	_____	_____
0490	700	51240 CONCRETE FOUNDATION PF- 2	15.000 EA	_____	_____	_____	_____
0500	700	51248 CONCRETE FOUNDATION CF-4	1.000 EA	_____	_____	_____	_____
0510	ATTD 703	51541 DETECTOR VIDEO DETECTION CAMERA	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00104666M01B

Oversight/State Project No.: (NFO)0250-043-797, M501

Order No.: M08

Federal Project No.: HSIP-5A27(394)

Contractor: _____

SECTION: 1

RTE 250 - SIX SIGNALS (COMBINED)

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	ATTD 703	51541 DETECTOR VIDEO DETECTION SYSTEM (2 INPUTS)	2.000 EA	_____	_____	_____	_____
0525	703	51525 EVP DETECTOR CABLE	100.000 LF	_____	_____	_____	_____
0530	700	51602 14/4 CONDUCTOR CABLE	6,450.000 LF	_____	_____	_____	_____
0540	700	51607 14/7 CONDUCTOR CABLE	300.000 LF	_____	_____	_____	_____
0550	700	51614 CONDUCTOR CABLE 16/3	650.000 LF	_____	_____	_____	_____
0560	ATTD	51614 CONDUCTOR CABLE COAXIAL	650.000 LF	_____	_____	_____	_____
0563	510	51614 CONDUCTOR CABLE REMOVE EXISTING CONDUCTOR CABLE	1,160.000 LF	_____	_____	_____	_____
0566	510	51614 CONDUCTOR CABLE RELOCATE & REUSE EXIST. CONDUCTOR CABLE	1,300.000 LF	_____	_____	_____	_____
0570	700	51615 14/1 ENCLOSED COND. CABLE	3,650.000 LF	_____	_____	_____	_____
0580	700	51700 14/2 CONDUCTOR CABLE SHIELDED	7,300.000 LF	_____	_____	_____	_____
0590	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	5.000 EA	_____	_____	_____	_____
0600	703	51834 HANGER ASSEMBLY SMB-2, ONE WAY	9.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00104666M01B

Oversight/State Project No.: (NFO)0250-043-797, M501

Order No.: M08

Federal Project No.: HSIP-5A27(394)

Contractor: _____

SECTION: 1

RTE 250 - SIX SIGNALS (COMBINED)

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0610	703	51835 HANGER ASSEMBLY SMB-2, TWO WAY	6.000 EA	_____	_____	_____	_____
0620	703	51838 HANGER ASSEMBLY SMB-3, ONE WAY	7.000 EA	_____	_____	_____	_____
0630	703	51839 HANGER ASSEMBLY SMB-3, TWO WAY	4.000 EA	_____	_____	_____	_____
0640	703	51840 HANGER ASSEMBLY SIGN MOUNTING SMD-2	4.000 EA	_____	_____	_____	_____
0650	703	51912 LOOP SAW CUT 3/8"	1,296.000 LF	_____	_____	_____	_____
0660	703	51913 LOOP SAWCUT 5/8"	115.000 LF	_____	_____	_____	_____
0670	703	51934 REMOVE EXISTING FOUNDATION	1.000 EA	_____	_____	_____	_____
0680	703	51936 REMOVE EXISTING CONTROLLER	1.000 EA	_____	_____	_____	_____
0690	510 ATTD	51963 REMOVE EXIST. J-BOX	7.000 EA	_____	_____	_____	_____
0700	510 ATTD	51963 REMOVE EXIST. SIGNAL/PED HEAD	9.000 EA	_____	_____	_____	_____
0710	510 ATTD	51963 REMOVE O.H. SIGN (MAST ARM / SPAN WIRE)	10.000 EA	_____	_____	_____	_____
0716	510	51963 REMOVE EXISTING ELECTRICAL SERVICE	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00104666M01B

Oversight/State Project No.: (NFO)0250-043-797, M501

Order No.: M08

Federal Project No.: HSIP-5A27(394)

Contractor: _____

SECTION: 1

RTE 250 - SIX SIGNALS (COMBINED)

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0720	510 ATTD	51964 REFURBISH RETRO-FIT LED (12")	17.000 EA	_____	_____	_____	_____
0730	703 ATTD	52002 TRAFFIC SIGNALIZATION CONTROLLER & CABINET	1.000 EA	_____	_____	_____	_____
0740	ATTD	52002 TRAFFIC SIGNALIZATION EXTERNAL 8 BATTERY PACK	1.000 EA	_____	_____	_____	_____
0750	ATTD	52002 TRAFFIC SIGNALIZATION UNINTERRUPTIBLE POWER SUPPLY	1.000 EA	_____	_____	_____	_____
0760	ATTD	52002 TRAFFIC SIGNALIZATION UPS CABINET WITH GENERATOR CONNECTION	1.000 EA	_____	_____	_____	_____
0763	ATTD	52002 TRAFFIC SIGNALIZATION ACCESSIBLE PED. PUSH BUTTON PA-2	26.000 EA	_____	_____	_____	_____
0766	ATTD	52002 TRAFFIC SIGNALIZATION ACCESSIBLE PED PUSH BUTTON PA-3	10.000 EA	_____	_____	_____	_____
0770	703	52404 PEDESTRIAN SIGNAL HEAD SP-9	36.000 EA	_____	_____	_____	_____
0780	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	3,025.000 LF	_____	_____	_____	_____
0790	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	720.000 LF	_____	_____	_____	_____
0800	512	54105 ERADICATION OF EXIST. LINEAR PVMT MARKING	1,470.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00104666M01B

Oversight/State Project No.: (NFO)0250-043-797, M501

Order No.: M08

Federal Project No.: HSIP-5A27(394)

Contractor: _____

SECTION: 1

RTE 250 - SIX SIGNALS (COMBINED)

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0810	512	54106 ERADICATION OF EXIST. NONLINEAR PVMT MRKG	1,367.000 SF	_____	_____	_____	_____
0820	704	54575 PVMT SYMB MRKG (SGL TURN ARROW) TY B, CL II	13.000 EA	_____	_____	_____	_____
0830	704	54576 PVMT SYMB MRKG (DBL TURN ARROW THRU/LT OR RT) TY A	6.000 EA	_____	_____	_____	_____
0840	700	55080 8 CONDUCTOR CABLE	820.000 LF	_____	_____	_____	_____
0850	700	55587 JUNCTION BOX JB-S2	10.000 EA	_____	_____	_____	_____
0860	700	56014 ELECT. SER. GRD. ELECTRODE(10')	28.000 EA	_____	_____	_____	_____
0870	700	56021 1" PVC CONDUIT	25.000 LF	_____	_____	_____	_____
0880	700	56050 BORED CONDUIT 2"	195.000 LF	_____	_____	_____	_____
0890	700	56051 BORED CONDUIT 3"	270.000 LF	_____	_____	_____	_____
0900	700	56053 2" PVC CONDUIT	535.000 LF	_____	_____	_____	_____
0910	700	56054 3" PVC CONDUIT	20.000 LF	_____	_____	_____	_____
0920	700	56200 TRENCH EXCAVATION ECI-1	355.000 LF	_____	_____	_____	_____
0930	412	68576 SAW CUTTING	342.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00104666M01B

Oversight/State Project No.: (NFO)0250-043-797, M501

Order No.: M08

Federal Project No.: HSIP-5A27(394)

Contractor: _____

SECTION: 1

RTE 250 - SIX SIGNALS (COMBINED)

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0940	303	85006 UNDERCUT EXCAVATION	35.000 CY	_____	_____	_____	_____
0950	ATTD	85011 FOG SEAL	LUMP SUM	LUMP SUM		_____	_____
0960	PLAN	85011 MODIFY SIGNAL (ALL SIGNALS)	LUMP SUM	LUMP SUM		_____	_____
0970	508	85021 DEMO. OF CONCRETE MEDIAN & SIDEWALK	316.000 SY	_____	_____	_____	_____
Section: 1				Total:		_____	_____
				Total Bid:		_____	_____