

Schedule of Items

Proposal ID: CM718PMA110927 Oversight/State Project No.: (NFO) PM7A-967-F18,P401
 Order No.: 730 Federal Project No.: PM07314

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	42,474.760 GAL	_____	_____	_____	_____
0020	315	10700 RUMBLE STRIP, ASPHALT	18,897.000 LF	_____	_____	_____	_____
0030	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	580.800 TON	_____	_____	_____	_____
0040	315	16350 ASPHALT CONC. TY. SM- 12.5A	46,213.170 TON	_____	_____	_____	_____
0050	315	16395 ASPH. CONC. BASE COURSE TY. BM-25.0A (T)	2,064.480 TON	_____	_____	_____	_____
0060	515	16516 FLEXIBLE PAVE. TIE-IN PLANING 0" - 2"	222.930 SY	_____	_____	_____	_____
0070	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	372,059.510 SY	_____	_____	_____	_____
0080	ATTD	24265 MAINTENANCE OF TRAFFIC MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM		_____	_____
0090	512	24282 FLAGGER SERVICE	1,536.000 HR	_____	_____	_____	_____
0100	704	54020 TYPE A PVMT LINE MRKG 4"	469,646.000 LF	_____	_____	_____	_____
0110	704	54028 TYPE A PAVEMENT LINE MRKG 24"	3,414.000 LF	_____	_____	_____	_____
0120	704	54043 TYPE B CLASS II PAVE. LINE MARKING 4"	1,980.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM718PMA110927 Oversight/State Project No.: (NFO) PM7A-967-F18,P401

Order No.: 730

Federal Project No.: PM07314

Contractor: _____

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	400.000 LF	_____	_____	_____	_____
0140	704	54079 TYPE B CLASS VI CONTRAST PVMT MRKG 4"	960.000 LF	_____	_____	_____	_____
0150	704	54101 PAVEMENT MARKING PVMT MESSAGE MARK. STOP AHEAD TY B CL. II	3.000 EA	_____	_____	_____	_____
0160	512	54106 ERADICATION OF EXIST. NONLINEAR PVMT MRKG	385.000 SF	_____	_____	_____	_____
0170	704	54217 SNOW PLOW. RAISED PAVE. MARKER ASPH.CONC	1,737.000 EA	_____	_____	_____	_____
0180	704	54396 PVMT MESSAGE MARK. SCHOOL ZONE TY B, CL II	1.000 EA	_____	_____	_____	_____
0190	704	54399 PVMT MESSAGE MARK. R/R CROSSING TY B, CL II	1.000 EA	_____	_____	_____	_____
0200	704	54428 TEMP. PVMT MRKG, TY. A, 4"	448,525.000 LF	_____	_____	_____	_____
0210	704	54575 PVMT SYMB MRKG (SGL TURN ARROW) TY B, CL II	83.000 EA	_____	_____	_____	_____
0220	704	54578 PVMT SYMB MRKG (DBL TURN ARROW THRU/LT OR RT) TY B, CL II	2.000 EA	_____	_____	_____	_____
0230	704	54670 BONUS ELIGIBLE PVMT BONUS ELIGIBLE TY. A. PAVE. LINE. MRKG. 24"	1.000 LF	_____	_____	_____	_____

Schedule of Items

Page: 4

Proposal ID: CM718PMA110927 Oversight/State Project No.: (NFO) PM7A-967-F18,P401

Order No.: 730

Federal Project No.: PM07314

Contractor: _____

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0240	704	54670 BONUS ELIGIBLE PVMT BONUS ELIGIBLE TY. A. PAVE. LINE. MRKG. 4"	1.000 LF	_____	_____	_____	_____
0250	704	54670 BONUS ELIGIBLE PVMT BONUS ELIGIBLE TY. B. CL.II PAVE. LINE. MRKG. 24"	1.000 LF	_____	_____	_____	_____
0260	704	54670 BONUS ELIGIBLE PVMT BONUS ELIGIBLE TY. B. CL.II PAVE. LINE. MRKG. 4"	1.000 LF	_____	_____	_____	_____
0270	704	54671 BONUS ELIGIBLE PVMT BONUS ELIGIBLE PAVE.MESSAGE MARK. SCHOOL ZONE TY B, CL. II	1.000 EA	_____	_____	_____	_____
0280	704	54671 BONUS ELIGIBLE PVMT BONUS ELIGIBLE PAVE.MESSAGE MARK.R/R CROSSING TY B, CL. II	1.000 EA	_____	_____	_____	_____
0290	704	54671 BONUS ELIGIBLE PVMT BONUS ELIGIBLE PAVEMENT MESSAGE MARK. "STOP AHEAD" TY B, CL. II	1.000 EA	_____	_____	_____	_____
0300	704	54671 BONUS ELIGIBLE PVMT BONUS ELIGIBLE PVMT. SYMB. MRKG. (DBL TURN ARROW THRU/LT OR RT) TY B, CL. II	1.000 EA	_____	_____	_____	_____
0310	704	54671 BONUS ELIGIBLE PVMT BONUS ELIGIBLE PVMT. SYMB. MRKG. (SGL TURN ARROW) TY B, CL. II	1.000 EA	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____

Schedule of Items

Page: 5

Proposal ID: CM718PMA110927

Oversight/State Project No.: (NFO) PM7A-967-F18,P401

Order No.: 730

Federal Project No.: PM07314

Contractor: _____

SECTION: 0002

ALTERNATE ITEM

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0320	ATTD	00306 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:		_____	_____
				Total Bid:		_____	_____