

Schedule of Items

Proposal ID: C0000097708B60  
Order No.: N78

Oversight/State Project No.: (NFO) 0684-009-743, M501, B660  
Federal Project No.: BROS-009-2 (037)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING (CONSTRUCTION)	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	19.000 CY				
0050	305	00140 BORROW EXCAVATION	142.000 CY				
0060	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	153.000 TON				
0070	308	10128 AGGR. BASE MATL. TY. I NO. 21B	98.000 TON				
0080	ATTD	10424 BLOTTED SEAL COAT TY. D	129.000 SY				
0090	511	24100 ALLAYING DUST	425.000 HR				
0100	512	24152 TYPE 3 BARRICADE 8'	8.000 EA				
0110	512	24160 TEMPORARY (CONSTRUCTION) SIGN	650.000 SF				
0120	512	24278 GROUP 2 CHANNELIZING DEVICES	5,300.000 DAY				
0130	512	24282 FLAGGER SERVICE	200.000 HR				

## Schedule of Items

Proposal ID: C0000097708B60

Oversight/State Project No.: (NFO) 0684-009-743, M501, B660

Order No.: N78

Federal Project No.: BROS-009-2 (037)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	512	24288 WARNING LIGHT TY. B	5,300.000 DAY	_____	_____	_____	_____
0150	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	44.000 LF	_____	_____	_____	_____
0160	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	147.000 SY	_____	_____	_____	_____
0170	505	24600 REMOVE EXISTING GUARDRAIL	33.000 LF	_____	_____	_____	_____
0180	514	25506 FIELD OFFICE TY.II	13.000 MO	_____	_____	_____	_____
0190	602	27012 TOPSOIL CLASS A 2"	0.510 ACRE	_____	_____	_____	_____
0200	603	27101 TEMPORARY SEED	51.000 LB	_____	_____	_____	_____
0210	603	27102 REGULAR SEED	168.000 LB	_____	_____	_____	_____
0220	603	27103 OVERSEEDING	68.000 LB	_____	_____	_____	_____
0230	603	27104 LEGUME SEED	8.000 LB	_____	_____	_____	_____
0240	603	27105 LEGUME OVERSEEDING	7.000 LB	_____	_____	_____	_____
0250	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,356.000 SY	_____	_____	_____	_____
0260	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,462.000 SY	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000097708B60

Oversight/State Project No.: (NFO) 0684-009-743, M501, B660

Order No.: N78

Federal Project No.: BROS-009-2 (037)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	603	27113 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	1,888.000 SY	_____	_____	_____	_____
0280	603	27230 FERTILIZER (NITROGEN - N)	70.000 LB	_____	_____	_____	_____
0290	603	27231 FERTILIZER (PHOSPHOROUS - P)	115.000 LB	_____	_____	_____	_____
0300	603	27232 FERTILIZER (POTASSIUM - K)	58.000 LB	_____	_____	_____	_____
0310	603	27250 LIME	1.800 TON	_____	_____	_____	_____
0320	303	27345 TEMPORARY DIVERSION DIKE	730.000 LF	_____	_____	_____	_____
0330	303	27415 CHECK DAM(ROCK) TY. II	8.000 EA	_____	_____	_____	_____
0340	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0350	303	27430 SILTATION CONTROL EXCAVATION	198.000 CY	_____	_____	_____	_____
0360	303	27504 TEMP. SILT FENCE TYPE B	1,099.000 LF	_____	_____	_____	_____
0370	701	50108 SIGN PANEL	129.000 SF	_____	_____	_____	_____
0380	700	50430 SIGN POST STP-1, 2", 14 GAUGE	94.000 LF	_____	_____	_____	_____
0390	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	108.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097708B60      Oversight/State Project No.: (NFO) 0684-009-743, M501, B660  
 Order No.: N78      Federal Project No.: BROS-009-2 (037)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	700	50490 CONCRETE SIGN FOUNDATION STP-1, TYPE F	20.000 EA	_____	_____	_____	_____
0410	ATTD	50860 REMOVE-DISPOSE SIGN STRUCT. TY. I	3.000 EA	_____	_____	_____	_____
0420	PLAN	60125 BRIDGE INCIDENTALS TEMPORARY WORK BRIDGE	LUMP SUM	LUMP SUM		_____	_____
0430	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	60.100 CY	_____	_____	_____	_____
0440	404	60490 BRIDGE DECK GROOVING	193.000 SY	_____	_____	_____	_____
0450	404	60495 COVER DEPTH SURVEY	193.000 SY	_____	_____	_____	_____
0460	406	61711 CORROSION RESISTANT REINF. STEEL CL. I	11,630.000 LB	_____	_____	_____	_____
0470	407	61812 STR.STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM		_____	_____
0480	410	62032 RAILING,KANSAS CORRAL 32" W/CURB	240.000 LF	_____	_____	_____	_____
0490	ATTD	62534 BRIDGE SUPERSTRUCTURE ELASTIC INCLUSION (10")	5.800 SY	_____	_____	_____	_____
0500	ATTD	62534 BRIDGE SUPERSTRUCTURE ELASTIC INCLUSION (13")	0.900 SY	_____	_____	_____	_____
0510	401	64011 STRUCTURE EXCAVATION	1,504.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097708B60  
Order No.: N78

Oversight/State Project No.: (NFO) 0684-009-743, M501, B660  
Federal Project No.: BROS-009-2 (037)

Contractor: \_\_\_\_\_

SECTION: 0001                      REGULAR BID ITEMS

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	401	64015 SELECT BACKFILL ABUTMENT ZONE	2,729.000 TON	_____	_____	_____	_____
0530	401	64032 GEOCOMPOSITE WALL DRAIN	159.000 SY	_____	_____	_____	_____
0540	401	64036 PIPE UNDERDRAIN 6"	44.000 LF	_____	_____	_____	_____
0550	403	64038 PREBORING PILE 24" DIA.	168.000 LF	_____	_____	_____	_____
0560	403	64112 STEEL PILES 12"	404.000 LF	_____	_____	_____	_____
0570	404	65013 CONCRETE CLASS A3	223.000 CY	_____	_____	_____	_____
0580	406	65200 REINF. STEEL	24,120.000 LB	_____	_____	_____	_____
0590	401	66120 COFFERDAM	1.000 EA	_____	_____	_____	_____
0600	414	66127 DRY RIPRAP CL.I 26"	104.000 TON	_____	_____	_____	_____
0610	PLAN	66921 BRIDGE SUBSTRUCTURE ROCK SOCKET 24" DIA.	208.000 LF	_____	_____	_____	_____
0620	PLAN	66926 BRIDGE SUBSTRUCTURE GEOSYNTHETIC REINFORCEMENT	1,430.000 SY	_____	_____	_____	_____
0630	413	67900 DISM.& REM. EX. STR. NUMBER 6103	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000097708B60      Oversight/State Project No.: (NFO) 0684-009-743, M501, B660  
 Order No.: N78      Federal Project No.: BROS-009-2 (037)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	430	67910 NBIS ACCESS, UNDER BRIDGE NBIS ACCESS UNDER BRIDGE-B660	1.000 DAY	_____	_____	_____	_____
0650	413	68476 ENV. & WORK. PROTECTION STR. NUMBER 6103	LUMP SUM	LUMP SUM	_____	_____	_____
0660	413	68492 MATERIAL DISPOSAL TYPE B	LUMP SUM	LUMP SUM	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____
				<b>Total Bid:</b>	_____	_____	_____