

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001 CONSTRUCTION BID ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING (CONSTRUCTION)	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	15,497.000 CY				
0050	303	00150 EMBANKMENT	905.000 CY				
0060	303	00212 MINOR STRUCTURE EXCAV. BOX CULVERT	240.000 CY				
0070	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	4,076.000 SY				
0080	PLAN	00506 BEDDING MATL. AGGR. NO. NO. 25 OR 26 AGGREGATE	137.000 TON				
0090	302	00522 CONCRETE CLASS A4 BOX CULVERT	159.000 CY				
0100	302 504	00525 CONCRETE CLASS A3 MISC.	18.300 CY				
0110	302 406	00540 REINF. STEEL	23,772.400 LB				
0120	501	00588 UNDERDRAIN UD-4	5,114.000 LF				
0130	501	00590 CROSSDRAIN CD-1	145.000 LF				

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001

CONSTRUCTION BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	501	00591 CROSSDRAIN CD-2	232.000 LF	_____	_____	_____	_____
0150	501	00595 OUTLET PIPE	84.000 LF	_____	_____	_____	_____
0160	302	00596 ENDWALL EW-12	3.000 EA	_____	_____	_____	_____
0170	302	01152 15" CONC. PIPE	610.000 LF	_____	_____	_____	_____
0180	302	01156 STORM SEWER PIPE 15"	1,649.000 LF	_____	_____	_____	_____
0190	302	01182 18" CONC. PIPE	40.000 LF	_____	_____	_____	_____
0200	302	01186 STORM SEWER PIPE 18"	1,356.000 LF	_____	_____	_____	_____
0210	302	01242 24" CONC. PIPE	40.000 LF	_____	_____	_____	_____
0220	302	01246 STORM SEWER PIPE 24"	1,049.000 LF	_____	_____	_____	_____
0230	302	01306 STORM SEWER PIPE 30"	200.000 LF	_____	_____	_____	_____
0240	302	01366 STORM SEWER PIPE 36"	319.000 LF	_____	_____	_____	_____
0250	302	01426 STORM SEWER PIPE 42"	917.000 LF	_____	_____	_____	_____
0260	302	02192 30" X 19" ELLIPTICAL CONC. PIPE	101.000 LF	_____	_____	_____	_____
0270	302	06151 15" END SECTION ES-1	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001

CONSTRUCTION BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	302	06361 36" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0290	302	06421 42" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0300	302	06502 30" X 19" END SECTION ES-1A	1.000 EA	_____	_____	_____	_____
0310	302	06740 DROP INLET DI-1	2.000 EA	_____	_____	_____	_____
0320	302	06752 DROP INLET DI-2B,L=14'	1.000 EA	_____	_____	_____	_____
0330	302	06785 DROP INLET DI-2E,L=10'	1.000 EA	_____	_____	_____	_____
0340	302	06815 DROP INLET DI-3A	4.000 EA	_____	_____	_____	_____
0350	302	06816 DROP INLET DI-3AA	1.000 EA	_____	_____	_____	_____
0360	302	06817 DROP INLET DI-3B,L=4'	4.000 EA	_____	_____	_____	_____
0370	302	06818 DROP INLET DI-3B,L=6'	2.000 EA	_____	_____	_____	_____
0380	302	06819 DROP INLET DI-3B,L=8'	13.000 EA	_____	_____	_____	_____
0390	302	06820 DROP INLET DI-3B,L=10'	6.000 EA	_____	_____	_____	_____
0400	302	06821 DROP INLET DI-3B,L=12'	3.000 EA	_____	_____	_____	_____
0410	302	06822 DROP INLET DI-3B,L=14'	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001

CONSTRUCTION BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	302	06824 DROP INLET DI-3B,L=18'	3.000 EA	_____	_____	_____	_____
0430	302	06829 DROP INLET DI-3BB,L=10'	1.000 EA	_____	_____	_____	_____
0440	302	06835 DROP INLET DI-3C,L=6'	5.000 EA	_____	_____	_____	_____
0450	302	06836 DROP INLET DI-3C,L=8'	3.000 EA	_____	_____	_____	_____
0460	302	07106 DROP INLET DI-4A	4.000 EA	_____	_____	_____	_____
0470	302	07110 DROP INLET DI-4B,L=6'	5.000 EA	_____	_____	_____	_____
0480	302	07112 DROP INLET DI-4B,L=8'	1.000 EA	_____	_____	_____	_____
0490	302	07114 DROP INLET DI-4B,L=10'	1.000 EA	_____	_____	_____	_____
0500	302	07116 DROP INLET DI-4B,L=12'	1.000 EA	_____	_____	_____	_____
0510	302	07206 DROP INLET DI-4C,L=8'	1.000 EA	_____	_____	_____	_____
0520	302	07506 DROP INLET DI-5	1.000 EA	_____	_____	_____	_____
0530	302	07508 DROP INLET DI-7	4.000 EA	_____	_____	_____	_____
0540	302	09056 MANHOLE MH-1 OR 2	44.700 LF	_____	_____	_____	_____
0550	302	09057 FRAME & COVER MH-1	8.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001

CONSTRUCTION BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0560	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	44.000 TON	_____	_____	_____	_____
0570	414	09150 EROSION CONTROL STONE CLASS I, EC-1	17.000 TON	_____	_____	_____	_____
0580	610	09155 GABIONS	84.000 CY	_____	_____	_____	_____
0590	308	10128 AGGR. BASE MATL. TY. I NO. 21B	7,983.000 TON	_____	_____	_____	_____
0600	204	10250 AGGR. MATERIAL NS AGGR. MATERIAL NO. 3 STONE FOR BACK FILL CEDAR LEVEL ROAD	4,230.000 TON	_____	_____	_____	_____
0610	303	10250 AGGR. MATERIAL NS NO. 57 STONE BACKFILL FOR BOX CULVERT	300.000 TON	_____	_____	_____	_____
0620	315	10610 ASPHALT CONCRETE TY. IM-19.0A	5,798.000 TON	_____	_____	_____	_____
0630	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	5,111.000 SY	_____	_____	_____	_____
0640	315	10635 ASPHALT CONC.TY. SM-9.5A	2,267.000 TON	_____	_____	_____	_____
0650	316	11040 CONCRETE ENTRANCE PAVE. 7"	173.000 SY	_____	_____	_____	_____
0660	315	11070 SAW-CUT ASPH CONC NS SAW CUT FULL DEPTH	3,770.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001

CONSTRUCTION BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	502	12020 STD. CURB CG-2	945.000 LF	_____	_____	_____	_____
0680	502	12022 RADIAL CURB CG-2	170.000 LF	_____	_____	_____	_____
0690	502	12600 STD. COMB. CURB & GUTTER CG-6	5,153.000 LF	_____	_____	_____	_____
0700	502	12610 RADIAL COMB. CURB & GUTTER CG-6	1,650.000 LF	_____	_____	_____	_____
0710	502	12940 ENTRANCE GUTTER CG-9D	1,314.000 SY	_____	_____	_____	_____
0720	504	13108 CG-12 DETECTABLE WARNING SURFACE	19.000 SY	_____	_____	_____	_____
0730	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	3,005.000 SY	_____	_____	_____	_____
0740	ATTD	13224 EXPOSED AGGR. SIDEWALK 4"	32.000 SY	_____	_____	_____	_____
0750	507	22643 FENCE FE-CL	1,163.000 LF	_____	_____	_____	_____
0760	507	22653 LINE BRACE UNIT FE-CL	22.000 EA	_____	_____	_____	_____
0770	507	22663 CORNER BRACE UNIT FE-CL	22.000 EA	_____	_____	_____	_____
0780	507	22677 GATE FE-CL L=14'	2.000 EA	_____	_____	_____	_____
0790	511	24100 ALLAYING DUST	7,200.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001 CONSTRUCTION BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	512	24160 TEMPORARY (CONSTRUCTION) SIGN	724.000 SF	_____	_____	_____	_____
0810	512	24260 CR. RUN AGGR. NO. 25 OR 26	410.000 TON	_____	_____	_____	_____
0820	512	24272 TRUCK MOUNTED ATTENUATOR	7,200.000 HR	_____	_____	_____	_____
0830	512	24278 GROUP 2 CHANNELIZING DEVICES	152,640.000 DAY	_____	_____	_____	_____
0840	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	672.000 HR	_____	_____	_____	_____
0850	512	24281 ELECTRONIC ARROW BOARD	14,400.000 HR	_____	_____	_____	_____
0860	512	24282 FLAGGER SERVICE	14,400.000 HR	_____	_____	_____	_____
0870	508	24400 OBSCURING ROADWAY	44.700 UNIT	_____	_____	_____	_____
0880	508	24420 DEMOLITION OF PAVEMENT RIGID	306.000 SY	_____	_____	_____	_____
0890	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	13,408.000 SY	_____	_____	_____	_____
0900	510	24831 ADJUST EXIST.DROP INLET adjust exist. drop inlet	3.000 EA	_____	_____	_____	_____
0910	514	25505 FIELD OFFICE TY.I	24.000 MO	_____	_____	_____	_____
0920	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01 Oversight/State Project No.: (NFO)U000-116-152, C501
 Order No.: N85 Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001 CONSTRUCTION BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	ATTD	25567 PROGRESS SCHEDULE UPDATES	27.000 EA	_____	_____	_____	_____
0940	414	26117 DRY RIPRAP CL. AI	20.000 TON	_____	_____	_____	_____
0950	414	26239 DRY RIPRAP CL.II 38"	108.000 TON	_____	_____	_____	_____
0960	602	27022 TOPSOIL CLASS B 2"	2.600 ACRE	_____	_____	_____	_____
0970	603	27101 TEMPORARY SEED	260.000 LB	_____	_____	_____	_____
0980	603	27102 REGULAR SEED	672.000 LB	_____	_____	_____	_____
0990	603	27103 OVERSEEDING	537.000 LB	_____	_____	_____	_____
1000	603	27104 LEGUME SEED	3.000 LB	_____	_____	_____	_____
1010	603	27105 LEGUME OVERSEEDING	2.000 LB	_____	_____	_____	_____
1020	603	27230 FERTILIZER (NITROGEN - N)	236.000 LB	_____	_____	_____	_____
1030	603	27231 FERTILIZER (PHOSPHOROUS - P)	326.000 LB	_____	_____	_____	_____
1040	603	27232 FERTILIZER (POTASSIUM - K)	163.000 LB	_____	_____	_____	_____
1050	603	27250 LIME	11.140 TON	_____	_____	_____	_____
1060	303	27284 EROSION CONTROL MULCH	27,346.410 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001

CONSTRUCTION BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1070	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	201.000 SY	_____	_____	_____	_____
1080	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	1,091.000 SY	_____	_____	_____	_____
1090	606	27326 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 2	5.000 SY	_____	_____	_____	_____
1100	303	27410 CHECK DAM, ROCK TY. I	9.000 EA	_____	_____	_____	_____
1110	303	27415 CHECK DAM(ROCK) TY. II	84.000 EA	_____	_____	_____	_____
1120	303	27422 DEWATERING BASIN EC-8	3.000 EA	_____	_____	_____	_____
1130	303	27430 SILTATION CONTROL EXCAVATION	1,112.000 CY	_____	_____	_____	_____
1140	303	27451 INLET PROTECTION TYPE A	7.000 EA	_____	_____	_____	_____
1150	303	27461 INLET PROTECTION TYPE B	61.000 EA	_____	_____	_____	_____
1160	303	27505 TEMP. SILT FENCE TYPE A	4,008.000 LF	_____	_____	_____	_____
1170	ATTD	27548 STORM WATER MANAGEMENT CONSTRUCTION RECORD DOCUMENTS	LUMP SUM	LUMP SUM	_____	_____	_____
1180	302	27560 STORM WATER MANAGEMENT RISER PIPE 36"	8.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001

CONSTRUCTION BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1190	302	27568 STORM WATER MANAGEMENT RISER PIPE 60"	6.000 LF	_____	_____	_____	_____
1200	520	40002 3/4" WATER SERVICE LINE	1,181.000 LF	_____	_____	_____	_____
1210	520	40003 1" WATER SERVICE LINE	602.000 LF	_____	_____	_____	_____
1220	520	40061 6" DI WATER MAIN	433.000 LF	_____	_____	_____	_____
1230	520	40081 8" DI WATER MAIN	1,250.000 LF	_____	_____	_____	_____
1240	520	40121 12" DI WATER MAIN	3,753.000 LF	_____	_____	_____	_____
1250	520	41006 6" GATE VALVE & BOX	7.000 EA	_____	_____	_____	_____
1260	520	41008 8" GATE VALVE & BOX	11.000 EA	_____	_____	_____	_____
1270	520	41012 12" GATE VALVE & BOX	10.000 EA	_____	_____	_____	_____
1280	520	41820 FIRE HYDRANT	6.000 EA	_____	_____	_____	_____
1290	520	41840 2" AIR RELEASE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1300	520	41970 5/8" WATER METER & BOX	28.000 EA	_____	_____	_____	_____
1310	520	41971 3/4" WATER METER & BOX	6.000 EA	_____	_____	_____	_____
1320	PLAN	41981 WATER FACILITIES 24" STEEL ENCASEMENT PIPE	41.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001

CONSTRUCTION BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1330	520	42044 4" SANITARY SERVICE LATERAL CONNECTION	206.000 LF	_____	_____	_____	_____
1340	520	42060 6" SAN. SEWER PIPE	79.000 LF	_____	_____	_____	_____
1350	520	42080 8" SAN. SEWER PIPE	958.000 LF	_____	_____	_____	_____
1360	520	42087 8" SANITARY SEWER FORCE MAIN	101.000 LF	_____	_____	_____	_____
1370	520	42107 10" SANITARY SEWER FORCE MAIN	649.000 LF	_____	_____	_____	_____
1380	520	42127 12" SANITARY SEWER FORCE MAIN	516.000 LF	_____	_____	_____	_____
1390	520	42610 10" VALVE & BOX FORCE MAIN	2.000 EA	_____	_____	_____	_____
1400	520	42755 SANITARY SEWER MANHOLE	110.000 LF	_____	_____	_____	_____
1410	520	42764 MANHOLE FRAME & COVER F&C-1	20.000 EA	_____	_____	_____	_____
1420	510	42765 ADJUST EXIST FRAME & COVER	10.000 EA	_____	_____	_____	_____
1430	520	42788 2" AIR RELEASE VALVE & BOX FORCE MAIN	1.000 EA	_____	_____	_____	_____
1440	520	42845 4" SEWER CLEANOUT	7.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001 CONSTRUCTION BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1450	PLAN	44300 SEWER UTILITY 20" STEEL ENCASEMENT PIPE	34.000 LF	_____	_____	_____	_____
1460	PLAN	44300 SEWER UTILITY MODIFIED MH-1 or MH-2	24.000 LF	_____	_____	_____	_____
1470	ATTD	45505 CONNECT TO EXIST. A/C PIPE	13.000 EA	_____	_____	_____	_____
1480	ATTD	45506 REMOVE EXIST. A/C PIPE	1,010.000 LF	_____	_____	_____	_____
1490	701	50108 SIGN PANEL	198.750 SF	_____	_____	_____	_____
1500	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	517.000 LF	_____	_____	_____	_____
1510	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	47.000 EA	_____	_____	_____	_____
1520	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	18,061.000 LF	_____	_____	_____	_____
1530	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	287.000 LF	_____	_____	_____	_____
1540	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	3,900.000 LF	_____	_____	_____	_____
1550	704	54401 PVMT MESSAGE MARK. SCHOOL ZONE	1.000 EA	_____	_____	_____	_____
1560	512	54428 TEMP. PVMT MRKG, TY. A, 4"	15,445.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000090018C01

Oversight/State Project No.: (NFO)U000-116-152, C501

Order No.: N85

Federal Project No.: RSTP-5A27(100)

Contractor: _____

SECTION: 0001

CONSTRUCTION BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1570	512	54440 TEMP. PVMT MRKG, TY. A, 24"	309.000 LF	_____	_____	_____	_____
1580	512	54512 TYPE D, CLASS II TEMP. PVMT MRKG 4"	400.000 LF	_____	_____	_____	_____
1590	512	54532 TEMP PVMT MRKG SCHOOL ZONE	1.000 EA	_____	_____	_____	_____
1600	704	54571 PVMT SYMB MRKG (THRU ARROW) TY B, CL I	10.000 EA	_____	_____	_____	_____
1610	704	54597 PVMT SYMB MRKG (FISH HOOK, LEFT) TY B, CL I	20.000 EA	_____	_____	_____	_____
1620	704	54659 PVMT SYMB MRKG (HELMETED BICYCLIST) TY B CL I	10.000 EA	_____	_____	_____	_____
1630	509	69007 FLOWABLE BACKFILL	66.000 CY	_____	_____	_____	_____
1640	ATTD	70525 ENVIR. PROTECTION DISPOSAL OF LOW LEVEL PETROLEUM CONTAMINATED SOIL	833.000 TON	_____	_____	_____	_____
1650	ATTD	70525 ENVIR. PROTECTION DISPOSAL OF PETROLEUM CONTAMINATED SOIL	307.000 TON	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____