

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	301	00112 CLEARING AND GRUBBING	4.000 UNIT				
0050	303	00120 REGULAR EXCAVATION	25,730.000 CY				
0060	305	00140 BORROW EXCAVATION	48,415.000 CY				
0070	ATTD	00154 GEOTEXTILE PAVING GEOSYNTHETICS	16,882.000 SY				
0080	ATTD	00154 GEOTEXTILE STABILIZATION GEOSYNTHETICS	1,400.000 SY				
0090	303	00155 GEOTEXTILE EMBANKMENT STABILIZATION	5,915.000 SY				
0100	ATTD	00170 SOIL BIORETENTION MEDIA	1,932.000 CY				
0110	ATTD	00170 SOIL DRY SWALE MEDIA	112.000 CY				
0120	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	34,089.000 SY				
0130	402	00515 TEMPORARY SHEET PILING	1,600.000 SF				

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302 504	00525 CONCRETE CLASS A3 MISC.	33.200 CY	_____	_____	_____	_____
0150	509	00529 FLOWABLE BACKFILL	11.000 CY	_____	_____	_____	_____
0160	302	00574 ENDWALL GRATE & FRAME EW-11A	2.000 EA	_____	_____	_____	_____
0170	501	00588 UNDERDRAIN UD-4	12,175.000 LF	_____	_____	_____	_____
0180	501	00591 CROSSDRAIN CD-2	192.000 LF	_____	_____	_____	_____
0190	501	00595 OUTLET PIPE	828.000 LF	_____	_____	_____	_____
0200	302	00596 ENDWALL EW-12	33.000 EA	_____	_____	_____	_____
0210	302	01150 15" PIPE	120.000 LF	_____	_____	_____	_____
0220	302	01180 18" PIPE	272.000 LF	_____	_____	_____	_____
0230	302	01182 18" CONC. PIPE	236.000 LF	_____	_____	_____	_____
0240	302	01186 STORM SEWER PIPE 18"	3,721.000 LF	_____	_____	_____	_____
0250	302	01240 24" PIPE	77.000 LF	_____	_____	_____	_____
0260	302	01241 JACKED & BORED 24" PIPE	185.000 LF	_____	_____	_____	_____
0270	302	01242 24" CONC. PIPE	112.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	302	01246 STORM SEWER PIPE 24"	1,268.000 LF	_____	_____	_____	_____
0290	302	01360 36" PIPE	210.000 LF	_____	_____	_____	_____
0300	302	06150 15" END SECTION ES-1 OR 2	2.000 EA	_____	_____	_____	_____
0310	302	06180 18" END SECTION ES-1 OR 2	10.000 EA	_____	_____	_____	_____
0320	302	06181 18" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0330	302	06240 24" END SECTION ES-1 OR 2	4.000 EA	_____	_____	_____	_____
0340	302	06360 36" END SECTION ES-1 OR 2	2.000 EA	_____	_____	_____	_____
0350	302	06749 DROP INLET DI-2B,L=8'	6.000 EA	_____	_____	_____	_____
0360	302	06750 DROP INLET DI-2B,L=10'	6.000 EA	_____	_____	_____	_____
0370	302	06759 DROP INLET DI-2BB,L=10'	1.000 EA	_____	_____	_____	_____
0380	302	07506 DROP INLET DI-5	4.000 EA	_____	_____	_____	_____
0390	302	07510 DROP INLET DI-7A	15.000 EA	_____	_____	_____	_____
0400	302	07512 DROP INLET DI-7B	2.000 EA	_____	_____	_____	_____
0410	302	08265 DROP INLET DI-10K TY. II,L=14'	8.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	302	09056 MANHOLE MH-1 OR 2	25.000 LF	_____	_____	_____	_____
0430	302	09057 FRAME & COVER MH-1	5.000 EA	_____	_____	_____	_____
0440	302	09066 FRAME & COVER (T-MH-2 FLAT SLAB TOP UNIT)	21.000 EA	_____	_____	_____	_____
0450	414	09149 EROSION CONTROL STONE CLASS A1 EC-1	330.000 SY	_____	_____	_____	_____
0460	306	10027 MANIPULATION 12"	52,865.000 SY	_____	_____	_____	_____
0470	308	10128 AGGR. BASE MATL. TY. I NO. 21B	27,652.000 TON	_____	_____	_____	_____
0480	308 / 309	10251 AGGR. MATERIAL NO. 57 STONE	1,861.000 CY	_____	_____	_____	_____
0490	315	10610 ASPHALT CONCRETE TY. IM- 19.0A	19,051.000 TON	_____	_____	_____	_____
0500	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	64,253.000 SY	_____	_____	_____	_____
0510	515	10629 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	1,232.000 SY	_____	_____	_____	_____
0520	315	10636 ASPHALT CONC.TY. SM-9.5D	10,270.000 TON	_____	_____	_____	_____
0530	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	9,882.000 TON	_____	_____	_____	_____
0540	315	10700 RUMBLE STRIP, ASPHALT	12,486.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0550	315	10701 LIQUID ASPHALT RUMBLE STRIP COATING	2,313.000 SY	_____	_____	_____	_____
0560	316	10791 PLAIN HYDRAULIC CEMENT CONC. PAVE. 9"	73.000 SY	_____	_____	_____	_____
0570	315	11070 SAW-CUT ASPH CONC ..	30,550.000 LF	_____	_____	_____	_____
0580	316	11071 SAW-CUT HYD.CEM.CON.PAV ..	2,185.000 LF	_____	_____	_____	_____
0590	502	12322 ASPHALT CONC. CURB TY. MC-3B	1,793.000 LF	_____	_____	_____	_____
0600	315	12505 ASPHALT CONCRETE, CURB BACKUP MATERIAL	107.000 TON	_____	_____	_____	_____
0610	505	13280 GUARDRAIL GR-MGS1	9,237.500 LF	_____	_____	_____	_____
0620	505	13281 GUARDRAIL GR-MGS1A	1,750.500 LF	_____	_____	_____	_____
0630	505	13286 GUARDRAIL TERMINAL GR-MGS2	22.000 EA	_____	_____	_____	_____
0640	505	13287 GUARDRAIL END ANCHORAGE GR-MGS3	19.000 EA	_____	_____	_____	_____
0650	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	17.000 EA	_____	_____	_____	_____
0660	505	13355 GUARDRAIL GR-10	75.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	505	13392 FIXED OBJECT ATTACH. GR-FOA-2 TY. I	9.000 EA	_____	_____	_____	_____
0680	505	13393 FIXED OBJECT ATTACH. GR-FOA-2 TY. II	6.000 EA	_____	_____	_____	_____
0690	505	13401 GUARDRAIL (FOA-CZ)	1.000 EA	_____	_____	_____	_____
0700	502	13461 MEDIAN BARRIER MB-7E	140.000 LF	_____	_____	_____	_____
0710	502	13462 MEDIAN BARRIER MB-7F	16.000 LF	_____	_____	_____	_____
0720	505	13607 IMPACT ATTEN. TL-3,>=40 MPH DES.SP.	25.000 EA	_____	_____	_____	_____
0730	502	21110 MEDIAN STRIP MS-1A	457.000 SY	_____	_____	_____	_____
0740	502	21215 MEDIAN STRIP MS-2	1,169.000 LF	_____	_____	_____	_____
0750	511	24100 ALLAYING DUST	2,000.000 HR	_____	_____	_____	_____
0760	512	24152 TYPE 3 BARRICADE 8'	44.000 EA	_____	_____	_____	_____
0770	512	24160 TEMPORARY (CONSTRUCTION) SIGN	3,933.000 SF	_____	_____	_____	_____
0780	512	24260 CR. RUN AGGR. NO. 25 OR 26	364.000 TON	_____	_____	_____	_____
0790	512	24272 TRUCK MOUNTED ATTENUATOR	5,800.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	512	24278 GROUP 2 CHANNELIZING DEVICES	203,492.000 DAY	_____	_____	_____	_____
0810	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	4,800.000 HR	_____	_____	_____	_____
0820	512	24281 ELECTRONIC ARROW BOARD	2,700.000 HR	_____	_____	_____	_____
0830	512	24282 FLAGGER SERVICE	1,800.000 HR	_____	_____	_____	_____
0840	512	24293 TRAFFIC BARR. SERVICE CONC. DOUBLE FACE	52,658.000 LF	_____	_____	_____	_____
0850	512	24293 TRAFFIC BARR. SERVICE CONC. SIGNLE FACE	700.000 LF	_____	_____	_____	_____
0860	512	24330 TRAFFIC CONTROL TUBULAR MARKERS	50.000 EA	_____	_____	_____	_____
0870	508	24400 OBSCURING ROADWAY	108.800 UNIT	_____	_____	_____	_____
0880	508	24410 DEMOLITION OF PAVEMENT COMBINATION	1,074.000 SY	_____	_____	_____	_____
0890	508	24420 DEMOLITION OF PAVEMENT RIGID	4,323.000 SY	_____	_____	_____	_____
0900	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	42,890.000 SY	_____	_____	_____	_____
0910	505	24600 REMOVE EXISTING GUARDRAIL	18,190.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0920	510	24831 ADJUST EXIST.DROP INLET ..	2.000 EA	_____	_____	_____	_____
0930	514	25505 FIELD OFFICE TY.I	26.000 MO	_____	_____	_____	_____
0940	ATTD	25561 FORMAL PARTNERING	26.000 DAY	_____	_____	_____	_____
0950	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____
0960	ATTD	25567 PROGRESS SCHEDULE UPDATES	24.000 EA	_____	_____	_____	_____
0970	602	27022 TOPSOIL CLASS B 2"	15.600 ACRE	_____	_____	_____	_____
0980	603	27101 TEMPORARY SEED	1,560.000 LB	_____	_____	_____	_____
0990	603	27102 REGULAR SEED	2,243.000 LB	_____	_____	_____	_____
1000	603	27103 OVERSEEDING	1,794.000 LB	_____	_____	_____	_____
1010	603	27104 LEGUME SEED	173.000 LB	_____	_____	_____	_____
1020	603	27105 LEGUME OVERSEEDING	138.000 LB	_____	_____	_____	_____
1030	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	83,490.000 SY	_____	_____	_____	_____
1040	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	75,504.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1050	603	27113 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	10,890.000 SY	_____	_____	_____	_____
1060	603	27230 FERTILIZER NITROGEN - N	1,543.000 LB	_____	_____	_____	_____
1070	603	27231 FERTILIZER PHOSPHOROUS - P	2,105.000 LB	_____	_____	_____	_____
1080	603	27232 FERTILIZER POTASSIUM - K	1,053.000 LB	_____	_____	_____	_____
1090	603	27250 LIME	149.000 TON	_____	_____	_____	_____
1100	606	27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	22,136.000 SY	_____	_____	_____	_____
1110	303	27410 CHECK DAM, ROCK TY. I	5.000 EA	_____	_____	_____	_____
1120	303	27415 CHECK DAM ROCK TY. II	123.000 EA	_____	_____	_____	_____
1130	303	27422 DEWATERING BASIN EC-8	8.000 EA	_____	_____	_____	_____
1140	303	27430 SILTATION CONTROL EXCAVATION	5,230.000 CY	_____	_____	_____	_____
1150	303	27451 INLET PROTECTION TYPE A	34.000 EA	_____	_____	_____	_____
1160	303	27461 INLET PROTECTION TYPE B	45.000 EA	_____	_____	_____	_____
1170	303	27500 GEOTEXTILE FABRIC	330.000 SY	_____	_____	_____	_____
1180	303	27505 TEMP. SILT FENCE TYPE A	24,656.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1190	303	27544 STORM WATER MGT. (ML OR CL TYPE MATERIAL)	1,257.000 CY	_____	_____	_____	_____
1200	303	27545 STORM WATER MANAGEMENT BASIN EXCAVATION	4,369.000 CY	_____	_____	_____	_____
1210	ATTD	27548 STORM WATER MANAGEMENT CONSTRUCTION RECORD DOCUMENTS	LUMP SUM	LUMP SUM	_____	_____	_____
1220	302	27550 STORM WATER MANAGEMENT DRAINAGE STR. SWM-1	14.000 LF	_____	_____	_____	_____
1230	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	590.000 CY	_____	_____	_____	_____
1240	605	28805 BED PREPARATION	157.000 UNIT	_____	_____	_____	_____
1250	605	28810 MULCHING	4.000 CY	_____	_____	_____	_____
1260	605	28811 REMULCHING	15.000 CY	_____	_____	_____	_____
1270	605	38900 PLANT OR TREE DAYLILY MARY'S GOLD	345.000 EA	_____	_____	_____	_____
1280	605	38900 PLANT OR TREE GOLD COAST JUNIPER	28.000 EA	_____	_____	_____	_____
1290	605	38900 PLANT OR TREE GREY OWL JUNIPER	58.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1300	605	38900 PLANT OR TREE GULF STREAM NADINA	138.000 EA	_____	_____	_____	_____
1310	605	38900 PLANT OR TREE IMPROVED MT. HOOD DAFFADIL	1,600.000 EA	_____	_____	_____	_____
1320	605	38900 PLANT OR TREE NATCHEZ CREPE MYRTLE	5.000 EA	_____	_____	_____	_____
1330	605	38900 PLANT OR TREE TUSKEGEE CREPE MYRTLE	40.000 EA	_____	_____	_____	_____
1340	605	38900 PLANT OR TREE WALKER'S LOW CATMINT	345.000 EA	_____	_____	_____	_____
1350	605	38900 PLANT OR TREE WINTER JASMINE	498.000 EA	_____	_____	_____	_____
1360	ATTD	38905 IRRIGATION (OBSERVATION WELL)	13.000 EA	_____	_____	_____	_____
1370	ATTD	39004 SEED MIXTURE (NATIVE SEED)	70.000 LB	_____	_____	_____	_____
1380	ATTD	39004 SEED MIXTURE (OVER SEEDING NATIVE SEED MIX)	112.000 LB	_____	_____	_____	_____
1390	701	50108 SIGN PANEL	5,816.000 SF	_____	_____	_____	_____
1400	700	50381 SIGN STRUCTURE, OVERHEAD SPAN 65'	1.000 EA	_____	_____	_____	_____
1410	700	50412 VIA SIGN POST, W12 X 16	360.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1420	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	3,560.000 LF	_____	_____	_____	_____
1430	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	183.000 EA	_____	_____	_____	_____
1440	700	50532 CONC. SIGN FOUND., SSP-VI A 3'0" DIA. X 8' DEPTH	18.000 EA	_____	_____	_____	_____
1450	700	50575 CONC. FOUND. O/H SIGN STRUCTURE	15.000 CY	_____	_____	_____	_____
1460	510	50600 REMOVE TY.I SIGNS	159.000 EA	_____	_____	_____	_____
1470	ATTD	50620 REPLACE WITH SIGN TY. SP-1 ON O/H STR.	22.000 EA	_____	_____	_____	_____
1480	ATTD	50702 REMOVE, SALVAGE O/H STR. & LGTS. TY. CS-1	1.000 EA	_____	_____	_____	_____
1490	ATTD	50704 REMOVE, SALVAGE O/H STR. & LGTS. TY.CD-1	3.000 EA	_____	_____	_____	_____
1500	ATTD	50707 REMOVE, SALVAGE O/H STR. & LGTS. TY. BM	2.000 EA	_____	_____	_____	_____
1510	ATTD	50860 REMOVE-DISPOSE SIGN STRUCT. TY. I	89.000 EA	_____	_____	_____	_____
1520	ATTD	50864 REMOVE-DISPOSE SIGN STRUCT. TY. VI A	3.000 EA	_____	_____	_____	_____
1530	ATTD	50865 REMOVE-DISPOSE SIGN STRUCT. TY. VIA 3	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1540	ATTD	50867 REMOVE-DISPOSE SIGN STRUCT. TY. WP-1	7.000 EA	_____	_____	_____	_____
1550	ATTD	50868 REMOVE-DISPOSE SIGN STRUCT. TY. WP-2	4.000 EA	_____	_____	_____	_____
1560	ATTD	50881 REMOVE, DISPOSE SIGN TY.SP-1 FROM O/H STR.	33.000 EA	_____	_____	_____	_____
1570	700	51170 ELECTRICAL SERVICE SE-5	2.000 EA	_____	_____	_____	_____
1580	703	51184 TRAFFIC SIGNAL HEAD SECTION 12" LED	51.000 EA	_____	_____	_____	_____
1590	700	51238 CONCRETE FOUNDATION SIGNAL POLE PF-8	39.000 CY	_____	_____	_____	_____
1600	700	51475 SIGNAL MAST ARM POLE MP-3, TYPE A	1.000 EA	_____	_____	_____	_____
1610	700	51476 SIGNAL MAST ARM POLE MP-3, TYPE B1	2.000 EA	_____	_____	_____	_____
1620	700	51478 SIGNAL MAST ARM POLE MP-3, TYPE C	1.000 EA	_____	_____	_____	_____
1630	700	51487 MAST ARM 49'	5.000 EA	_____	_____	_____	_____
1640	700	51488 MAST ARM 60'	4.000 EA	_____	_____	_____	_____
1650	700	51489 MAST ARM 65'	2.000 EA	_____	_____	_____	_____
1660	703	51508 VIDEO DETECTION CABLE	2,325.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1670	703	51523 EVP DETECTION SYSTEM 3-WAY	2.000 EA	_____	_____	_____	_____
1680	703	51525 EVP DETECTOR CABLE	500.000 LF	_____	_____	_____	_____
1690	703	51541 DETECTOR VIDEO DETECTION SYSTEM (360 DEGREE)	2.000 EA	_____	_____	_____	_____
1700	700	51607 14/7 CONDUCTOR CABLE	2,185.000 LF	_____	_____	_____	_____
1710	703	51840 HANGER ASSEMBLY SM-3, IN-LINE (SIGNAL HEADS)	12.000 EA	_____	_____	_____	_____
1720	703	51840 HANGER ASSEMBLY SMD-2 (SIGNS)	12.000 EA	_____	_____	_____	_____
1730	703	51994 UNINTERRUPTIBLE POWER SUPPLY TYPE 2	2.000 EA	_____	_____	_____	_____
1740	703	51995 UNINTERRUPTIBLE POWER SUPPLY BATTERY PACK	2.000 EA	_____	_____	_____	_____
1750	ATTD	52002 TRAFFIC SIGNALIZATION ATC CABINET-COMBINATION CONFIGURATION (16 OUTPUTS)	2.000 EA	_____	_____	_____	_____
1760	700	52002 TRAFFIC SIGNALIZATION CONC. FOUNDATION (CF-5)	2.000 EA	_____	_____	_____	_____
1770	ATTD	52002 TRAFFIC SIGNALIZATION REPEATER BOARD ASSEMBLE	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1780	ATTD	52002 TRAFFIC SIGNALIZATION SNMP/HTTP EXTERNAL ADAPTER	2.000 EA	_____	_____	_____	_____
1790	704	54020 TYPE A PVMT LINE MRKG 4"	11,129.000 LF	_____	_____	_____	_____
1800	704	54022 TYPE A PVMT LINE MRKG 6"	38,189.000 LF	_____	_____	_____	_____
1810	704	54028 TYPE A PAVEMENT LINE MRKG 24"	410.000 LF	_____	_____	_____	_____
1820	704	54076 TYPE B CLASS VI PVMT LINE MRKG 6"	52,400.000 LF	_____	_____	_____	_____
1830	704	54077 TYPE B CLASS VI PVMT LINE MRKG 8"	750.000 LF	_____	_____	_____	_____
1840	704	54078 TYPE B CLASS VI PVMT LINE MRKG 12"	775.000 LF	_____	_____	_____	_____
1850	704	54100 PAVEMENT MARKING 6" CONTRAST 30'-10' SKIP	165.000 LF	_____	_____	_____	_____
1860	704	54100 PAVEMENT MARKING CONSTR. PAVE. MARK. TY. B. CL VI 6"	880.000 LF	_____	_____	_____	_____
1870	704	54100 PAVEMENT MARKING PERM. (TY B, CL VI, 3' LONG 9' SKIP) 6" WIDE	774.000 LF	_____	_____	_____	_____
1880	704	54100 PAVEMENT MARKING TY. B CL VI 3' LONG, 9' SKIP 6" CONTRAST BRIDGE MARKING WHITE	695.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1890	704	54100 PAVEMENT MARKING TY. B, CLASS VI PVMT LINE MRKG 10'-30' SKIP	4,645.000 LF	_____	_____	_____	_____
1900	704	54100 PAVEMENT MARKING TY. B, CLASS VI PVMT LINE MRKG 2'-4' SKIP	504.000 LF	_____	_____	_____	_____
1910	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	203,574.000 LF	_____	_____	_____	_____
1920	704	54217 SNOW PLOW. RAISED PAVE. MARKER ASPH.CONC	4,420.000 EA	_____	_____	_____	_____
1930	704	54400 PVMT MESSAGE MARK. ONLY	15.000 EA	_____	_____	_____	_____
1940	704	54404 PVMT MESSAGE MARK. R/R CROSSING	2.000 EA	_____	_____	_____	_____
1950	512	54432 TEMP. PVMT MRKG, TY. A, 8"	282,082.000 LF	_____	_____	_____	_____
1960	512	54459 TEMP. PVMT SYMBOL MRKG RAILROAD CROSSING TY. A	28.000 EA	_____	_____	_____	_____
1970	512	54526 TEMP PVMT MRKG TY.D DBL ARROW, THRU / RT	4.000 EA	_____	_____	_____	_____
1980	512	54526 TEMP PVMT MRKG TY.D SNG ARROW LEFT	8.000 EA	_____	_____	_____	_____
1990	512	54526 TEMP PVMT MRKG TY.D SNG ARROW RIGHT	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2000	704	54571 PVMT SYMB MRKG THRU ARROW TY B, CL I	3.000 EA	_____	_____	_____	_____
2010	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	19.000 EA	_____	_____	_____	_____
2020	700	55080 8 CONDUCTOR CABLE	430.000 LF	_____	_____	_____	_____
2030	700	55385 ELECTRICAL SERVICE WORK PAD	2.000 EA	_____	_____	_____	_____
2040	700	55587 JUNCTION BOX JB-S2	16.000 EA	_____	_____	_____	_____
2050	700	55588 JUNCTION BOX JB-S3	7.000 EA	_____	_____	_____	_____
2060	700	56014 ELECT. SER. GRD. ELECTRODE 10'	10.000 EA	_____	_____	_____	_____
2070	700	56050 BORED CONDUIT 2"	75.000 LF	_____	_____	_____	_____
2080	700	56051 BORED CONDUIT 3"	592.000 LF	_____	_____	_____	_____
2090	700	56053 2" PVC CONDUIT	363.000 LF	_____	_____	_____	_____
2100	700	56054 3" PVC CONDUIT	543.000 LF	_____	_____	_____	_____
2110	700	56055 4" PVC CONDUIT	20.000 LF	_____	_____	_____	_____
2120	700	56200 TRENCH EXCAVATION ECI-1	4,150.000 LF	_____	_____	_____	_____
2130	700	56205 TEST BORE	5.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2140	808	57202 FIBER OPTIC CABLE 96 STRAND	3,300.000 LF	_____	_____	_____	_____
2150	808	57204 PRE-TERMINATED FIBER PATCH PANEL	2.000 EA	_____	_____	_____	_____
2160	808	57210 UNDERGROUND SPLICE ENCLOSURE	2.000 EA	_____	_____	_____	_____
2170	809	57221 MANAGED FIELD ETHERNET SWITCH Gbps	2.000 EA	_____	_____	_____	_____
2180	809	57227 DISTRIBUTION SFP MODULE 1Gbps, LC, AND SHORT HAUL	3.000 EA	_____	_____	_____	_____
2190	812	57351 BORED ITS CONDUIT HDPE 2"	1,100.000 LF	_____	_____	_____	_____
2200	812	57361 ITS CONDUIT HDPE 2"	2,450.000 LF	_____	_____	_____	_____
2210	700	59071 COMMUNICATION EQUIP. CAT. 6 OUTDOOR CABLE	500.000 LF	_____	_____	_____	_____
2220	404	60411 CONC. CLASS A4 MOD. LIGHTWEIGHT LOW SHRINKAGE	643.600 CY	_____	_____	_____	_____
2230	ATTD	60420 CONCRETE ULTRA-HIGH PERFORMANCE CONCRETE (UHPC) - LONGITUDINAL JOINT & PIER CLOSURE	52.600 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2240	ATTD	60420 CONCRETE ULTRA-HIGH PERFORMANCE CONCRETE (UHPC) - PIER CLOSURE DIAPHRAGM	45.300 CY	_____	_____	_____	_____
2250	316	60450 CONC. CLASS A4 BRIDGE APPR. SLAB	363.900 CY	_____	_____	_____	_____
2260	316	60452 REINF. STEEL BRIDGE APPR. SLAB	55,100.000 LB	_____	_____	_____	_____
2270	404	60490 BRIDGE DECK GROOVING	3,060.000 SY	_____	_____	_____	_____
2280	406	61713 CORROSION RESISTANT REINF. STEEL CL. III	227,960.000 LB	_____	_____	_____	_____
2290	407	61812 STR. STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM	_____	_____	_____
2300	ATTD	62004 ARCHITECTURAL TREATMENT	260.000 SY	_____	_____	_____	_____
2310	410	62010 CONCRETE PARAPET	452.000 LF	_____	_____	_____	_____
2320	410	62056 BRIDGE MEDIAN BARRIER CAST-IN-PLACE CONCRETE F-SHAPE	200.000 LF	_____	_____	_____	_____
2330	420	62418 ADHESIVE BASED JOINT SEALER CLASS II, 2"	293.800 LF	_____	_____	_____	_____
2340	401	64011 STRUCTURE EXCAVATION	1,623.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000097565B18

Oversight/State Project No.: 0064-043-744,C501,B618

Order No.: N75

Federal Project No.: STP-0643(513)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2350	401	64015 SELECT BACKFILL ABUTMENT ZONE	3,461.000 TON	_____	_____	_____	_____
2360	401	64032 GEOCOMPOSITE WALL DRAIN	182.000 SY	_____	_____	_____	_____
2370	401	64036 PIPE UNDERDRAIN 6"	310.000 LF	_____	_____	_____	_____
2380	403	64102 DYNAMIC PILE TEST END BEARING PILES	3.000 EA	_____	_____	_____	_____
2390	403	64775 PILE POINT FOR 14" STEEL PILE	116.000 EA	_____	_____	_____	_____
2400	403	64778 DRIVING TEST FOR 14" STEEL PILE	170.000 LF	_____	_____	_____	_____
2410	403	64875 PILE STEEL 14" 42'-6"	2,508.000 LF	_____	_____	_____	_____
2420	403	64875 PILE STEEL 14" 66'-6"	1,789.000 LF	_____	_____	_____	_____
2430	403	64875 PILE STEEL 14" 61'-3"	1,654.000 LF	_____	_____	_____	_____
2440	ATTD	64901 RETAINING STRUCTURE (MSE WALL OR EQUIVALENT)	7,764.000 SF	_____	_____	_____	_____
2450	404	65013 CONCRETE CLASS A3	593.800 CY	_____	_____	_____	_____
2460	406	65200 REINF. STEEL	13,040.000 LB	_____	_____	_____	_____

Total Bid: _____.