

Schedule of Items

Proposal ID: C0000094724B01

Oversight/State Project No.: (NFO)0122-033-733,C501,B614

Order No.: N92

Federal Project No.: STP-033-2(049)

Contractor: _____

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	32,272.000 CY				
0050	302 504	00525 CONCRETE CLASS A3 MISC.	5.000 CY				
0060	509	00529 FLOWABLE BACKFILL	5.000 CY				
0070	ATTD	00536 CONCRETE A3 MISC	3.000 CY				
0080	302 406	00540 REINF. STEEL	680.000 LB				
0090	501	00591 CROSSDRAIN CD-2	25.000 LF				
0100	501	00595 OUTLET PIPE	11.000 LF				
0110	302	00596 ENDWALL EW-12	1.000 EA				
0120	302	01156 STORM SEWER PIPE 15"	62.000 LF				
0130	302	01186 STORM SEWER PIPE 18"	68.000 LF				
0140	302	01246 STORM SEWER PIPE 24"	94.000 LF				

Schedule of Items

Proposal ID: C0000094724B01

Oversight/State Project No.: (NFO)0122-033-733,C501,B614

Order No.: N92

Federal Project No.: STP-033-2(049)

Contractor: _____

SECTION: 0001

ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	06150 15" END SECTION ES-1 OR 2	4.000 EA	_____	_____	_____	_____
0160	302	09056 MANHOLE MH-1 OR 2	10.000 LF	_____	_____	_____	_____
0170	302	09057 FRAME & COVER MH-1	1.000 EA	_____	_____	_____	_____
0180	502	09125 ENERGY DISSIPATOR EG-1	1.000 EA	_____	_____	_____	_____
0190	414	09151 EROSION CONTROL STONE CLASS I, EC-1	137.000 SY	_____	_____	_____	_____
0200	502	09225 PAVED FLUME PG-4	22.000 SY	_____	_____	_____	_____
0210	502	09248 DITCH FLUME CONNECTOR PG-7	1.000 EA	_____	_____	_____	_____
0220	303	09250 SLOPE DRAIN	4.000 EA	_____	_____	_____	_____
0230	308	10128 AGGR. BASE MATL. TY. I NO. 21B	2,766.000 TON	_____	_____	_____	_____
0240	315	10610 ASPHALT CONCRETE TY. IM- 19.0A	797.000 TON	_____	_____	_____	_____
0250	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	950.000 TON	_____	_____	_____	_____
0260	315	10700 RUMBLE STRIP, ASPHALT	3,197.000 LF	_____	_____	_____	_____
0270	315	11070 SAW-CUT ASPH CONC (10" MAXIMUM DEPTH)	773.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000094724B01

Oversight/State Project No.: (NFO)0122-033-733,C501,B614

Order No.: N92

Federal Project No.: STP-033-2(049)

Contractor: _____

SECTION: 0001

ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	502	12322 ASPHALT CONC. CURB TY. MC-3B	35.000 LF	_____	_____	_____	_____
0290	315	12505 ASPHALT CONCRETE, CURB BACKUP MATERIAL	2.000 TON	_____	_____	_____	_____
0300	505	13280 GUARDRAIL GR-MGS1	1,198.000 LF	_____	_____	_____	_____
0310	505	13286 GUARDRAIL TERMINAL GR-MGS2	6.000 EA	_____	_____	_____	_____
0320	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	4.000 EA	_____	_____	_____	_____
0330	505	13383 FIXED OBJECT ATTACH. GR-FOA-1 TY. I	4.000 EA	_____	_____	_____	_____
0340	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	2,400.000 LF	_____	_____	_____	_____
0350	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	7.000 EA	_____	_____	_____	_____
0360	315	16340 ASPHALT CONC. TY. SM-9.5D	545.000 TON	_____	_____	_____	_____
0370	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	936.000 SY	_____	_____	_____	_____
0380	512	17386 GUARDRAIL GUARDRAIL (GR MGS4 SERVICE CONNECTOR)	2.000 EA	_____	_____	_____	_____
0390	512	17386 GUARDRAIL GUARDRAIL (MGS2 SERVICE TERMINAL)	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000094724B01

Oversight/State Project No.: (NFO)0122-033-733,C501,B614

Order No.: N92

Federal Project No.: STP-033-2(049)

Contractor: _____

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	512	24152 TYPE 3 BARRICADE 8'	8.000 EA	_____	_____	_____	_____
0410	512	24160 TEMPORARY (CONSTRUCTION) SIGN	548.000 SF	_____	_____	_____	_____
0420	512	24272 TRUCK MOUNTED ATTENUATOR	16.000 HR	_____	_____	_____	_____
0430	512	24278 GROUP 2 CHANNELIZING DEVICES	3,036.000 DAY	_____	_____	_____	_____
0440	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	10,944.000 HR	_____	_____	_____	_____
0450	512	24282 FLAGGER SERVICE	384.000 HR	_____	_____	_____	_____
0460	508	24410 DEMOLITION OF PAVEMENT COMBINATION	2,176.000 SY	_____	_____	_____	_____
0470	505	24600 REMOVE EXISTING GUARDRAIL	553.000 LF	_____	_____	_____	_____
0480	514	25506 FIELD OFFICE TY.II	24.000 MO	_____	_____	_____	_____
0490	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____
0500	ATTD	25567 PROGRESS SCHEDULE UPDATES	24.000 EA	_____	_____	_____	_____
0510	414	26127 DRY RIPRAP CL.I 26"	60.000 TON	_____	_____	_____	_____
0520	602	27012 TOPSOIL CLASS A 2"	2.500 ACRE	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000094724B01 Oversight/State Project No.: (NFO)0122-033-733,C501,B614
 Order No.: N92 Federal Project No.: STP-033-2(049)

Contractor: _____

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	603	27101 TEMPORARY SEED	243.000 LB	_____	_____	_____	_____
0540	603	27102 REGULAR SEED	412.000 LB	_____	_____	_____	_____
0550	603	27103 OVERSEEDING	329.000 LB	_____	_____	_____	_____
0560	603	27104 LEGUME SEED	91.000 LB	_____	_____	_____	_____
0570	603	27105 LEGUME OVERSEEDING	73.000 LB	_____	_____	_____	_____
0580	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	3,630.000 SY	_____	_____	_____	_____
0590	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	22,893.000 SY	_____	_____	_____	_____
0600	603	27120 SEDIMENT RETENTION ROLL 18" MIN	4,600.000 LF	_____	_____	_____	_____
0610	603	27230 FERTILIZER NITROGEN - N	233.000 LB	_____	_____	_____	_____
0620	603	27231 FERTILIZER PHOSPHOROUS - P	320.000 LB	_____	_____	_____	_____
0630	603	27232 FERTILIZER POTASSIUM - K	260.000 LB	_____	_____	_____	_____
0640	603	27250 LIME	11.000 TON	_____	_____	_____	_____
0650	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	1,604.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000094724B01

Oversight/State Project No.: (NFO)0122-033-733,C501,B614

Order No.: N92

Federal Project No.: STP-033-2(049)

Contractor: _____

SECTION: 0001

ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	606	27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	37.000 SY	_____	_____	_____	_____
0670	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	901.000 SY	_____	_____	_____	_____
0680	303	27345 TEMPORARY DIVERSION DIKE	995.000 LF	_____	_____	_____	_____
0690	303	27415 CHECK DAM ROCK TY. II	45.000 EA	_____	_____	_____	_____
0700	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0710	303	27430 SILTATION CONTROL EXCAVATION	252.000 CY	_____	_____	_____	_____
0720	303	27500 GEOTEXTILE FABRIC	75.000 SY	_____	_____	_____	_____
0730	303	27505 TEMP. SILT FENCE TYPE A	1,350.000 LF	_____	_____	_____	_____
0740	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	623.000 CY	_____	_____	_____	_____
0750	520	40121 12" DI WATER MAIN	270.000 LF	_____	_____	_____	_____
0760	520	40992 WATER UTILITY (12" BLOW- OFF VALVE AND MANHOLE)	2.000 EA	_____	_____	_____	_____
0770	701	50108 SIGN PANEL	23.000 SF	_____	_____	_____	_____
0780	700	50430 SIGN POST STP-1, 2", 14 GAUGE	72.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000094724B01 Oversight/State Project No.: (NFO)0122-033-733,C501,B614
 Order No.: N92 Federal Project No.: STP-033-2(049)

Contractor: _____

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0790	700	50500 CONC. SIGN FOUND., SSP-V A 1' DIA. X 3' DEPTH	9.000 EA	_____	_____	_____	_____
0800	ATTD	50759 RELOC. EXIST. SIGN PANEL TY. SP-1	11.000 EA	_____	_____	_____	_____
0810	ATTD	51963 REMOVE (REMOVE AND DISPOSE GROUND MOUNTED SIGN PANEL)	1.000 EA	_____	_____	_____	_____
0820	ATTD	51963 REMOVE (REMOVE AND DISPOSE GROUND MOUNTED SIGN STRUCTURE)	9.000 EA	_____	_____	_____	_____
0830	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	6,395.000 LF	_____	_____	_____	_____
0840	512	54428 TEMP. PVMT MRKG, TY. A, 4"	5,570.000 LF	_____	_____	_____	_____
0850	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	230.000 CY	_____	_____	_____	_____
0860	316	60450 CONC. CLASS A4 BRIDGE APPR. SLAB	104.200 CY	_____	_____	_____	_____
0870	316	60452 REINF. STEEL BRIDGE APPR. SLAB	14,980.000 LB	_____	_____	_____	_____
0880	404	60490 BRIDGE DECK GROOVING	849.000 SY	_____	_____	_____	_____
0890	406	61712 CORROSION RESISTANT REINF. STEEL CL. II	46,180.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000094724B01

Oversight/State Project No.: (NFO)0122-033-733,C501,B614

Order No.: N92

Federal Project No.: STP-033-2(049)

Contractor: _____

SECTION: 0001

ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0900	407	61812 STR.STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM			
0910	410	62032 RAILING,KANSAS CORRAL 32" W/CURB	599.000 LF				
0920	420	62413 ADHESIVE BASED JOINT SEALER CLASS I, 2-1/2"	76.000 LF				
0930	ATTD	62534 BRIDGE SUPERSTRUCTURE (PLAN ELASTIC INCLUSION (14 INCH))	58.000 SY				
0940	401	64011 STRUCTURE EXCAVATION	425.000 CY				
0950	401	64015 SELECT BACKFILL ABUTMENT ZONE	3,177.000 TON				
0960	PLAN	64038 PREBORING PILE (12" STEEL PIPE)	969.000 LF				
0970	403	64112 STEEL PILES 12"	1,343.000 LF				
0980	ATTD PLAN	64875 PILE (DENSIFIED AGGREGATE PIER)	610.000 LF				
0990	ATTD	64901 RETAINING STRUCTURE (RETAINING STRUCTURE)	8,690.000 SF				
1000	404	65013 CONCRETE CLASS A3	69.600 CY				
1010	406	65200 REINF. STEEL	9,360.000 LB				

Schedule of Items

Proposal ID: C0000094724B01
Order No.: N92

Oversight/State Project No.: (NFO)0122-033-733,C501,B614
Federal Project No.: STP-033-2(049)

Contractor: _____

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1020	401	66120 COFFERDAM	2.000 EA	_____	_____	_____	_____
1030	414	66127 DRY RIPRAP CL.I 26"	629.000 TON	_____	_____	_____	_____
1040	ATTD	66924 BRIDGE SUBSTRUCTURE (LOAD TEST)	4.000 EA	_____	_____	_____	_____
1050	ATTD	66927 BRIDGE SUBSTRUCTURE (PLAN TEMPORARY SHORING)	LUMP SUM	LUMP SUM	_____	_____	_____
1060	ATTD PLAN	67350 WATER LINE (B614)	LUMP SUM	LUMP SUM	_____	_____	_____
1070	413	67900 DISM.& REM. EX. STR. (REMOVE EXISTING STRUCTURE)	LUMP SUM	LUMP SUM	_____	_____	_____
1080	413	67904 BRIDGE INCIDENTALS (REMOVE EXIST. ASBESTOS [STR. NO. 1020])	LUMP SUM	LUMP SUM	_____	_____	_____
1090	413	68476 ENV.& WORK. PROTECTION [STR. NO. 1020]	LUMP SUM	LUMP SUM	_____	_____	_____
1100	413	68492 MATERIAL DISPOSAL (TYPE B [STR. NO. 1020])	LUMP SUM	LUMP SUM	_____	_____	_____
1110	ATTD	70525 ENVIR. PROTECTION (LOW-LEVEL PETROLEUM CONTAMINATED SOIL DISPOSAL)	100.000 TON	_____	_____	_____	_____
1120	ATTD	85016 (OBSTRUCTION REMOVAL)	4.000 HR	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____

Total Bid: _____.