

Schedule of Items

Proposal ID: CM319PMC113226 Oversight/State Project No.: PM3C-963-F19,N501

Order No.: 330

Federal Project No.: PM03369

Contractor: \_\_\_\_\_

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	308	10103 AGGR. MATL. NO. 25 OR 26	2,261.240 TON	_____	_____	_____	_____
0020	310	10417 TACK COAT	21,147.000 GAL	_____	_____	_____	_____
0030	315	10700 RUMBLE STRIP, ASPHALT	15,206.000 LF	_____	_____	_____	_____
0040	ATTD	10706 PAVEMENT SHOULDER WEDGE PREPARATION	25,766.000 LF	_____	_____	_____	_____
0050	315	16340 ASPHALT CONC. TY. SM-9.5D	6,598.510 TON	_____	_____	_____	_____
0060	315	16355 ASPHALT CONC. TY. SM-12.5D	16,700.070 TON	_____	_____	_____	_____
0070	315	16390 ASPH. CONC. TY. BM-25.0A	5,537.660 TON	_____	_____	_____	_____
0080	315	16395 ASPH. CONC. TY. BM-25.0A T	1,889.540 TON	_____	_____	_____	_____
0090	515	16516 FLEXIBLE PAVE. TIE-IN PLANING 0" - 2"	400.000 SY	_____	_____	_____	_____
0100	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	127,548.260 SY	_____	_____	_____	_____
0110	515	16523 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	24,076.800 SY	_____	_____	_____	_____
0120	512 ATTD	24265 MAINTENANCE OF TRAFFIC PM3C	LUMP SUM	LUMP SUM	_____	_____	_____
0130	512	24282 FLAGGER SERVICE	2,900.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM319PMC113226 Oversight/State Project No.: PM3C-963-F19,N501

Order No.: 330

Federal Project No.: PM03369

Contractor: \_\_\_\_\_

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	704	54020 TYPE A PVMT LINE MRKG 4"	108,808.000 LF	_____	_____	_____	_____
0150	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	33,684.000 LF	_____	_____	_____	_____
0160	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	91,390.000 LF	_____	_____	_____	_____
0170	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	150.000 LF	_____	_____	_____	_____
0180	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	100.000 LF	_____	_____	_____	_____
0190	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	86,592.000 LF	_____	_____	_____	_____
0200	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	228.000 SF	_____	_____	_____	_____
0210	704	54217 SNOW PLOW. RAISED PAVE. MARKER ASPH.CONC	382.000 EA	_____	_____	_____	_____
0220	704	54404 PVMT MESSAGE MARK. R/R CROSSING	2.000 EA	_____	_____	_____	_____
0230	512	54428 TEMP. PVMT MRKG, TY. A, 4"	151,566.000 LF	_____	_____	_____	_____
0240	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	4.000 EA	_____	_____	_____	_____
0250	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM319PMC113226 Oversight/State Project No.: PM3C-963-F19,N501

Order No.: 330

Federal Project No.: PM03369

Contractor: \_\_\_\_\_

Section: 0001

Total: \_\_\_\_\_

SECTION: 0002

ALTERNATE ITEM

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	ATTD	00306 SELECT MATERIAL SHOULDER MAINTENANCE MATERIAL	1.000 TON	_____	_____	_____	_____
			Section: 0002	Total:		_____	
				Total Bid:		_____	