

Schedule of Items

Proposal ID: CM619PMK113050    Oversight/State Project No.: (NFO) PM6K-966-F19,P401  
 Order No.: 632    Federal Project No.: PM06398 / HSIP-966-6(090)

Contractor: \_\_\_\_\_

SECTION: 0001                      REGULAR ITEMS

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	40,136.000 GAL	_____	_____	_____	_____
0020	ATTD	10505 PAVEMENT IM-19.0A FOR PATCHING LOCATIONS	1,262.320 TON	_____	_____	_____	_____
0030	315	10700 RUMBLE STRIP, ASPHALT	58,526.000 LF	_____	_____	_____	_____
0040	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	2,185.740 TON	_____	_____	_____	_____
0050	315	16350 ASPHALT CONC. TY. SM- 12.5A	33,968.020 TON	_____	_____	_____	_____
0060	315	16365 ASPHALT CONC. TY. IM-19.0A	7,647.930 TON	_____	_____	_____	_____
0070	315	16373 ASPH. CONC. TY. IM-19.0A T	4,487.640 TON	_____	_____	_____	_____
0080	ATTD	16515 FLEXIBLE PAVE. PLANING MILLING FOR PATCHING LOCATIONS	7,654.000 SY	_____	_____	_____	_____
0090	515	16516 FLEXIBLE PAVE. TIE-IN PLANING 0" - 2"	1,372.800 SY	_____	_____	_____	_____
0100	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	190,265.540 SY	_____	_____	_____	_____
0110	515	16523 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	69,084.730 SY	_____	_____	_____	_____
0120	ATTD	24265 MAINTENANCE OF TRAFFIC MOT	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: CM619PMK113050    Oversight/State Project No.: (NFO) PM6K-966-F19,P401  
 Order No.: 632    Federal Project No.: PM06398 / HSIP-966-6(090)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	24282 FLAGGER SERVICE	1,673.000 HR	_____	_____	_____	_____
0140	704	54020 TYPE A PVMT LINE MRKG 4"	460.000 LF	_____	_____	_____	_____
0150	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	188,152.000 LF	_____	_____	_____	_____
0160	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	129,540.000 LF	_____	_____	_____	_____
0170	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	1,974.000 LF	_____	_____	_____	_____
0180	704	54079 TYPE B CLASS VI CONTRAST PVMT MRKG 4"	700.000 LF	_____	_____	_____	_____
0190	ATTD	54101 PAVEMENT MARKING YIELD TRIANGLE MARKINGS	5.000 EA	_____	_____	_____	_____
0200	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	2,984.000 LF	_____	_____	_____	_____
0210	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	952.000 SF	_____	_____	_____	_____
0220	704	54217 SNOW PLOW. RAISED PAVE. MARKER ASPH.CONC	1,922.000 EA	_____	_____	_____	_____
0230	704	54400 PVMT MESSAGE MARK. ONLY	1.000 EA	_____	_____	_____	_____
0240	704	54401 PVMT MESSAGE MARK. SCHOOL ZONE	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM619PMK113050    Oversight/State Project No.: (NFO) PM6K-966-F19,P401  
 Order No.: 632    Federal Project No.: PM06398 / HSIP-966-6(090)

Contractor: \_\_\_\_\_

SECTION: 0001                      REGULAR ITEMS

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	512	54428 TEMP. PVMT MRKG, TY. A, 4"	316,620.000 LF	_____	_____	_____	_____
0260	704	54571 PVMT SYMB MRKG THRU ARROW TY B, CL I	1.000 EA	_____	_____	_____	_____
0270	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	45.000 EA	_____	_____	_____	_____
0280	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	6.000 EA	_____	_____	_____	_____
0290	704	54589 PVMT SYMB MRKG LANE REDUCTION ARROW TY B, CL I	2.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____

SECTION: 0002                      ALTERNATE ITEM

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0300	ATTD	00306 SELECT MATERIAL SHOULDER MAINTENANCE MATERIAL	1.000 TON	_____	_____	_____	_____
<b>Section: 0002</b>				<b>Total:</b>	_____	_____	_____
				<b>Total Bid:</b>	_____	_____	_____