

Schedule of Items

Proposal ID: C0000088616M01

Oversight/State Project No.: 0772-070-639,M501,B640

Order No.: A96

Federal Project No.: BR-070-2(031)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	303	00125 GRADING	LUMP SUM	LUMP SUM			
0040	305	00140 BORROW EXCAVATION	155.000 CY				
0050	501	00588 UNDERDRAIN UD-4	105.000 LF				
0060	501	00595 OUTLET PIPE	105.000 LF				
0070	302	00596 ENDWALL EW-12	1.000 EA				
0080	302	01180 18" PIPE	94.000 LF				
0090	302	01240 24" PIPE	72.000 LF				
0100	414	09150 EROSION CONTROL STONE CLASS I, EC-1	17.000 TON				
0110	308	10065 AGGR. MATL. NO. 1	103.000 TON				
0120	308	10100 AGGR. MATL. NO. 21B	184.000 TON				
0130	315	10635 ASPHALT CONC.TY. SM-9.5A	45.000 TON				
0140	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	66.000 TON				

Schedule of Items

Proposal ID: C0000088616M01

Oversight/State Project No.: 0772-070-639,M501,B640

Order No.: A96

Federal Project No.: BR-070-2(031)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	502	13244 SAW CUT H.C.C. ITEMS SAW CUT	32.000 LF	_____	_____	_____	_____
0160	505	13349 GUARDRAIL TERMINAL SITE PREPARATION	4.000 EA	_____	_____	_____	_____
0170	505	13383 FIXED OBJECT ATTACH. GR-FOA-1 TY. I	1.000 EA	_____	_____	_____	_____
0180	505	13401 GUARDRAIL GUARDRAIL MB-3 TERMINAL GR-9	1.000 EA	_____	_____	_____	_____
0190	505	13607 IMPACT ATTEN. STD. IA-1, TL-3>=40 MPH DES.SP.	3.000 EA	_____	_____	_____	_____
0200	511	24100 ALLAYING DUST	100.000 HR	_____	_____	_____	_____
0210	512	24152 TYPE 3 BARRICADE 8'	8.000 EA	_____	_____	_____	_____
0220	512	24160 TEMPORARY (CONSTRUCTION) SIGN	700.000 SF	_____	_____	_____	_____
0230	512	24260 CR. RUN AGGR. NO. 25 OR 26	68.000 TON	_____	_____	_____	_____
0240	512	24278 GROUP 2 CHANNELIZING DEVICES	120.000 DAY	_____	_____	_____	_____
0250	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	700.000 HR	_____	_____	_____	_____
0260	512	24282 FLAGGER SERVICE	200.000 HR	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000088616M01

Oversight/State Project No.: 0772-070-639,M501,B640

Order No.: A96

Federal Project No.: BR-070-2(031)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	40.000 LF	_____	_____	_____	_____
0280	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	353.000 SY	_____	_____	_____	_____
0290	514	25506 FIELD OFFICE TY.II	10.000 MO	_____	_____	_____	_____
0300	414	26127 DRY RIPRAP CL.I 26"	402.000 TON	_____	_____	_____	_____
0310	603	27101 TEMPORARY SEED	28.000 LB	_____	_____	_____	_____
0320	603	27102 REGULAR SEED	48.000 LB	_____	_____	_____	_____
0330	603	27103 OVERSEEDING	38.000 LB	_____	_____	_____	_____
0340	603	27104 LEGUME SEED	7.000 LB	_____	_____	_____	_____
0350	603	27105 LEGUME OVERSEEDING	6.000 LB	_____	_____	_____	_____
0360	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	575.000 SY	_____	_____	_____	_____
0370	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,474.000 SY	_____	_____	_____	_____
0380	603	27230 FERTILIZER NITROGEN - N	27.000 LB	_____	_____	_____	_____
0390	603	27231 FERTILIZER PHOSPHOROUS - P	37.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000088616M01

Oversight/State Project No.: 0772-070-639,M501,B640

Order No.: A96

Federal Project No.: BR-070-2(031)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	603	27232 FERTILIZER POTASSIUM - K	18.000 LB	_____	_____	_____	_____
0410	603	27250 LIME	1.260 TON	_____	_____	_____	_____
0420	303	27415 CHECK DAM ROCK TY. II	10.000 EA	_____	_____	_____	_____
0430	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0440	303	27430 SILTATION CONTROL EXCAVATION	45.000 CY	_____	_____	_____	_____
0450	303	27505 TEMP. SILT FENCE TYPE A	220.000 LF	_____	_____	_____	_____
0460	701	50108 SIGN PANEL	30.500 SF	_____	_____	_____	_____
0470	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	36.000 LF	_____	_____	_____	_____
0480	510	50600 REMOVE TY.I SIGNS	13.000 EA	_____	_____	_____	_____
0490	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	54.000 CY	_____	_____	_____	_____
0500	404	60490 BRIDGE DECK GROOVING	195.000 SY	_____	_____	_____	_____
0510	406	61711 CORROSION RESISTANT REINF. STEEL CL. I	10,480.000 LB	_____	_____	_____	_____
0520	407	61812 STR.STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000088616M01

Oversight/State Project No.: 0772-070-639,M501,B640

Order No.: A96

Federal Project No.: BR-070-2(031)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	410	62031 RAILING,KANSAS CORRAL 27" W/OUT CURB	144.000 LF	_____	_____	_____	_____
0540	ATTD	62534 BRIDGE SUPERSTRUCTURE ELASTIC INCLUSION 10" EPS AT BACK WALL OF ABUTMENT B ONLY	6.500 SY	_____	_____	_____	_____
0550	401	64011 STRUCTURE EXCAVATION	577.000 CY	_____	_____	_____	_____
0560	401	64015 SELECT BACKFILL ABUTMENT ZONE	669.000 TON	_____	_____	_____	_____
0570	401	64032 GEOCOMPOSITE WALL DRAIN	81.000 SY	_____	_____	_____	_____
0580	404	65013 CONCRETE CLASS A3	116.000 CY	_____	_____	_____	_____
0590	406	65200 REINF. STEEL	9,540.000 LB	_____	_____	_____	_____
0600	414	66239 DRY RIPRAP CL.II 38"	59.000 TON	_____	_____	_____	_____
0610	413	67900 DISM.& REM. EX. STR. DISMANTLE AND REMOVE EXISTING STRUCTURE NUMBER 6153	LUMP SUM	LUMP SUM	_____	_____	_____
0620	413	68476 ENV.& WORK. PROTECTION ENVIRONMENTAL AND WORKER PROTECTION STRUCTURE 6153	LUMP SUM	LUMP SUM	_____	_____	_____
0630	413	68492 MATERIAL DISPOSAL MATERIAL DISPOSAL STRUCTURE NUMBER 6153	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000088616M01

Oversight/State Project No.: 0772-070-639,M501,B640

Order No.: A96

Federal Project No.: BR-070-2(031)

Contractor: \_\_\_\_\_

Section: 0001

Total: \_\_\_\_\_

Total Bid: \_\_\_\_\_