

Schedule of Items

Proposal ID: C000093087B60

Oversight/State Project No.: 0195-127-599,C501,B660

Order No.: A48

Federal Project No.: NHPP-195-6(025)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	71.000 CY				
0050	303	00150 EMBANKMENT	70.000 CY				
0060	308	10128 AGGR. BASE MATL. TY. I NO. 21B	727.000 TON				
0070	315	10608 ASPHALT CONCRETE TY. SM-12.5D	241.000 TON				
0080	315	10611 ASPHALT CONCRETE TY. IM-19.0D	238.000 TON				
0090	315	10642 ASPHALT CONCRETE TY. BM-25.0A	538.000 TON				
0100	315	11070 SAW-CUT ASPH CONC FULL DEPTH	694.000 LF				
0110	502	12020 STD. CURB CG-2	245.000 LF				
0120	512	13495 TRAF. BARR. SER. CONC. SINGLE FACE PAR.MB-10A	1,362.000 LF				
0130	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	4.000 EA				

Schedule of Items

Proposal ID: C000093087B60

Oversight/State Project No.: 0195-127-599,C501,B660

Order No.: A48

Federal Project No.: NHPP-195-6(025)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	519	13750 SOUND WALL COLOR COATING	1,776.000 SY	_____	_____	_____	_____
0150	519	13752 STR.MOUNTED SOUND BARR.WALL - ABSORPTIVE	8,870.000 SF	_____	_____	_____	_____
0160	502	21020 MEDIAN STRIP MS-1	9.000 SY	_____	_____	_____	_____
0170	502	21215 MEDIAN STRIP MS-2	324.000 LF	_____	_____	_____	_____
0180	512	24150 TYPE 3 BARRICADE 4'	2.000 EA	_____	_____	_____	_____
0190	512	24160 TEMPORARY (CONSTRUCTION) SIGN	1,076.000 SF	_____	_____	_____	_____
0200	512	24272 TRUCK MOUNTED ATTENUATOR	2,160.000 HR	_____	_____	_____	_____
0210	512	24278 GROUP 2 CHANNELIZING DEVICES	31,665.000 DAY	_____	_____	_____	_____
0220	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	71,280.000 HR	_____	_____	_____	_____
0230	512	24281 ELECTRONIC ARROW BOARD	2,160.000 HR	_____	_____	_____	_____
0240	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	620.000 LF	_____	_____	_____	_____
0250	512	24333 TEMPORARY TRAFFIC CONTROL SIGNAL - DETOUR	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C000093087B60

Oversight/State Project No.: 0195-127-599,C501,B660

Order No.: A48

Federal Project No.: NHPP-195-6(025)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	508	24420 DEMOLITION OF PAVEMENT RIGID	33.000 SY	_____	_____	_____	_____
0270	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	1,419.000 SY	_____	_____	_____	_____
0280	510	24500 REMOVE EXIST. MS-1	9.000 SY	_____	_____	_____	_____
0290	510	24502 REMOVE EXIST. AND DISPOSE OF BR. MOUNTED SIGN STRUCTURE	1.000 EA	_____	_____	_____	_____
0300	510	24840 RECONSTRUCT EXIST. REMOVE, SALVAGE, STORE AND RE-INSTALL EXISTING LIGHT POLE AND FIXTURES	1.000 EA	_____	_____	_____	_____
0310	514	25505 FIELD OFFICE TY.I	9.000 MO	_____	_____	_____	_____
0320	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____
0330	ATTD	25567 PROGRESS SCHEDULE UPDATES	13.000 EA	_____	_____	_____	_____
0340	303	27430 SILTATION CONTROL EXCAVATION	127.000 CY	_____	_____	_____	_____
0350	303	27461 INLET PROTECTION TYPE B	4.000 EA	_____	_____	_____	_____
0360	303	27505 TEMP. SILT FENCE TYPE A	628.000 LF	_____	_____	_____	_____
0370	701	50108 SIGN PANEL	50.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000093087B60

Oversight/State Project No.: 0195-127-599,C501,B660

Order No.: A48

Federal Project No.: NHPP-195-6(025)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	700	50412 VIA SIGN POST, W12 X 16	30.000 LF	_____	_____	_____	_____
0390	700	50528 CONC. SIGN FOUND., SSP-VI A 3'0" DIA. X 7' DEPTH	2.000 EA	_____	_____	_____	_____
0400	704	54075 TYPE B CLASS VI PVMT LINE MRKG 4"	62.000 LF	_____	_____	_____	_____
0410	704	54076 TYPE B CLASS VI PVMT LINE MRKG 6"	2,470.000 LF	_____	_____	_____	_____
0420	704	54077 TYPE B CLASS VI PVMT LINE MRKG 8"	619.000 LF	_____	_____	_____	_____
0430	704	54218 SNOW PLOW. RAISED PAVE. MARKER HYD. CONC	12.000 EA	_____	_____	_____	_____
0440	512	54430 TEMP. PVMT MRKG, TY. A, 6"	6,915.000 LF	_____	_____	_____	_____
0450	700	55140 CONCRETE FOUNDATION LF- 1 TY. A	1.000 EA	_____	_____	_____	_____
0460	407	61800 STRUCT. STEEL STEEL PLATE FOR INLET PROTECTION	LUMP SUM	LUMP SUM	_____	_____	_____
0470	ATTD	67904 BRIDGE INCIDENTALS SAFETY SHIELDING	LUMP SUM	LUMP SUM	_____	_____	_____
0480	430	67910 NBIS ACCESS, UNDER BRIDGE STR. NO 2855	2.000 DAY	_____	_____	_____	_____
0490	410	68010 CONCRETE PARAPET	606.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000093087B60

Oversight/State Project No.: 0195-127-599,C501,B660

Order No.: A48

Federal Project No.: NHPP-195-6(025)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0500	410	68011 PARAPET CONCRETE PARAPET BLOCKED BACK	638.000 LF	_____	_____	_____	_____
0510	404	68043 CONC. CLASS A4 MOD.LOW SHRINKAGE	603.100 CY	_____	_____	_____	_____
0520	404	68085 COVER DEPTH SURVEY	3,685.000 SY	_____	_____	_____	_____
0530	406	68093 CORROSION RESISTANT REINF. STEEL CL. III	135,820.000 LB	_____	_____	_____	_____
0540	407	68115 STRUCT. STEEL MISC STEEL REPAIRS	LUMP SUM	LUMP SUM	_____	_____	_____
0550	412	68172 CRACK REPAIR TYPE B	100.000 LF	_____	_____	_____	_____
0560	412	68180 EMBEDDED GALVANIC ANODES	1,580.000 EA	_____	_____	_____	_____
0570	425	68315 TYPE A MILLING 1-1/2"	1,754.000 SY	_____	_____	_____	_____
0580	412	68339 DECK SLAB CLOSURE	35.000 SY	_____	_____	_____	_____
0590	411	68472 RECOAT EX. STR. NO. 2855	LUMP SUM	LUMP SUM	_____	_____	_____
0600	413	68476 ENV. & WORK. PROTECTION STR. NO 2855	LUMP SUM	LUMP SUM	_____	_____	_____
0610	413	68492 MATERIAL DISPOSAL STR. NO 2855	LUMP SUM	LUMP SUM	_____	_____	_____
0620	421	68550 ELASTOMERIC EXPANSION DAM 0" TO 2"	232.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000093087B60

Oversight/State Project No.: 0195-127-599,C501,B660

Order No.: A48

Federal Project No.: NHPP-195-6(025)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0630	412	68573 RECONSTRUCT EXPANSION JOINT, HES	162.000 LF	_____	_____	_____	_____
0640	412	68579 RECONSTRUCT BACK WALL, HES	115.000 LF	_____	_____	_____	_____
0650	425	68616 PLACE VERY EARLY STRENGTH LATEX MODIFIED CONCRETE OVERLAY	1,488.000 SY	_____	_____	_____	_____
0660	425	68619 FURNISH HIGH EARLY STRENGTH LATEX MOD. CONC. .	112.000 CY	_____	_____	_____	_____
0670	425	68642 TYPE A HYDRO-DEMOLITION 1/2"	1,488.000 SY	_____	_____	_____	_____
0680	425	68648 TYPE B HYDRO-DEMOLITION 3"	266.000 SY	_____	_____	_____	_____
0690	ATTD	68900 REM. PORT. OF EX. STR. NO 2855	LUMP SUM	LUMP SUM		_____	_____
0700	ATTD	68904 SUPERSTR. WID./REPAIR CAP BEAM BRACKET REPAIR	40.000 EA	_____	_____	_____	_____
0710	ATTD	68904 SUPERSTR. WID./REPAIR REPLACE EXPANSION BEARING	16.000 EA	_____	_____	_____	_____
0720	ATTD	68908 SUPERSTR. WID./REPAIR TEMPORARY SUPPORT	LUMP SUM	LUMP SUM		_____	_____
0730	ATTD	68910 SUPERSTR. WID./REPAIR DIAMOND GRINDING	3,685.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000093087B60

Oversight/State Project No.: 0195-127-599,C501,B660

Order No.: A48

Federal Project No.: NHPP-195-6(025)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0740	401	69009 POROUS BACKFILL	11.000 CY	_____	_____	_____	_____
0750	401	69011 STRUCTURE EXCAVATION	55.000 CY	_____	_____	_____	_____
0760	406	69091 CORROSION RESISTANT REINF. STEEL CL. I	1,410.000 LB	_____	_____	_____	_____
0770	412	69500 CONCRETE SUBSTRUCT. SURFACE REPAIR	24.000 SY	_____	_____	_____	_____
0780	412	69822 RECONSTRUCT BRIDGE SEAT HES	16.000 EA	_____	_____	_____	_____
0790	ATTD	69905 BR. SUBSTR. WID./REPAIR EMBEDDED GALVANIC ANODES TYPE 2	755.000 EA	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____