

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	16,653.000 CY				
0050	303	00137 BORROW EXCAVATION (MIN. CBR 10)	45,259.000 CY				
0060	ATTD	00154 GEOTEXTILE (GEOGRID REINFORCEMENT)	467.000 SY				
0070	303	00211 MINOR STRUCTURE EXCAV. PIPE CULVERT	223.000 CY				
0080	ATTD	00306 SELECT MATERIAL TYPE OGB	4,193.000 TON				
0090	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	18,106.000 SY				
0100	302 504	00525 CONCRETE CLASS A3 MISC.	48.700 CY				
0110	509	00529 FLOWABLE BACKFILL	71.800 CY				
0120	302 406	00540 REINF. STEEL	1,535.000 LB				
0130	302	00572 ENDWALL PIPE GRATE EW- 11 TYPE II	16.000 LF				

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	00573 ENDWALL PIPE GRATE EW-11 TYPE III	19.000 LF	_____	_____	_____	_____
0150	501	00588 UNDERDRAIN UD-4	3,094.000 LF	_____	_____	_____	_____
0160	501	00591 CROSSDRAIN CD-2	330.000 LF	_____	_____	_____	_____
0170	501	00595 OUTLET PIPE	361.000 LF	_____	_____	_____	_____
0180	302	00596 ENDWALL EW-12	17.000 EA	_____	_____	_____	_____
0190	302	01122 12" CONC. PIPE	33.000 LF	_____	_____	_____	_____
0200	302	01150 15" PIPE	172.000 LF	_____	_____	_____	_____
0210	302	01152 15" CONC. PIPE	197.000 LF	_____	_____	_____	_____
0220	302	01156 STORM SEWER PIPE 15"	27.000 LF	_____	_____	_____	_____
0230	302	01240 24" PIPE	5.000 LF	_____	_____	_____	_____
0240	302	01241 JACKED & BORED 24" PIPE	137.000 LF	_____	_____	_____	_____
0250	302	01242 24" CONC. PIPE	359.000 LF	_____	_____	_____	_____
0260	302	01302 30" CONC. PIPE	76.000 LF	_____	_____	_____	_____
0270	302	01361 JACKED & BORED 36" PIPE	59.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	302	01362 36" CONC. PIPE	210.000 LF	_____	_____	_____	_____
0290	302	01422 42" CONC. PIPE	208.000 LF	_____	_____	_____	_____
0300	302	06121 12" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0310	302	06151 15" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0320	302	06240 24" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0330	302	06241 24" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0340	302	06361 36" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0350	302	07508 DROP INLET DI-7	3.000 EA	_____	_____	_____	_____
0360	302	08965 DROP INLET DI-13 TY.II	2.000 EA	_____	_____	_____	_____
0370	302	09056 MANHOLE MH-1 OR 2	36.200 LF	_____	_____	_____	_____
0380	302	09057 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0390	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	29.100 TON	_____	_____	_____	_____
0400	414	09150 EROSION CONTROL STONE CLASS I, EC-1	109.100 TON	_____	_____	_____	_____
0410	414	09152 EROSION CONTROL STONE CLASS II, EC-1	91.800 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	308	10103 AGGR. MATL. NO. 25 OR 26	92.000 TON	_____	_____	_____	_____
0430	308	10128 AGGR. BASE MATL. TY. I NO. 21B	9,327.000 TON	_____	_____	_____	_____
0440	315	10610 ASPHALT CONCRETE TY. IM- 19.0A	2,085.000 TON	_____	_____	_____	_____
0450	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	7,667.000 SY	_____	_____	_____	_____
0460	315	10635 ASPHALT CONC.TY. SM-9.5A	1,839.000 TON	_____	_____	_____	_____
0470	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	5,570.000 TON	_____	_____	_____	_____
0480	PLAN 315	11070 SAW-CUT ASPH CONC FULL DEPTH	5,507.000 LF	_____	_____	_____	_____
0490	502	12030 STD. CURB CG-3	41.000 LF	_____	_____	_____	_____
0500	502	12032 RADIAL CURB CG-3	187.000 LF	_____	_____	_____	_____
0510	502	12322 ASPHALT CONC. CURB TY. MC-3B	20.000 LF	_____	_____	_____	_____
0520	315	12505 ASPHALT CONCRETE, CURB BACKUP MATERIAL	5.000 TON	_____	_____	_____	_____
0530	503	13212 R/W MONUMENT RM-2	16.000 EA	_____	_____	_____	_____
0540	505	13262 SALVAGE EXIST. GUARDRAIL TERMINAL GR-MGS3	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0550	505	13280 GUARDRAIL GR-MGS1	3,861.000 LF	_____	_____	_____	_____
0560	505	13283 RADIAL GUARDRAIL GR-MGS1	864.000 LF	_____	_____	_____	_____
0570	505	13286 GUARDRAIL TERMINAL GR-MGS2	10.000 EA	_____	_____	_____	_____
0580	505	13287 GUARDRAIL END ANCHORAGE GR-MGS3	4.000 EA	_____	_____	_____	_____
0590	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	12.000 EA	_____	_____	_____	_____
0600	505	13355 GUARDRAIL GR-10	100.000 LF	_____	_____	_____	_____
0610	505	13392 FIXED OBJECT ATTACH. GR-FOA-2 TY. I	2.000 EA	_____	_____	_____	_____
0620	505	13393 FIXED OBJECT ATTACH. GR-FOA-2 TY. II	2.000 EA	_____	_____	_____	_____
0630	505	13401 GUARDRAIL TERMINAL SITE PREPARATION (4 FT. - MODERATE)	2.000 EA	_____	_____	_____	_____
0640	505	13401 GUARDRAIL TERMINAL SITE PREPARATION (6 FT. - MODERATE)	8.000 EA	_____	_____	_____	_____
0650	505	13480 CABLE BARRICADE CR-1	1.000 EA	_____	_____	_____	_____
0660	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	5,128.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	17.000 EA	_____	_____	_____	_____
0680	ATTD	14411 PIPE TIE IN	1.000 EA	_____	_____	_____	_____
0690	507	22511 FENCE FE-W2	503.000 LF	_____	_____	_____	_____
0700	507	22541 LINE BRACE UNIT FE-W1,FE- W2	8.000 EA	_____	_____	_____	_____
0710	507	22581 CORNER BRACE UNIT FE- W1,FE-W2	3.000 EA	_____	_____	_____	_____
0720	507	23042 WATER GATE FE-4 TY.II	1.000 EA	_____	_____	_____	_____
0730	511	24100 ALLAYING DUST	2,199.000 HR	_____	_____	_____	_____
0740	512	24152 TYPE 3 BARRICADE 8'	18.000 EA	_____	_____	_____	_____
0750	512	24160 TEMPORARY (CONSTRUCTION) SIGN	11,207.000 SF	_____	_____	_____	_____
0760	512	24269 PORTABLE TEMPORARY RUMBLE STRIP	2.000 EA	_____	_____	_____	_____
0770	512	24272 TRUCK MOUNTED ATTENUATOR	3,958.000 HR	_____	_____	_____	_____
0780	512	24278 GROUP 2 CHANNELIZING DEVICES	98,670.000 DAY	_____	_____	_____	_____
0790	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	5,656.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621

Order No.: A50

Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	512	24281 ELECTRONIC ARROW BOARD	5,136.000 HR	_____	_____	_____	_____
0810	512	24282 FLAGGER SERVICE	2,638.000 HR	_____	_____	_____	_____
0820	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	4,316.000 LF	_____	_____	_____	_____
0830	ATTD	24330 TRAFFIC CONTROL ATC CABINET - 5 DOOR CONFIGURATION (16 CHANNEL HIGH VOLTAGE)	2.000 EA	_____	_____	_____	_____
0840	700 703	24333 TEMPORARY TRAFFIC CONTROL SIGNAL - STAGE 1 & 2 ROUTE 11 AND ROUTE 259	LUMP SUM	LUMP SUM	_____	_____	_____
0850	700 703	24333 TEMPORARY TRAFFIC CONTROL SIGNAL - STAGE 3 ROUTE 11 AND RAMP A/D	LUMP SUM	LUMP SUM	_____	_____	_____
0860	700, 703	24333 TEMPORARY TRAFFIC CONTROL SIGNAL - STAGE 3 ROUTE 11 AND ROUTE 259	LUMP SUM	LUMP SUM	_____	_____	_____
0870	ATTD	24355 POLICE PATROL UNIFORMED FLAGGER	1,200.000 HR	_____	_____	_____	_____
0880	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	9,814.000 SY	_____	_____	_____	_____
0890	510	24503 REMOVE EXIST. (DEMOLITION D701)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0900	510	24503 REMOVE EXIST. (DEMOLITION D702)	LUMP SUM	LUMP SUM			
0910	510	24505 RELOCATE EXIST. SIGN STRUCTURE TYPE 1	1.000 EA				
0920	505	24600 REMOVE EXISTING GUARDRAIL	5,045.000 LF				
0930	510	24602 REMOVE EXIST. FENCE AND DISPOSE	1,109.000 LF				
0940	514	25506 FIELD OFFICE TY.II	23.000 MO				
0950	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM			
0960	ATTD	25567 PROGRESS SCHEDULE UPDATES	23.000 EA				
0970	602	27024 TOPSOIL (CLASS B 3" DEPTH)	1.270 ACRE				
0980	603	27101 TEMPORARY SEED	575.000 LB				
0990	603	27102 REGULAR SEED	863.000 LB				
1000	603	27103 OVERSEEDING	690.000 LB				
1010	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	12,584.000 SY				
1020	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	50,046.000 SY				

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621

Order No.: A50

Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1030	603	27120 SEDIMENT RETENTION ROLL 18" MIN	2,760.000 LF	_____	_____	_____	_____
1040	603	27230 FERTILIZER NITROGEN - N	550.000 LB	_____	_____	_____	_____
1050	603	27231 FERTILIZER PHOSPHOROUS - P	755.000 LB	_____	_____	_____	_____
1060	603	27232 FERTILIZER POTASSIUM - K	378.000 LB	_____	_____	_____	_____
1070	603	27250 LIME	27.000 TON	_____	_____	_____	_____
1080	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	1,892.000 SY	_____	_____	_____	_____
1090	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	96.000 SY	_____	_____	_____	_____
1100	606	27327 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	8.000 SY	_____	_____	_____	_____
1110	302	27336 TEMP. DIVERSION CHANNEL LINING CL. A	304.000 SY	_____	_____	_____	_____
1120	302	27337 TEMP. DIVERSION CHANNEL LINING CL. B	91.000 SY	_____	_____	_____	_____
1130	302	27340 TEMP. DIVERSION CHANNEL EXCAVATION	143.000 CY	_____	_____	_____	_____
1140	303	27345 TEMPORARY DIVERSION DIKE	484.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1150	303	27410 CHECK DAM, ROCK TY. I	2.000 EA	_____	_____	_____	_____
1160	303	27415 CHECK DAM ROCK TY. II	95.000 EA	_____	_____	_____	_____
1170	303	27422 DEWATERING BASIN EC-8	4.000 EA	_____	_____	_____	_____
1180	303	27430 SILTATION CONTROL EXCAVATION	2,516.000 CY	_____	_____	_____	_____
1190	303	27451 INLET PROTECTION TYPE A	5.000 EA	_____	_____	_____	_____
1200	303	27461 INLET PROTECTION TYPE B	2.000 EA	_____	_____	_____	_____
1210	303	27504 TEMP. SILT FENCE TYPE B	8,337.000 LF	_____	_____	_____	_____
1220	245	27544 STORM WATER MGT. LOW PERMEABILITY LINER	238.000 CY	_____	_____	_____	_____
1230	PLAN ATTD	27548 STORM WATER MANAGEMENT MODIFIED EW-1 WITH WEIR WALL	LUMP SUM	LUMP SUM		_____	_____
1240	ATTD	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION (CONSTRUCTION RECORD DOCUMENTS)	LUMP SUM	LUMP SUM		_____	_____
1250	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	5,158.000 CY	_____	_____	_____	_____
1260	701	50108 SIGN PANEL	1,017.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1270	700	50410 VIA SIGN POST, W10 X 12	22.000 LF	_____	_____	_____	_____
1280	700	50412 VIA SIGN POST, W12 X 16	72.000 LF	_____	_____	_____	_____
1290	700	50414 VIA SIGN POST, W14 X 22	34.000 LF	_____	_____	_____	_____
1300	700	50430 SIGN POST STP-1, 2", 14 GAUGE	219.000 LF	_____	_____	_____	_____
1310	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	148.000 LF	_____	_____	_____	_____
1320	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	226.000 LF	_____	_____	_____	_____
1330	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	50.000 LF	_____	_____	_____	_____
1340	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	26.000 EA	_____	_____	_____	_____
1350	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	8.000 EA	_____	_____	_____	_____
1360	700	50506 CONC. SIGN FOUND., SSP-VI A 2'3" DIA. X 4'6" DEPTH	2.000 EA	_____	_____	_____	_____
1370	700	50528 CONC. SIGN FOUND., SSP-VI A 3'0" DIA. X 7' DEPTH	8.000 EA	_____	_____	_____	_____
1380	700	51170 ELECTRICAL SERVICE SE-5	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1390	703	51185 TRAFFIC SIGNAL HEAD SECTION 12" HVS BACKPLATE	61.000 EA	_____	_____	_____	_____
1400	700	51212 PEDESTAL POLE PF-2 12'	2.000 EA	_____	_____	_____	_____
1410	700	51238 CONCRETE FOUNDATION SIGNAL POLE PF-8	40.000 CY	_____	_____	_____	_____
1420	700	51240 CONCRETE FOUNDATION PF-2	2.000 EA	_____	_____	_____	_____
1430	700	51243 CONC FOUNDATION CF-5	2.000 EA	_____	_____	_____	_____
1440	700	51475 SIGNAL MAST ARM POLE MP-3, TYPE A	1.000 EA	_____	_____	_____	_____
1450	700	51476 SIGNAL MAST ARM POLE MP-3, TYPE B1	1.000 EA	_____	_____	_____	_____
1460	700	51478 SIGNAL MAST ARM POLE MP-3, TYPE C	1.000 EA	_____	_____	_____	_____
1470	700	51485 MAST ARM 30'	1.000 EA	_____	_____	_____	_____
1480	700	51488 MAST ARM 60'	1.000 EA	_____	_____	_____	_____
1490	700	51489 MAST ARM 65'	1.000 EA	_____	_____	_____	_____
1500	703	51523 EVP DETECTION SYSTEM 3-WAY	2.000 EA	_____	_____	_____	_____
1510	703	51525 EVP DETECTOR CABLE	1,914.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1520	703	51540 LOOP DETECTOR AMPLIFIER	16.000 EA	_____	_____	_____	_____
1530	700	51602 14/4 CONDUCTOR CABLE	5,940.000 LF	_____	_____	_____	_____
1540	700	51615 14/1 ENCLOSED COND. CABLE	5,632.000 LF	_____	_____	_____	_____
1550	700	51700 14/2 CONDUCTOR CABLE SHIELDED	5,049.000 LF	_____	_____	_____	_____
1560	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	16.000 EA	_____	_____	_____	_____
1570	703	51832 HANGER ASSEMBLY SMB-1, ONE WAY	2.000 EA	_____	_____	_____	_____
1580	703	51840 HANGER ASSEMBLY SMD-2, ONE WAY	13.000 EA	_____	_____	_____	_____
1590	703	51913 LOOP SAWCUT 5/8"	1,860.000 LF	_____	_____	_____	_____
1600	700	51930 REMOVE EXISTING SIGN STRUCTURE TYPE 1	1.000 EA	_____	_____	_____	_____
1610	700	51930 REMOVE EXISTING SIGN STRUCTURE TYPE ST-1	13.000 EA	_____	_____	_____	_____
1620	700	51930 REMOVE EXISTING SIGN STRUCTURE TYPE ST-2	1.000 EA	_____	_____	_____	_____
1630	700	51930 REMOVE EXISTING SIGN STRUCTURE TYPE STP-1	18.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1640	700	51930 REMOVE EXISTING SIGN STRUCTURE TYPE STP-2	2.000 EA	_____	_____	_____	_____
1650	700	51930 REMOVE EXISTING SIGN STRUCTURE TYPE STP-3	1.000 EA	_____	_____	_____	_____
1660	700	51930 REMOVE EXISTING SIGN STRUCTURE TYPE VIA	1.000 EA	_____	_____	_____	_____
1670	700	51930 REMOVE EXISTING SIGN STRUCTURE TYPE WP-1	3.000 EA	_____	_____	_____	_____
1680	700	51930 REMOVE EXISTING SIGN STRUCTURE TYPE WP-2	2.000 EA	_____	_____	_____	_____
1690	700	51931 REMOVE EXISTING SIGN PANEL TYPE SP-1	1.000 EA	_____	_____	_____	_____
1700	700	51932 RELOCATE EXISTING SIGN PANEL TYPE SP-1	2.000 EA	_____	_____	_____	_____
1710	700	51932 RELOCATE EXISTING SIGN PANEL TYPE SP-2	1.000 EA	_____	_____	_____	_____
1720	703	51994 UNINTERRUPTIBLE POWER SUPPLY TYPE 2	2.000 EA	_____	_____	_____	_____
1730	703	51995 UNINTERRUPTIBLE POWER SUPPLY BATTERY PACK	2.000 EA	_____	_____	_____	_____
1740	ATTD	52002 TRAFFIC SIGNALIZATION ADVANCED TRAFFIC CONTROLLER (2070LX)	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621

Order No.: A50

Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1750	ATTD	52003 TRAFFIC ENGINEERING QUEUE MANAGEMENT TEAM	1,280.000 HR	_____	_____	_____	_____
1760	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	14,316.000 LF	_____	_____	_____	_____
1770	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	524.000 LF	_____	_____	_____	_____
1780	704	54075 TYPE B CLASS VI PVMT LINE MRKG 4"	725.000 LF	_____	_____	_____	_____
1790	704	54076 TYPE B CLASS VI PVMT LINE MRKG 6"	827.000 LF	_____	_____	_____	_____
1800	704	54079 TYPE B CLASS VI CONTRAST PVMT MRKG 4"	1,663.000 LF	_____	_____	_____	_____
1810	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	13,015.000 LF	_____	_____	_____	_____
1820	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	561.000 SF	_____	_____	_____	_____
1830	510	54210 REMOVE EXIST. RAISED PAVEMENT MARKER	229.000 EA	_____	_____	_____	_____
1840	704	54217 SNOW PLOW. RAISED PAVE. MARKER ASPH.CONC	183.000 EA	_____	_____	_____	_____
1850	704	54218 SNOW PLOW. RAISED PAVE. MARKER HYD. CONC	21.000 EA	_____	_____	_____	_____
1860	512	54242 TEMP. PAVE. MARKER 2 WAY	796.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1870	512	54428 TEMP. PVMT MRKG, TY. A, 4"	44,760.000 LF	_____	_____	_____	_____
1880	512	54430 TEMP. PVMT MRKG, TY. A, 6"	8,817.000 LF	_____	_____	_____	_____
1890	512	54432 TEMP. PVMT MRKG, TY. A, 8"	7,108.000 LF	_____	_____	_____	_____
1900	512	54440 TEMP. PVMT MRKG, TY. A, 24"	883.000 LF	_____	_____	_____	_____
1910	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	23.000 EA	_____	_____	_____	_____
1920	512	54466 TYPE E TEMP. PVMT MRKG 6"	500.000 LF	_____	_____	_____	_____
1930	704	54526 TEMP PVMT MRKG TY.D CLASS III 6"	5,580.000 EA	_____	_____	_____	_____
1940	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	15.000 EA	_____	_____	_____	_____
1950	704	54576 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY A	2.000 EA	_____	_____	_____	_____
1960	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	2.000 EA	_____	_____	_____	_____
1970	704	54625 PVMT SYMB MRKG YIELD 2'x3' TY B, CL I	7.000 EA	_____	_____	_____	_____
1980	700	55080 8 CONDUCTOR CABLE	5,028.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1990	700	55586 JUNCTION BOX JB-S1	4.000 EA	_____	_____	_____	_____
2000	700	55587 JUNCTION BOX JB-S2	23.000 EA	_____	_____	_____	_____
2010	700	55588 JUNCTION BOX JB-S3	2.000 EA	_____	_____	_____	_____
2020	700	56014 ELECT. SER. GRD. ELECTRODE 10'	6.000 EA	_____	_____	_____	_____
2030	700	56021 1" PVC CONDUIT	89.000 LF	_____	_____	_____	_____
2040	700	56024 1 1/4" PVC CONDUIT	573.000 LF	_____	_____	_____	_____
2050	700	56026 1 1/4" METAL CONDUIT	44.000 LF	_____	_____	_____	_____
2060	700	56050 BORED CONDUIT 2"	996.000 LF	_____	_____	_____	_____
2070	700	56051 BORED CONDUIT 3"	1,496.000 LF	_____	_____	_____	_____
2080	700	56053 2" PVC CONDUIT	1,903.000 LF	_____	_____	_____	_____
2090	700	56054 3" PVC CONDUIT	2,508.000 LF	_____	_____	_____	_____
2100	700	56055 4" PVC CONDUIT	56.000 LF	_____	_____	_____	_____
2110	700	56200 TRENCH EXCAVATION ECI-1	2,640.000 LF	_____	_____	_____	_____
2120	700	56205 TEST BORE	5.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2130	808	57203 FIBER OPTIC DROP CABLE 12 STRAND	1,408.000 LF	_____	_____	_____	_____
2140	808	57204 PRE-TERMINATED FIBER PATCH PANEL	1.000 EA	_____	_____	_____	_____
2150	808	57215 FIBER DISTRIBUTION CENTER	1.000 EA	_____	_____	_____	_____
2160	809	57221 MANAGED FIELD ETHERNET SWITCH Gbps	1.000 EA	_____	_____	_____	_____
2170	809	57227 DISTRIBUTION SFP MODULE 1Gbps, LC, AND SHORT HAUL	4.000 EA	_____	_____	_____	_____
2180	810	57257 L3 FIELD AGGREGATION ETHERNET SWITCH HARDENED	1.000 EA	_____	_____	_____	_____
2190	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	727.500 CY	_____	_____	_____	_____
2200	404	60490 BRIDGE DECK GROOVING	2,575.000 SY	_____	_____	_____	_____
2210	404	60495 COVER DEPTH SURVEY	2,575.000 SY	_____	_____	_____	_____
2220	406	61712 CORROSION RESISTANT REINF. STEEL CL. II	158,050.000 LB	_____	_____	_____	_____
2230	407	61812 STR. STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM	_____	_____	_____
2240	410	62010 CONCRETE PARAPET	772.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2250	PLAN ATTD	62535 BRIDGE SUPERSTRUCTURE ELASTOMERIC BEARING DEVICE	14.000 EA	_____	_____	_____	_____
2260	PLAN ATTD	62535 BRIDGE SUPERSTRUCTURE LOW PROFILE BEARING DEVICE	7.000 EA	_____	_____	_____	_____
2270	401	64011 STRUCTURE EXCAVATION	2,536.000 CY	_____	_____	_____	_____
2280	401	64015 SELECT BACKFILL ABUTMENT ZONE	3,415.000 TON	_____	_____	_____	_____
2290	401	64032 GEOCOMPOSITE WALL DRAIN	498.000 SY	_____	_____	_____	_____
2300	401	64036 PIPE UNDERDRAIN 6"	483.000 LF	_____	_____	_____	_____
2310	404	65013 CONCRETE CLASS A3	1,287.100 CY	_____	_____	_____	_____
2320	404	65095 CONCRETE CLASS A3 OR T3 (UNREINFORCED)	93.100 CY	_____	_____	_____	_____
2330	406	65200 REINF. STEEL	119,860.000 LB	_____	_____	_____	_____
2340	ATTD	66925 BRIDGE SUBSTRUCTURE AGGR. MATL. NO. 1	647.000 TON	_____	_____	_____	_____
2350	413	67900 DISM.& REM. EX. STR. STR. NO. 1172	LUMP SUM	LUMP SUM	_____	_____	_____
2360	PLAN ATTD	67904 BRIDGE INCIDENTALS TEMPORARY SHORING	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000097111B621 Oversight/State Project No.: 0011-082-752, C501,B621
 Order No.: A50 Federal Project No.: BR-5115(150)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2370	430	67910 NBIS ACCESS, UNDER BRIDGE B-621	1.000 DAY	_____	_____	_____	_____
2380	413	68476 ENV.& WORK. PROTECTION STR. NO. 1172	LUMP SUM	LUMP SUM	_____	_____	_____
2390	413	68492 MATERIAL DISPOSAL STR. NO. 1172, TYPE B	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____