

Schedule of Items

Proposal ID: C0000114770M01      Oversight/State Project No.: (NFO) 0003-111-314,M501  
 Order No.: B17      Federal Project No.: NHPP-BR06(282)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00102 CONSTRUCTION SURVEYING MIN.-PLAN	LUMP SUM	LUMP SUM			
0030	303	00125 GRADING	LUMP SUM	LUMP SUM			
0040	308	10128 AGGR. BASE MATL. TY. I NO. 21B	498.000 TON				
0050	315	10608 ASPHALT CONCRETE TY. SM-12.5D	428.000 TON				
0060	315	10610 ASPHALT CONCRETE TY. IM-19.0A	104.000 TON				
0070	315	10642 ASPHALT CONCRETE TY. BM-25.0A	131.000 TON				
0080	315	11070 SAW-CUT ASPH CONC FULL DEPTH	1,031.000 LF				
0090	502	12020 STD. CURB CG-2	378.000 LF				
0100	502	12022 RADIAL CURB CG-2	231.000 LF				
0110	504	13108 CG-12 DETECTABLE WARNING SURFACE	10.000 SY				
0120	511	24100 ALLAYING DUST	100.000 HR				
0130	512	24152 TYPE 3 BARRICADE 8'	8.000 EA				

Schedule of Items

Proposal ID: C0000114770M01

Oversight/State Project No.: (NFO) 0003-111-314,M501

Order No.: B17

Federal Project No.: NHPP-BR06(282)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	512	24160 TEMPORARY (CONSTRUCTION) SIGN	871.000 SF	_____	_____	_____	_____
0150	512	24272 TRUCK MOUNTED ATTENUATOR	540.000 HR	_____	_____	_____	_____
0160	512	24278 GROUP 2 CHANNELIZING DEVICES	1,395.000 DAY	_____	_____	_____	_____
0170	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	540.000 HR	_____	_____	_____	_____
0180	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	64.000 LF	_____	_____	_____	_____
0190	508	24410 DEMOLITION OF PAVEMENT COMBINATION	191.000 SY	_____	_____	_____	_____
0200	510	24825 MODIFY EXIST. CONTROLLER CABINET	1.000 EA	_____	_____	_____	_____
0210	602	27012 TOPSOIL CLASS A 2"	0.180 ACRE	_____	_____	_____	_____
0220	603	27101 TEMPORARY SEED	23.000 LB	_____	_____	_____	_____
0230	603	27102 REGULAR SEED	45.000 LB	_____	_____	_____	_____
0240	603	27103 OVERSEEDING	36.000 LB	_____	_____	_____	_____
0250	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,271.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000114770M01      Oversight/State Project No.: (NFO) 0003-111-314,M501  
 Order No.: B17      Federal Project No.: NHPP-BR06(282)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	1,234.000 SY	_____	_____	_____	_____
0270	603	27230 FERTILIZER NITROGEN - N	22.000 LB	_____	_____	_____	_____
0280	603	27231 FERTILIZER PHOSPHOROUS - P	30.000 LB	_____	_____	_____	_____
0290	603	27232 FERTILIZER POTASSIUM - K	15.000 LB	_____	_____	_____	_____
0300	603	27250 LIME	1.040 TON	_____	_____	_____	_____
0310	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	225.000 SY	_____	_____	_____	_____
0320	303	27415 CHECK DAM ROCK TY. II	3.000 EA	_____	_____	_____	_____
0330	303	27430 SILTATION CONTROL EXCAVATION	335.000 CY	_____	_____	_____	_____
0340	303	27451 INLET PROTECTION TYPE A	1.000 EA	_____	_____	_____	_____
0350	303	27461 INLET PROTECTION TYPE B	2.000 EA	_____	_____	_____	_____
0360	303	27505 TEMP. SILT FENCE TYPE A	1,812.000 LF	_____	_____	_____	_____
0370	701	50108 SIGN PANEL	124.000 SF	_____	_____	_____	_____
0380	700	50430 SIGN POST STP-1, 2", 14 GAUGE	132.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000114770M01

Oversight/State Project No.: (NFO) 0003-111-314,M501

Order No.: B17

Federal Project No.: NHPP-BR06(282)

Contractor: \_\_\_\_\_

SECTION: 0001                      REGULAR ITEMS

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	24.000 LF	_____	_____	_____	_____
0400	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	13.000 EA	_____	_____	_____	_____
0410	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	2.000 EA	_____	_____	_____	_____
0420	510	50600 REMOVE TY.I SIGNS	6.000 EA	_____	_____	_____	_____
0430	703	51540 LOOP DETECTOR AMPLIFIER	1.000 EA	_____	_____	_____	_____
0440	700	51615 14/1 ENCLOSED COND. CABLE	1,000.000 LF	_____	_____	_____	_____
0450	700	51700 14/2 CONDUCTOR CABLE SHIELDED	800.000 LF	_____	_____	_____	_____
0460	703	51912 LOOP SAW CUT 3/8"	324.000 LF	_____	_____	_____	_____
0470	703	51913 LOOP SAWCUT 5/8"	40.000 LF	_____	_____	_____	_____
0480	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	1,715.000 LF	_____	_____	_____	_____
0490	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	1,177.000 LF	_____	_____	_____	_____
0500	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	87.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000114770M01      Oversight/State Project No.: (NFO) 0003-111-314,M501  
 Order No.: B17      Federal Project No.: NHPP-BR06(282)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	3.000 EA	_____	_____	_____	_____
0520	704	54585 PVMT SYMB MRKG DBL TURN ARROW, LT/RT TY B, CL I	1.000 EA	_____	_____	_____	_____
0530	700	56022 1" METAL CONDUIT	20.000 LF	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	
				<b>Total Bid:</b>		_____	