Proposal ID: C000097712B63 **Oversight/State Project No.:** 0644-009-746,M501,B663
Order No.: B12 **Federal Project No.:** BROS-009-2(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM		_____	_____
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM		_____	_____
0040	303	00125 GRADING	LUMP SUM	LUMP SUM		_____	_____
0050	501	00592 CROSSDRAIN CD-1&2	47.000 LF	_____	_____	_____	_____
0060	501	00595 OUTLET PIPE	23.000 LF	_____	_____	_____	_____
0070	302	00596 ENDWALL EW-12	3.000 EA	_____	_____	_____	_____
0080	302	01152 15" CONC. PIPE	30.000 LF	_____	_____	_____	_____
0090	302	06151 15" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0100	302	06815 DROP INLET DI-3A	1.000 EA	_____	_____	_____	_____
0110	302	06816 DROP INLET DI-3AA	1.000 EA	_____	_____	_____	_____
0120	414	09150 EROSION CONTROL STONE CLASS I, EC-1	21.000 TON	_____	_____	_____	_____
0130	308	10128 AGGR. BASE MATL. TY. I NO. 21B	800.000 TON	_____	_____	_____	_____
0140	315	10635 ASPHALT CONC.TY. SM-9.5A	97.000 TON	_____	_____	_____	_____

Proposal ID: C000097712B63 **Oversight/State Project No.:** 0644-009-746,M501,B663
Order No.: B12 **Federal Project No.:** BROS-009-2(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0150	315	10642 ASPHALT CONCRETE TY. BM-25.0A	189.000 TON	_____	_____	_____	_____
0160	315	11070 SAW-CUT ASPH CONC FULL DEPTH	54.000 LF	_____	_____	_____	_____
0170	502	12322 ASPHALT CONC. CURB TY. MC-3B	47.000 LF	_____	_____	_____	_____
0180	315	12505 ASPHALT CONCRETE, CURB BACKUP MATERIAL	2.000 TON	_____	_____	_____	_____
0190	503	13212 R/W MONUMENT RM-2	10.000 EA	_____	_____	_____	_____
0200	505	13286 GUARDRAIL TERMINAL GR-MGS2	3.000 EA	_____	_____	_____	_____
0210	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	3.000 EA	_____	_____	_____	_____
0220	505	13320 GUARDRAIL GR-2	12.500 LF	_____	_____	_____	_____
0230	505	13331 RAD. GUARDRAIL GR-2	48.000 LF	_____	_____	_____	_____
0240	505	13345 ALTERNATE BREAKAWAY CABLE TERMINAL GR-9	1.000 EA	_____	_____	_____	_____
0250	505	13355 GUARDRAIL GR-10	37.500 LF	_____	_____	_____	_____
0260	505	13383 FIXED OBJECT ATTACH. GR-FOA-1 TY. I	4.000 EA	_____	_____	_____	_____
0270	512	24150 TYPE 3 BARRICADE 4'	8.000 EA	_____	_____	_____	_____

Proposal ID: C000097712B63 **Oversight/State Project No.:** 0644-009-746,M501,B663
Order No.: B12 **Federal Project No.:** BROS-009-2(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0280	512	24152 TYPE 3 BARRICADE 8'	6.000 EA	_____	_____	_____	_____
0290	512	24160 TEMPORARY (CONSTRUCTION) SIGN	1,140.000 SF	_____	_____	_____	_____
0300	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	340.000 HR	_____	_____	_____	_____
0310	512	24282 FLAGGER SERVICE	56.000 HR	_____	_____	_____	_____
0320	512	24288 WARNING LIGHT TY. B	3,670.000 DAY	_____	_____	_____	_____
0330	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	100.000 LF	_____	_____	_____	_____
0340	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	715.000 SY	_____	_____	_____	_____
0350	510	24602 REMOVE EXIST. FENCE .	260.000 LF	_____	_____	_____	_____
0360	514	25505 FIELD OFFICE TY.I	14.000 MO	_____	_____	_____	_____
0370	602	27012 TOPSOIL CLASS A 2"	0.300 ACRE	_____	_____	_____	_____
0380	603	27101 TEMPORARY SEED	30.000 LB	_____	_____	_____	_____
0390	603	27102 REGULAR SEED	51.000 LB	_____	_____	_____	_____
0400	603	27103 OVERSEEDING	41.000 LB	_____	_____	_____	_____
0410	603	27104 LEGUME SEED	13.000 LB	_____	_____	_____	_____

Proposal ID: C000097712B63 **Oversight/State Project No.:** 0644-009-746,M501,B663
Order No.: B12 **Federal Project No.:** BROS-009-2(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0420	603	27105 LEGUME OVERSEEDING	11.000 LB	_____	_____	_____	_____
0430	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	605.000 SY	_____	_____	_____	_____
0440	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,662.000 SY	_____	_____	_____	_____
0450	603	27230 FERTILIZER NITROGEN - N	29.000 LB	_____	_____	_____	_____
0460	603	27231 FERTILIZER PHOSPHOROUS - P	39.000 LB	_____	_____	_____	_____
0470	603	27232 FERTILIZER POTASSIUM - K	20.000 LB	_____	_____	_____	_____
0480	603	27250 LIME	1.350 TON	_____	_____	_____	_____
0490	606	27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	262.000 SY	_____	_____	_____	_____
0500	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	94.000 SY	_____	_____	_____	_____
0510	606	27326 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 2	35.000 SY	_____	_____	_____	_____
0520	303	27345 TEMPORARY DIVERSION DIKE	229.000 LF	_____	_____	_____	_____
0530	303	27415 CHECK DAM ROCK TY. II	21.000 EA	_____	_____	_____	_____
0540	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____

Proposal ID: C000097712B63 **Oversight/State Project No.:** 0644-009-746,M501,B663
Order No.: B12 **Federal Project No.:** BROS-009-2(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0550	303	27430 SILTATION CONTROL EXCAVATION	215.000 CY	_____	_____	_____	_____
0560	608	27440 MOWING	10.000 HR	_____	_____	_____	_____
0570	303	27461 INLET PROTECTION TYPE B	2.000 EA	_____	_____	_____	_____
0580	303	27504 TEMP. SILT FENCE TYPE B	550.000 LF	_____	_____	_____	_____
0590	303	27505 TEMP. SILT FENCE TYPE A	606.000 LF	_____	_____	_____	_____
0600	303	27525 TURBIDITY CURTAIN, PERVIOUS	137.000 LF	_____	_____	_____	_____
0610	701	50108 SIGN PANEL	5.180 SF	_____	_____	_____	_____
0620	700	50430 SIGN POST STP-1, 2", 14 GAUGE	30.000 LF	_____	_____	_____	_____
0630	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	15.000 LF	_____	_____	_____	_____
0640	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	3.000 EA	_____	_____	_____	_____
0650	700 ATTD	50902 TRAFFIC SIGN RELOC. EXIST. SIGN PANEL TY. SP-1	2.000 EA	_____	_____	_____	_____
0660	700	50902 TRAFFIC SIGN REMOVE-DISPOSE SIGN STRUCTURE TY. GM	13.000 EA	_____	_____	_____	_____
0670	704	54020 TYPE A PVMT LINE MRKG 4"	730.000 LF	_____	_____	_____	_____

Proposal ID: C000097712B63 **Oversight/State Project No.:** 0644-009-746,M501,B663
Order No.: B12 **Federal Project No.:** BROS-009-2(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0680	704	54079 TYPE B CLASS VI CONTRAST PVMT MRKG 4"	180.000 LF				
0690	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	100.000 LF				
0700	ATTD	60125 BRIDGE TEMPORARY WORK BRIDGE	LUMP SUM	LUMP SUM			
0710	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	66.000 CY				
0720	404	60490 BRIDGE DECK GROOVING	220.000 SY				
0730	404	60495 COVER DEPTH SURVEY	220.000 SY				
0740	406	61711 CORROSION RESISTANT REINF. STEEL CL. I	11,060.000 LB				
0750	407	61812 STR.STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM			
0760	410	62032 RAILING,KANSAS CORRAL 32" W/CURB	188.000 LF				
0770	401	64011 STRUCTURE EXCAVATION	1,060.000 CY				
0780	401	64015 SELECT BACKFILL ABUTMENT ZONE	1,685.000 TON				
0790	401	64032 GEOCOMPOSITE WALL DRAIN	121.000 SY				