

Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	4,433.000 CY				
0050	303	00141 BORROW EXCAVATION Min CBR-15	516.000 CY				
0060	305	00142 BORROW EXCAVATION MIN. CBR-20	2,916.000 CY				
0070	303	00212 MINOR STRUCTURE EXCAV. BOX CULVERT	588.000 CY				
0080	305	00280 SELECT MATL. TY. II MIN. CBR-20	1,422.000 CY				
0090	ATTD	00507 BEDDING MATL. AGGR. NO. 57	183.000 TON				
0100	402	00515 TEMPORARY SHEET PILING	1,950.000 SF				
0110	302	00523 PRECAST BOX CULVERT 2 - STD. 12' X 6' PRECAST BOX CULVERTS	48.000 LF				
0120	302 504	00525 CONCRETE CLASS A3 MISC.	2.600 CY				
0130	302	01150 15" PIPE	155.000 LF				

## Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	08962 DROP INLET DI-13 TY.I	5.000 EA	_____	_____	_____	_____
0150	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	61.000 TON	_____	_____	_____	_____
0160	414	09150 EROSION CONTROL STONE CLASS I, EC-1	14.000 TON	_____	_____	_____	_____
0170	303	09250 SLOPE DRAIN	10.000 EA	_____	_____	_____	_____
0180	308	10128 AGGR. BASE MATL. TY. I NO. 21B	1,866.000 TON	_____	_____	_____	_____
0190	308	10250 AGGR. MATERIAL NO. 57	1,341.000 TON	_____	_____	_____	_____
0200	315	10607 ASPHALT CONCRETE TY. SM- 12.5A	427.200 TON	_____	_____	_____	_____
0210	315	10610 ASPHALT CONCRETE TY. IM- 19.0A	350.400 TON	_____	_____	_____	_____
0220	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	868.000 SY	_____	_____	_____	_____
0230	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	867.900 TON	_____	_____	_____	_____
0240	315	11070 SAW-CUT ASPH CONC (FULL DEPTH)	321.000 LF	_____	_____	_____	_____
0250	315	11070 SAW-CUT ASPH CONC 12" DEPTH	900.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	502	12030 STD. CURB CG-3	99.000 LF	_____	_____	_____	_____
0270	502	12322 ASPHALT CONC. CURB TY. MC-3B	979.000 LF	_____	_____	_____	_____
0280	315	12505 ASPHALT CONCRETE, CURB BACKUP MATERIAL	46.500 TON	_____	_____	_____	_____
0290	503	13212 R/W MONUMENT RM-2	20.000 EA	_____	_____	_____	_____
0300	504	13232 GEOTEXTILE DRAINAGE FABRIC	6,534.000 SY	_____	_____	_____	_____
0310	505	13280 GUARDRAIL GR-MGS1	1,276.000 LF	_____	_____	_____	_____
0320	505	13286 GUARDRAIL TERMINAL GR- MGS2	8.000 EA	_____	_____	_____	_____
0330	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	16.000 EA	_____	_____	_____	_____
0340	505	13383 FIXED OBJECT ATTACH. GR- FOA-1 TY. I	8.000 EA	_____	_____	_____	_____
0350	505	13392 FIXED OBJECT ATTACH. GR- FOA-2 TY. I	4.000 EA	_____	_____	_____	_____
0360	502	13460 MEDIAN BARRIER MB-7D	52.000 LF	_____	_____	_____	_____
0370	512	13495 TRAF. BARR. SER. CONC. SINGLE FACE PAR.MB-10A	200.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	512	13611 IMPACT ATTENUATOR SERVICE TYPE I	4.000 EA	_____	_____	_____	_____
0390	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	158.100 TON	_____	_____	_____	_____
0400	315	16373 ASPH. CONC. TY. IM-19.0A T	22.000 TON	_____	_____	_____	_____
0410	507	23570 HIGH VISIBILITY FENCE, 4'	2,525.000 LF	_____	_____	_____	_____
0420	511	24100 ALLAYING DUST	2,080.000 HR	_____	_____	_____	_____
0430	512	24152 TYPE 3 BARRICADE 8'	10.000 EA	_____	_____	_____	_____
0440	512	24160 TEMPORARY (CONSTRUCTION) SIGN	3,796.000 SF	_____	_____	_____	_____
0450	512	24278 GROUP 2 CHANNELIZING DEVICES	4,768.000 DAY	_____	_____	_____	_____
0460	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	3,024.000 HR	_____	_____	_____	_____
0470	512	24288 WARNING LIGHT TY. B	11,680.000 DAY	_____	_____	_____	_____
0480	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	1,290.000 LF	_____	_____	_____	_____
0490	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	2,795.000 SY	_____	_____	_____	_____
0500	505	24600 REMOVE EXISTING GUARDRAIL	1,696.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	514	25505 FIELD OFFICE TY.I	24.000 MO	_____	_____	_____	_____
0520	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____
0530	ATTD	25567 PROGRESS SCHEDULE UPDATES	24.000 EA	_____	_____	_____	_____
0540	414	26117 DRY RIPRAP CL. AI	179.000 TON	_____	_____	_____	_____
0550	414	26126 DRY RIPRAP CL.I 26"	2,128.000 SY	_____	_____	_____	_____
0560	602	27012 TOPSOIL CLASS A 2"	0.100 ACRE	_____	_____	_____	_____
0570	602	27022 TOPSOIL CLASS B 2"	0.670 ACRE	_____	_____	_____	_____
0580	603	27101 TEMPORARY SEED	77.000 LB	_____	_____	_____	_____
0590	603	27102 REGULAR SEED	115.000 LB	_____	_____	_____	_____
0600	603	27103 OVERSEEDING	92.000 LB	_____	_____	_____	_____
0610	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,040.000 SY	_____	_____	_____	_____
0620	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	4,332.000 SY	_____	_____	_____	_____
0630	603	27113 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	3,019.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	603	27120 SEDIMENT RETENTION ROLL 18" MIN	1,342.000 LF	_____	_____	_____	_____
0650	603	27230 FERTILIZER NITROGEN - N	74.000 LB	_____	_____	_____	_____
0660	603	27231 FERTILIZER PHOSPHOROUS - P	101.000 LB	_____	_____	_____	_____
0670	603	27232 FERTILIZER POTASSIUM - K	51.000 LB	_____	_____	_____	_____
0680	603	27250 LIME	3.460 TON	_____	_____	_____	_____
0690	ATTD	27275 EROSION CONTROL TEMP. SAND BAG COFFERDAM OR EQUIVALENT TEMP. ENCLOSURE	1,264.000 LF	_____	_____	_____	_____
0700	303	27275 EROSION CONTROL TURBIDITY CURTAIN, IMPERVIOUS, TYPE I	521.000 LF	_____	_____	_____	_____
0710	303	27275 EROSION CONTROL TURBIDITY CURTAIN, IMPERVIOUS, TYPE II	217.000 LF	_____	_____	_____	_____
0720	303	27275 EROSION CONTROL TURBIDITY CURTAIN, PERVIOUS, TYPE I	190.000 LF	_____	_____	_____	_____
0730	303	27284 EROSION CONTROL MULCH	599.000 SY	_____	_____	_____	_____
0740	303	27288 EROSION CONTROL MULCH	1.100 ACRE	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0750	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	2,563.000 SY	_____	_____	_____	_____
0760	303	27345 TEMPORARY DIVERSION DIKE	385.000 LF	_____	_____	_____	_____
0770	303	27415 CHECK DAM ROCK TY. II	5.000 EA	_____	_____	_____	_____
0780	303	27422 DEWATERING BASIN EC-8	17.000 EA	_____	_____	_____	_____
0790	303	27430 SILTATION CONTROL EXCAVATION	1,187.000 CY	_____	_____	_____	_____
0800	303	27461 INLET PROTECTION TYPE B	5.000 EA	_____	_____	_____	_____
0810	303	27504 TEMP. SILT FENCE TYPE B	3,936.000 LF	_____	_____	_____	_____
0820	303	27505 TEMP. SILT FENCE TYPE A	1,154.000 LF	_____	_____	_____	_____
0830	401	27510 COFFERDAM	2.000 EA	_____	_____	_____	_____
0840	701	50108 SIGN PANEL	59.400 SF	_____	_____	_____	_____
0850	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	13.000 EA	_____	_____	_____	_____
0860	700	50430 SIGN POST STP-1, 2", 14 GAUGE	38.000 LF	_____	_____	_____	_____
0870	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	62.500 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0880	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	9.000 EA	_____	_____	_____	_____
0890	512	51956 PORTABLE TRAFFIC CONTROL SIGNAL	LUMP SUM	LUMP SUM	_____	_____	_____
0900	ATTD	51965 INSTALL & REMOVE TEMP PIPE (MIN. OF 2- 42" CULVERTS)	LUMP SUM	LUMP SUM	_____	_____	_____
0910	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	9,125.000 LF	_____	_____	_____	_____
0920	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	35.000 LF	_____	_____	_____	_____
0930	704	54079 TYPE B CLASS VI CONTRAST PVMT MRKG 4"	2,864.000 LF	_____	_____	_____	_____
0940	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	4,800.000 LF	_____	_____	_____	_____
0950	704	54217 SNOW PLOW. RAISED PAVE. MARKER ASPH.CONC	14.000 EA	_____	_____	_____	_____
0960	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	1,770.000 LF	_____	_____	_____	_____
0970	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	300.000 LF	_____	_____	_____	_____
0980	512	54548 TYPE D, CLASS III TEMP. PVMT MRKG 24"	48.000 LF	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001

ALL PROJECT ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0990	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	775.400 CY	_____	_____	_____	_____
1000	316	60450 CONC. CLASS A4 BRIDGE APPR. SLAB	152.800 CY	_____	_____	_____	_____
1010	316	60452 REINF. STEEL BRIDGE APPR. SLAB	23,720.000 LB	_____	_____	_____	_____
1020	404	60490 BRIDGE DECK GROOVING	2,368.000 SY	_____	_____	_____	_____
1030	404	60495 COVER DEPTH SURVEY	2,100.000 SY	_____	_____	_____	_____
1040	405	61226 PREST.CONC.BEAM,BULB-T 45" DEPTH +100'-110'	24.000 EA	_____	_____	_____	_____
1050	406	61711 CORROSION RESISTANT REINF. STEEL CL. I	154,720.000 LB	_____	_____	_____	_____
1060	410	62033 RAILING.KANSAS CORRAL 32" W/OUT CURB	1,276.000 LF	_____	_____	_____	_____
1070	420	62412 ADHESIVE BASED JOINT SEALER CLASS I, 2"	120.000 LF	_____	_____	_____	_____
1080	ATTD	62534 BRIDGE SUPERSTRUCTURE ELASTIC INCLUSION 15"	118.000 SY	_____	_____	_____	_____
1090	401	64011 STRUCTURE EXCAVATION	1,212.000 CY	_____	_____	_____	_____
1100	401	64015 SELECT BACKFILL ABUTMENT ZONE	1,964.000 TON	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1110	401	64032 GEOCOMPOSITE WALL DRAIN	70.000 SY	_____	_____	_____	_____
1120	401	64036 PIPE UNDERDRAIN 6"	218.000 LF	_____	_____	_____	_____
1130	402	64040 SHEET PILES STEEL	12,055.000 SF	_____	_____	_____	_____
1140	402	64045 TEMPORARY SHEET PILING	8,725.000 SF	_____	_____	_____	_____
1150	403	64101 DYNAMIC PILE TEST	8.000 EA	_____	_____	_____	_____
1160	403	64114 STEEL PILES 14"	1,200.000 LF	_____	_____	_____	_____
1170	403	64775 PILE POINT FOR 14" STEEL PILE	24.000 EA	_____	_____	_____	_____
1180	403	64778 DRIVING TEST FOR 14" STEEL PILE	260.000 LF	_____	_____	_____	_____
1190	403	64875 PILE 54" PRECAST CYLINDER PILE	832.000 LF	_____	_____	_____	_____
1200	403	64875 PILE DRIVING TEST FOR 54" PRECAST CYLINDER PILE	436.000 LF	_____	_____	_____	_____
1210	404	65013 CONCRETE CLASS A3	57.200 CY	_____	_____	_____	_____
1220	404	65095 CONCRETE LOW SHRINKAGE CLASS A4 MOD.	151.200 CY	_____	_____	_____	_____
1230	406	65200 REINF. STEEL	27,300.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101495B62      Oversight/State Project No.: (NFO) 0671-087-610,C502, B622  
 Order No.: A98      Federal Project No.: BR-087-5(033), STP-087-5(044),

Contractor: \_\_\_\_\_

SECTION: 0001      ALL PROJECT ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1240	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	3,800.000 LB	_____	_____	_____	_____
1250	401	66120 COFFERDAM	12.000 EA	_____	_____	_____	_____
1260	414	66127 DRY RIPRAP CL.I 26"	11,008.000 TON	_____	_____	_____	_____
1270	413	67900 DISM.& REM. EX. STR. NO. 6213	LUMP SUM	LUMP SUM	_____	_____	_____
1280	413	67900 DISM.& REM. EX. STR. NO. 6214	LUMP SUM	LUMP SUM	_____	_____	_____
1290	ATTD	67904 BRIDGE INCIDENTALS CONSTRUCTION ACCESS (TEMPORARY WORK BRIDGE)B662	LUMP SUM	LUMP SUM	_____	_____	_____
1300	ATTD	67904 BRIDGE INCIDENTALS CONSTRUCTION ACCESS (TEMPORARY WORK BRIDGE)B666	LUMP SUM	LUMP SUM	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____
				<b>Total Bid:</b>	_____	_____	_____