

Schedule of Items

Proposal ID: C0000113639B20 Oversight/State Project No.: 9999-964-583,B618-620,C501
 Order No.: B60 Federal Project No.: NHPP-BR04(329)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	308	10099 AGGR. MATL. NO. 21A OR 21B	162.000 TON				
0030	315	10700 RUMBLE STRIP, ASPHALT	2,000.000 LF				
0040	505	13260 SALVAGE EXIST. GUARDRAIL	440.000 LF				
0050	505	13263 INSTALL SALVAGED GUARDRAIL	440.000 LF				
0060	505	13268 REMOVE EXISTING GUARDRAIL TERMINAL	6.000 EA				
0070	505	13392 FIXED OBJECT ATTACH. GR-FOA-2 TY. I	6.000 EA				
0080	315	16340 ASPHALT CONC. TY. SM-9.5D	42.000 TON				
0090	315	16370 ASPHALT CONC. TY. IM-19.0D	35.000 TON				
0100	315	16374 ASPH. CONC. TY. IM-19.0D T	89.000 TON				
0110	512	24160 TEMPORARY (CONSTRUCTION) SIGN	1,333.000 SF				
0120	512	24272 TRUCK MOUNTED ATTENUATOR	32.000 HR				
0130	512	24278 GROUP 2 CHANNELIZING DEVICES	4,088.000 DAY				

Schedule of Items

Proposal ID: C0000113639B20

Oversight/State Project No.: 9999-964-583,B618-620,C501

Order No.: B60

Federal Project No.: NHPP-BR04(329)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	948.000 HR	_____	_____	_____	_____
0150	512	24281 ELECTRONIC ARROW BOARD	756.000 HR	_____	_____	_____	_____
0160	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	2,105.000 SY	_____	_____	_____	_____
0170	510	24501 REMOVE EXIST. RUMBLE STRIP	2,000.000 LF	_____	_____	_____	_____
0180	704	54076 TYPE B CLASS VI PVMT LINE MRKG 6"	3,000.000 LF	_____	_____	_____	_____
0190	704	54080 TYPE B CLASS VI CONTRAST PVMT MRKG 6"	500.000 LF	_____	_____	_____	_____
0200	704	54100 PAVEMENT MARKING TYPE D, CLASS II TEMPORARY PAVEMENT MARKING 6"	9,686.000 LF	_____	_____	_____	_____
0210	704	54100 PAVEMENT MARKING TYPE D, CLASS II TEMPORARY PAVEMENT MARKING 8"	11,704.000 LF	_____	_____	_____	_____
0220	704	54100 PAVEMENT MARKING TYPE E TEMPORARY PAVEMENT MARKING 6"	18,609.000 LF	_____	_____	_____	_____
0230	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	3,100.000 LF	_____	_____	_____	_____
0240	704	54217 SNOW PLOW. RAISED PAVE. MARKER ASPH.CONC	70.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113639B20 Oversight/State Project No.: 9999-964-583,B618-620,C501
 Order No.: B60 Federal Project No.: NHPP-BR04(329)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	704	54218 SNOW PLOW. RAISED PAVE. MARKER HYD. CONC	30.000 EA	_____	_____	_____	_____
0260	404	68090 BRIDGE DECK GROOVING	3,604.000 SY	_____	_____	_____	_____
0270	412	68180 EMBEDDED GALVANIC ANODES	387.000 EA	_____	_____	_____	_____
0280	412	68225 PARAPET CLOSURE TYPE A	6.000 EA	_____	_____	_____	_____
0290	425	68317 TYPE A MILLING 1" - 1-1/2"	3,604.000 SY	_____	_____	_____	_____
0300	412	68339 DECK SLAB CLOSURE	67.000 SY	_____	_____	_____	_____
0310	420	68527 ADHESIVE BASED JOINT SEALER CLASS I, 1"	540.000 LF	_____	_____	_____	_____
0320	420	68528 ADHESIVE BASED JOINT SEALER CLASS I, 1 1/2"	106.000 LF	_____	_____	_____	_____
0330	425	68616 PLACE VERY EARLY STRENGTH LATEX MODIFIED CONCRETE OVERLAY	3,604.000 SY	_____	_____	_____	_____
0340	425, ATTD	68621 FURNISH VERY EARLY STRENGTH LATEX MOD. CONC. 1-1/2" - 2"	193.400 CY	_____	_____	_____	_____
0350	425	68644 TYPE A HYDRO-DEMOLITION 1/4" - 3/4"	3,604.000 SY	_____	_____	_____	_____
0360	512	68762 TRAF. BARR. SER. CONC. DOUBLE FACE PARAPET MB- 11A	5,114.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113639B20 Oversight/State Project No.: 9999-964-583,B618-620,C501
 Order No.: B60 Federal Project No.: NHPP-BR04(329)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0370	ATTD	68904 SUPERSTR. WID./REPAIR CLEAN DECK DRAINS	5.000 EA	_____	_____	_____	_____
0380	ATTD	68910 SUPERSTR. WID./REPAIR TY. C PATCHING (MOD)	20.000 SY	_____	_____	_____	_____
0390	406	69093 CORROSION RESISTANT REINF. STEEL CL. III	3,680.000 LB	_____	_____	_____	_____
0400	ATTD	70116 ASBESTOS REMOVAL FROM BRIDGE STRUCTURES (VA STR. # 2036)	LUMP SUM	LUMP SUM		_____	_____
0410	ATTD	70116 ASBESTOS REMOVAL FROM BRIDGE STRUCTURES (VA STR. # 2037)	LUMP SUM	LUMP SUM		_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____