

Schedule of Items

Proposal ID: C0000113032B27

Oversight/State Project No.: 0707-001-706,M501,B627

Order No.: C52

Federal Project No.: STP-001-5(066)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00111 CLEARING AND GRUBBING	0.080 ACRE				
0040	303	00120 REGULAR EXCAVATION	260.000 CY				
0050	303	00150 EMBANKMENT	62.000 CY				
0060	302	01272 27" CONC. PIPE	8.000 LF				
0070	ATTD	02112 DRAINAGE SUMP PIT	2.000 EA				
0080	414	09150 EROSION CONTROL STONE CLASS I, EC-1	50.000 TON				
0090	308	10128 AGGR. BASE MATL. TY. I NO. 21B	189.000 TON				
0100	315	10607 ASPHALT CONCRETE TY. SM-12.5A	83.000 TON				
0110	315	10642 ASPHALT CONCRETE TY. BM-25.0A	79.000 TON				
0120	315	11070 SAW-CUT ASPH CONC FULL DEPTH	34.000 LF				
0130	505	13280 GUARDRAIL GR-MGS1	218.000 LF				

Schedule of Items

Proposal ID: C0000113032B27

Oversight/State Project No.: 0707-001-706,M501,B627

Order No.: C52

Federal Project No.: STP-001-5(066)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	505	13286 GUARDRAIL TERMINAL GR-MGS2	1.000 EA	_____	_____	_____	_____
0150	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	7.000 EA	_____	_____	_____	_____
0160	505	13383 FIXED OBJECT ATTACH. GR-FOA-1 TY. I	4.000 EA	_____	_____	_____	_____
0170	511	24100 ALLAYING DUST	50.000 HR	_____	_____	_____	_____
0180	512	24152 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0190	512	24160 TEMPORARY (CONSTRUCTION) SIGN	700.000 SF	_____	_____	_____	_____
0200	512	24278 GROUP 2 CHANNELIZING DEVICES	250.000 DAY	_____	_____	_____	_____
0210	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	1,200.000 HR	_____	_____	_____	_____
0220	512	24288 WARNING LIGHT TY. B	1,500.000 DAY	_____	_____	_____	_____
0230	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	522.000 SY	_____	_____	_____	_____
0240	505	24600 REMOVE EXISTING GUARDRAIL	516.000 LF	_____	_____	_____	_____
0250	514	25506 FIELD OFFICE TY.II	11.000 MO	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113032B27

Oversight/State Project No.: 0707-001-706,M501,B627

Order No.: C52

Federal Project No.: STP-001-5(066)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM			
0270	ATTD	25567 PROGRESS SCHEDULE UPDATES	12.000 EA				
0280	602	27012 TOPSOIL CLASS A 2"	0.080 ACRE				
0290	603	27101 TEMPORARY SEED	8.000 LB				
0300	603	27102 REGULAR SEED	12.000 LB				
0310	603	27103 OVERSEEDING	10.000 LB				
0320	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	484.000 SY				
0330	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	387.000 SY				
0340	603	27230 FERTILIZER NITROGEN - N	8.000 LB				
0350	603	27231 FERTILIZER PHOSPHOROUS - P	11.000 LB				
0360	603	27232 FERTILIZER POTASSIUM - K	5.000 LB				
0370	603	27250 LIME	0.360 TON				
0380	ATTD	27275 EROSION CONTROL 60" HDPE TEMP. DIVERSION PIPE	192.000 LF				

## Schedule of Items

Proposal ID: C0000113032B27

Oversight/State Project No.: 0707-001-706,M501,B627

Order No.: C52

Federal Project No.: STP-001-5(066)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	ATTD	27275 EROSION CONTROL SAND BAG DIKE	90.000 LF	_____	_____	_____	_____
0400	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	10.000 SY	_____	_____	_____	_____
0410	303	27430 SILTATION CONTROL EXCAVATION	83.000 CY	_____	_____	_____	_____
0420	303	27505 TEMP. SILT FENCE TYPE A	572.000 LF	_____	_____	_____	_____
0430	401	27510 COFFERDAM	2.000 EA	_____	_____	_____	_____
0440	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	12.000 CY	_____	_____	_____	_____
0450	404	60495 COVER DEPTH SURVEY	111.000 SY	_____	_____	_____	_____
0460	ATTD	61010 SHEAR KEYS	18.000 CF	_____	_____	_____	_____
0470	410	62080 RAILING, ILLINOIS STEEL	74.000 LF	_____	_____	_____	_____
0480	ATTD 405	62536 BRIDGE SUPERSTRUCTURE THREE-SIDED PRECAST CONCRETE BOX	LUMP SUM	LUMP SUM	_____	_____	_____
0490	401	64011 STRUCTURE EXCAVATION	936.000 CY	_____	_____	_____	_____
0500	401	64015 SELECT BACKFILL ABUTMENT ZONE	912.000 TON	_____	_____	_____	_____
0510	401	64032 GEOCOMPOSITE WALL DRAIN	54.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113032B27

Oversight/State Project No.: 0707-001-706,M501,B627

Order No.: C52

Federal Project No.: STP-001-5(066)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	401	64036 PIPE UNDERDRAIN 6"	122.000 LF	_____	_____	_____	_____
0530	403	64101 DYNAMIC PILE TEST	2.000 EA	_____	_____	_____	_____
0540	403	64818 DRIVING TEST FOR 14" PRESTR. CONC. PILE	164.000 LF	_____	_____	_____	_____
0550	404	65013 CONCRETE CLASS A3	126.200 CY	_____	_____	_____	_____
0560	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	15,500.000 LB	_____	_____	_____	_____
0570	410	65831 RAILING, ILLINOIS STEEL	60.000 LF	_____	_____	_____	_____
0580	414	66127 DRY RIPRAP CL.I 26"	338.000 TON	_____	_____	_____	_____
0590	413	67900 DISM.& REM. EX. STR. NO. 24320	LUMP SUM	LUMP SUM	_____	_____	_____

Section: 0001

Total: \_\_\_\_\_

SECTION: 0002 ALTERNATE 1 - PRESTRESSED 14" CONCRETE PILES WITH STAINLESS STEEL STRAND

Cat Alt Set ID: 0001 Cat Alt Mbr ID: 1

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0600	403	64514 PRESTR. CONC STAINLESS STEEL STRAND PILES 14"	1,720.000 LF	_____	_____	_____	_____

Section: 0002

Total: \_\_\_\_\_

Schedule of Items

Proposal ID: C0000113032B27

Oversight/State Project No.: 0707-001-706,M501,B627

Order No.: C52

Federal Project No.: STP-001-5(066)

Contractor: \_\_\_\_\_

SECTION: 0003

ALTERNATE 2 - PRESTRESSED 14" CONCRETE PILES

Cat Alt Set ID: 0001

WITH CFRP STRAND

Cat Alt Mbr ID: 2

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0610	403	64614 PRESTR. CONC CFRP STRAND PILES 14"	1,720.000 LF	_____	_____	_____	_____
<b>Section: 0003</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____