Proposal ID: C0000111298B10 **Oversight/State Project No.:** 0460-067-736, C501, B610
Order No.: C04 **Federal Project No.:** NHPP-BR04(332)

Contractor: _____

SECTION: Not Assigned to a Section
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM		_____	_____
0030	308	10100 AGGR. MATL. NO. 21B	6.000 TON	_____	_____	_____	_____
0040	315	10607 ASPHALT CONCRETE TY. SM-12.5A	2.000 TON	_____	_____	_____	_____
0050	315	10610 ASPHALT CONCRETE TY. IM-19.0A	2.000 TON	_____	_____	_____	_____
0060	512	24160 TEMPORARY (CONSTRUCTION) SIGN	635.000 SF	_____	_____	_____	_____
0070	512	24272 TRUCK MOUNTED ATTENUATOR	2,160.000 HR	_____	_____	_____	_____
0080	512	24278 GROUP 2 CHANNELIZING DEVICES	7,650.000 DAY	_____	_____	_____	_____
0090	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	4,320.000 HR	_____	_____	_____	_____
0100	512	24281 ELECTRONIC ARROW BOARD	4,320.000 HR	_____	_____	_____	_____
0110	512	24288 WARNING LIGHT TY. B	1,260.000 DAY	_____	_____	_____	_____
0120	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	20.000 LF	_____	_____	_____	_____

Proposal ID: C0000111298B10 **Oversight/State Project No.:** 0460-067-736, C501, B610
Order No.: C04 **Federal Project No.:** NHPP-BR04(332)

Contractor: _____

SECTION: Not Assigned to a Section
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0130	704	54079 TYPE B CLASS VI CONTRAST PVMT MRKG 4"	1,717.000 LF				
0140	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	1,717.000 LF				
0150	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	3,640.000 LF				
0160	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	977.000 LF				
0170	404	60495 COVER DEPTH SURVEY	1,728.000 SY				
0180	404	68090 BRIDGE DECK GROOVING	1,728.000 SY				
0190	412	68172 CRACK REPAIR TYPE B	171.000 LF				
0200	412	68180 EMBEDDED GALVANIC ANODES	40.000 EA				
0210	412	68226 PARAPET CLOSURE TYPE B	4.000 EA				
0220	425	68315 TYPE A MILLING 1-1/2"	1,728.000 SY				
0230	412	68332 H.E.S. PATCHING TYPE C	10.000 SY				
0240	412	68339 DECK SLAB CLOSURE	50.000 SY				
0250	411	68455 PRE.& SPOT COAT EX. STR. STR. NO. 1034	1,000.000 SF				

Proposal ID: C0000111298B10 **Oversight/State Project No.:** 0460-067-736, C501, B610
Order No.: C04 **Federal Project No.:** NHPP-BR04(332)

Contractor: _____

SECTION: Not Assigned to a Section
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0260	411	68472 RECOAT EX. STR. ENTIRE BRIDGE	LUMP SUM	LUMP SUM		_____	. _____
0270	411	68474 ENV. PROT. & HEALTH & SAFETY STR. NO. 1034	LUMP SUM	LUMP SUM		_____	. _____
0280	411	68476 ENV.& WORK. PROTECTION STR. NO. 1034	LUMP SUM	LUMP SUM		_____	. _____
0290	411	68490 DISPOSAL OF MATERIAL STR. NO. 1034	LUMP SUM	LUMP SUM		_____	. _____
0300	421	68550 ELASTOMERIC EXPANSION DAM 0" TO 2"	133.000 LF	_____	. _____	_____	. _____
0310	412	68572 RECONSTRUCT EXPANSION JOINT	133.000 LF	_____	. _____	_____	. _____
0320	412	68590 JACKING AND BLOCKING BEAM	30.000 EA	_____	. _____	_____	. _____
0330	425	68616 PLACE VERY EARLY STRENGTH LATEX MODIFIED CONCRETE OVERLAY	1,728.000 SY	_____	. _____	_____	. _____
0340	425	68621 FURNISH VERY EARLY STRENGTH LATEX MOD. CONC. 1 1/2" to 2"	96.000 CY	_____	. _____	_____	. _____
0350	425	68642 TYPE A HYDRO-DEMOLITION 1/2"	1,728.000 SY	_____	. _____	_____	. _____
0360	413	68900 REM. PORT. OF EX. STR. BRIDGE FEDERAL #12826	LUMP SUM	LUMP SUM		_____	. _____

Proposal ID: C0000111298B10 **Oversight/State Project No.:** 0460-067-736, C501, B610
Order No.: C04 **Federal Project No.:** NHPP-BR04(332)

Contractor: _____

SECTION: Not Assigned to a Section
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0370	ATTD	68904 SUPERSTR. WID./REPAIR REPLACE BEARING	30.000 EA	_____	_____	_____	_____
0380	ATTD	68908 SUPERSTR. WID./REPAIR PIER 3 TEMPORARY SHORING STRUCTURAL STEEL	LUMP SUM	LUMP SUM		_____	_____
0390	ATTD	68908 SUPERSTR. WID./REPAIR SUPERSTRUCTURE STEEL REPAIR	LUMP SUM	LUMP SUM		_____	_____
0400	412	69002 EMBEDDED GALVANIC ANODES	141.000 EA	_____	_____	_____	_____
0410	412	69030 CONCRETE CLASS A3	45.600 CY	_____	_____	_____	_____
0420	ATTD	69068 TEMP SUPPORT OF EXCAVATION PIER 3 ACCESS FOR TEMPORARY SHORING	LUMP SUM	LUMP SUM		_____	_____
0430	406	69091 CORROSION RESISTANT REINF. STEEL CL. I	8,440.000 LB	_____	_____	_____	_____
0440	412	69500 CONCRETE SUBSTRUCT. SURFACE REPAIR	42.000 SY	_____	_____	_____	_____
0450	415	69740 CONCRETE SLAB SLOPE PROTECTION 4"	140.000 SY	_____	_____	_____	_____
		Section:		**Total:**		_____	_____

Proposal ID: C0000111298B10 **Oversight/State Project No.:** 0460-067-736, C501, B610

Order No.: C04 **Federal Project No.:** NHPP-BR04(332)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
		Section: 0001		**Total:**		_____	._____
				Total Bid:		_____	._____