

Schedule of Items

Proposal ID: C0000109586N01B Oversight/State Project No.: HSIP-005-705, N501

Order No.: C41

Federal Project No.: HSIP-5118(298)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	ATTD	00124 ROCK EXCAVATION	5.000 CY				
0030	303	00125 GRADING	LUMP SUM	LUMP SUM			
0040	ATTD	00134 TEST EXCAVATION UTILITY TEST PIT (ASPHALT CONC. PAVEMENT)	6.000 EA				
0050	305	00140 BORROW EXCAVATION	2,500.000 CY				
0060	308	10128 AGGR. BASE MATL. TY. I NO. 21B	1,168.640 TON				
0070	310	10417 TACK COAT	59.720 GAL				
0080	315	10636 ASPHALT CONC.TY. SM-9.5D	33.370 TON				
0090	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	85.690 TON				
0100	ATTD	11070 SAW-CUT ASPH CONC (FULL DEPTH)	1,654.000 LF				
0110	502	12020 STD. CURB CG-2	756.000 LF				
0120	502	12600 STD. COMB. CURB & GUTTER CG-6	215.000 LF				
0130	502	12610 RADIAL COMB. CURB & GUTTER CG-6	385.000 LF				

Schedule of Items

Proposal ID: C0000109586N01B Oversight/State Project No.: HSIP-005-705, N501

Order No.: C41

Federal Project No.: HSIP-5118(298)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	504	13108 CG-12 DETECTABLE WARNING SURFACE	104.540 SY	_____	_____	_____	_____
0150	ATTD	13120 ENTRANCE GUTTER 7" HES	194.960 SY	_____	_____	_____	_____
0160	521	13215 MAILBOX POST, SINGLE	14.000 EA	_____	_____	_____	_____
0170	521	13216 MAILBOX POST, DOUBLE	1.000 EA	_____	_____	_____	_____
0180	521	13217 MAILBOX POST, MULTIPLE	2.000 EA	_____	_____	_____	_____
0190	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	2,853.220 SY	_____	_____	_____	_____
0200	504	13222 HYDRAULIC CEMENT CONC. SIDEWALK 7"	164.440 SY	_____	_____	_____	_____
0210	505	13282 GUARDRAIL GR-MGS1, 9' POST	687.500 LF	_____	_____	_____	_____
0220	505	13286 GUARDRAIL TERMINAL GR- MGS2	6.000 EA	_____	_____	_____	_____
0230	510	13346 REMOVE GR-7 TERMINAL	1.000 EA	_____	_____	_____	_____
0240	ATTD	13401 GUARDRAIL TERMINAL SITE PREP (4-FT MODERATE)	6.000 EA	_____	_____	_____	_____
0250	ATTD	14100 REMOVE SIDEWALK AND ENTRANCE	405.310 SY	_____	_____	_____	_____
0260	ATTD	14120 REMOVE COMB. CURB AND GUTTER	601.370 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109586N01B Oversight/State Project No.: HSIP-005-705, N501

Order No.: C41

Federal Project No.: HSIP-5118(298)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	110.000 TON	_____	_____	_____	_____
0280	ATTD	14451 SAW CUT HYDRAULIC CEMENT CONCRETE ITEMS ...	1,941.000 LF	_____	_____	_____	_____
0290	512	24150 TYPE 3 BARRICADE 4'	52.000 EA	_____	_____	_____	_____
0300	512	24160 TEMPORARY (CONSTRUCTION) SIGN	322.000 SF	_____	_____	_____	_____
0310	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	20.000 DAY	_____	_____	_____	_____
0320	512	24272 TRUCK MOUNTED ATTENUATOR	1,760.000 HR	_____	_____	_____	_____
0330	512	24278 GROUP 2 CHANNELIZING DEVICES	12,300.000 DAY	_____	_____	_____	_____
0340	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	672.000 HR	_____	_____	_____	_____
0350	512	24281 ELECTRONIC ARROW BOARD	2,150.000 HR	_____	_____	_____	_____
0360	512	24282 FLAGGER SERVICE	340.000 HR	_____	_____	_____	_____
0370	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	275.780 SY	_____	_____	_____	_____
0380	505	24600 REMOVE EXISTING GUARDRAIL	450.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109586N01B Oversight/State Project No.: HSIP-005-705, N501

Order No.: C41

Federal Project No.: HSIP-5118(298)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	ATTD	24825 MODIFY EXIST. CONTROLLER CABINET	3.000 EA	_____	_____	_____	_____
0400	ATTD	25570 CONTRACT - PEDESTRIAN SHUTTLE SERVICE	LUMP SUM	LUMP SUM		_____	_____
0410	414	26119 DRY RIPRAP CL.I 18"	50.000 TON	_____	_____	_____	_____
0420	602	27023 TOPSOIL CLASS B	433.000 CY	_____	_____	_____	_____
0430	603	27102 REGULAR SEED	206.000 LB	_____	_____	_____	_____
0440	603	27103 OVERSEEDING	165.000 LB	_____	_____	_____	_____
0450	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	5,445.000 SY	_____	_____	_____	_____
0460	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	605.000 SY	_____	_____	_____	_____
0470	603	27230 FERTILIZER NITROGEN - N	77.000 LB	_____	_____	_____	_____
0480	603	27231 FERTILIZER PHOSPHOROUS - P	94.000 LB	_____	_____	_____	_____
0490	603	27232 FERTILIZER POTASSIUM - K	47.000 LB	_____	_____	_____	_____
0500	603	27250 LIME	3.500 TON	_____	_____	_____	_____
0510	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	2,500.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109586N01B Oversight/State Project No.: HSIP-005-705, N501

Order No.: C41

Federal Project No.: HSIP-5118(298)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	500.000 SY	_____	_____	_____	_____
0530	303	27415 CHECK DAM ROCK TY. II	10.000 EA	_____	_____	_____	_____
0540	303	27430 SILTATION CONTROL EXCAVATION	320.000 CY	_____	_____	_____	_____
0550	303	27461 INLET PROTECTION TYPE B	10.000 EA	_____	_____	_____	_____
0560	303	27505 TEMP. SILT FENCE TYPE A	3,000.000 LF	_____	_____	_____	_____
0570	701	50108 SIGN PANEL	326.000 SF	_____	_____	_____	_____
0580	700	50430 SIGN POST STP-1, 2", 14 GAUGE	399.000 LF	_____	_____	_____	_____
0590	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	69.000 LF	_____	_____	_____	_____
0600	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	74.000 EA	_____	_____	_____	_____
0610	ATTD	50610 RELOC. EXIST. SIGN STRUCT. TY. I	6.000 EA	_____	_____	_____	_____
0620	ATTD	50759 RELOC. EXIST. SIGN PANEL TY. SP-1	2.000 EA	_____	_____	_____	_____
0630	ATTD	50867 REMOVE-DISPOSE SIGN STRUCT. TY. WP-1	64.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109586N01B Oversight/State Project No.: HSIP-005-705, N501

Order No.: C41

Federal Project No.: HSIP-5118(298)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	703	51198 PEDESTRIAN ACTUATION PA- 2	1.000 EA	_____	_____	_____	_____
0650	703	51200 PEDESTRIAN ACTUATION PA- 4	9.000 EA	_____	_____	_____	_____
0660	700	51210 PEDESTAL POLE PF-2 10'	8.000 EA	_____	_____	_____	_____
0670	700	51240 CONCRETE FOUNDATION PF- 2	8.000 EA	_____	_____	_____	_____
0680	700	51602 14/4 CONDUCTOR CABLE	2,950.000 LF	_____	_____	_____	_____
0690	703	51838 HANGER ASSEMBLY SMB-3, ONE WAY	8.000 EA	_____	_____	_____	_____
0700	703	51839 HANGER ASSEMBLY SMB-3, TWO WAY	1.000 EA	_____	_____	_____	_____
0710	703	51937 REMOVE EXISTING MANHOLE/JUNCTION BOX	12.000 EA	_____	_____	_____	_____
0720	ATTD	51963 REMOVE EXIST. CONCRETE FOUNDATION	1.000 EA	_____	_____	_____	_____
0730	ATTD	51963 REMOVE EXIST. SIGNAL POLE	1.000 EA	_____	_____	_____	_____
0740	703	52403 PEDESTRIAN SIGNAL HEAD SP-8	10.000 EA	_____	_____	_____	_____
0750	704	54020 TYPE A PVMT LINE MRKG 4"	50.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109586N01B Oversight/State Project No.: HSIP-005-705, N501

Order No.: C41

Federal Project No.: HSIP-5118(298)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0760	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	600.000 LF	_____	_____	_____	_____
0770	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	166.000 LF	_____	_____	_____	_____
0780	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	1,568.000 LF	_____	_____	_____	_____
0790	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	198.000 SF	_____	_____	_____	_____
0800	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	2.000 EA	_____	_____	_____	_____
0810	704	54586 PVMT SYMB MRKG DBL TURN ARROW, LT/RT TY B, CL II	1.000 EA	_____	_____	_____	_____
0820	700	55587 JUNCTION BOX JB-S2	13.000 EA	_____	_____	_____	_____
0830	700	56050 BORED CONDUIT 2"	80.000 LF	_____	_____	_____	_____
0840	700	56051 BORED CONDUIT 3"	340.000 LF	_____	_____	_____	_____
0850	700	56053 2" PVC CONDUIT	150.000 LF	_____	_____	_____	_____
0860	700	56054 3" PVC CONDUIT	630.000 LF	_____	_____	_____	_____
0870	700	56200 TRENCH EXCAVATION ECI-1	140.000 LF	_____	_____	_____	_____
0880	700	56202 TRENCH EXCAVATION ECI-2	75.000 LF	_____	_____	_____	_____

Proposal ID: C0000109586N01B Oversight/State Project No.: HSIP-005-705, N501

Order No.: C41

Federal Project No.: HSIP-5118(298)

Contractor: _____

Section: 0001

Total: _____.

Total Bid: _____.