

Schedule of Items

Proposal ID: C0000110624B15

Oversight/State Project No.: 0011-060-587, B615, M501

Order No.: D26

Federal Project No.: STP-BR02(444)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00111 CLEARING AND GRUBBING	0.100 ACRE				
0040	303	00120 REGULAR EXCAVATION	759.000 CY				
0050	305	00140 BORROW EXCAVATION	135.000 CY				
0060	302	01156 STORM SEWER PIPE 15"	470.000 LF				
0070	302	07506 DROP INLET DI-5	2.000 EA				
0080	308	10065 AGGR. MATL. NO. 1	417.000 TON				
0090	308	10128 AGGR. BASE MATL. TY. I NO. 21B	414.000 TON				
0100	315	10611 ASPHALT CONCRETE TY. IM- 19.0D	135.000 TON				
0110	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	138.000 SY				
0120	315	10636 ASPHALT CONC.TY. SM-9.5D	34.000 TON				
0130	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	453.000 TON				

Schedule of Items

Proposal ID: C0000110624B15 Oversight/State Project No.: 0011-060-587, B615, M501
 Order No.: D26 Federal Project No.: STP-BR02(444)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	315	11070 SAW-CUT ASPH CONC FULL DEPTH	700.000 LF	_____	_____	_____	_____
0150	502	12322 ASPHALT CONC. CURB TY. MC-3B	50.000 LF	_____	_____	_____	_____
0160	505	13282 GUARDRAIL GR-MGS1, 9' POST	425.000 LF	_____	_____	_____	_____
0170	505	13286 GUARDRAIL TERMINAL GR-MGS2	6.000 EA	_____	_____	_____	_____
0180	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	6.000 EA	_____	_____	_____	_____
0190	505	13349 GUARDRAIL TERMINAL SITE PREPARATION	6.000 EA	_____	_____	_____	_____
0200	505	13383 FIXED OBJECT ATTACH. GR-FOA-1 TY. I	4.000 EA	_____	_____	_____	_____
0210	505	13384 FIXED OBJECT ATTACH. GR-FOA-1 TY. II	2.000 EA	_____	_____	_____	_____
0220	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	1,137.000 LF	_____	_____	_____	_____
0230	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	1.000 EA	_____	_____	_____	_____
0240	511	24100 ALLAYING DUST	300.000 HR	_____	_____	_____	_____
0250	512	24152 TYPE 3 BARRICADE 8'	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110624B15

Oversight/State Project No.: 0011-060-587, B615, M501

Order No.: D26

Federal Project No.: STP-BR02(444)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	512	24160 TEMPORARY (CONSTRUCTION) SIGN	753.000 SF	_____	_____	_____	_____
0270	512	24278 GROUP 2 CHANNELIZING DEVICES	47,100.000 DAY	_____	_____	_____	_____
0280	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	672.000 HR	_____	_____	_____	_____
0290	512	24281 ELECTRONIC ARROW BOARD	14,400.000 HR	_____	_____	_____	_____
0300	512	24282 FLAGGER SERVICE	600.000 HR	_____	_____	_____	_____
0310	512	24288 WARNING LIGHT TY. B	300.000 DAY	_____	_____	_____	_____
0320	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	1,150.000 SY	_____	_____	_____	_____
0330	505	24600 REMOVE EXISTING GUARDRAIL	859.000 LF	_____	_____	_____	_____
0340	514	25507 FIELD OFFICE TY.III	12.000 MO	_____	_____	_____	_____
0350	414	26119 DRY RIPRAP CL.I 18"	4.000 TON	_____	_____	_____	_____
0360	602	27012 TOPSOIL CLASS A 2"	0.300 ACRE	_____	_____	_____	_____
0370	603	27101 TEMPORARY SEED	30.000 LB	_____	_____	_____	_____
0380	603	27102 REGULAR SEED	54.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110624B15

Oversight/State Project No.: 0011-060-587, B615, M501

Order No.: D26

Federal Project No.: STP-BR02(444)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	603	27103 OVERSEEDING	43.000 LB	_____	_____	_____	_____
0400	603	27104 LEGUME SEED	20.000 LB	_____	_____	_____	_____
0410	603	27105 LEGUME OVERSEEDING	16.000 LB	_____	_____	_____	_____
0420	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,210.000 SY	_____	_____	_____	_____
0430	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,057.000 SY	_____	_____	_____	_____
0440	603	27230 FERTILIZER NITROGEN - N	29.000 LB	_____	_____	_____	_____
0450	603	27231 FERTILIZER PHOSPHOROUS - P	39.000 LB	_____	_____	_____	_____
0460	603	27232 FERTILIZER POTASSIUM - K	20.000 LB	_____	_____	_____	_____
0470	603	27250 LIME	1.350 TON	_____	_____	_____	_____
0480	303	27415 CHECK DAM ROCK TY. II	14.000 EA	_____	_____	_____	_____
0490	303	27430 SILTATION CONTROL EXCAVATION	328.000 CY	_____	_____	_____	_____
0500	303	27451 INLET PROTECTION TYPE A	3.000 EA	_____	_____	_____	_____
0510	303	27505 TEMP. SILT FENCE TYPE A	1,636.000 LF	_____	_____	_____	_____
0520	701	50108 SIGN PANEL	6.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110624B15

Oversight/State Project No.: 0011-060-587, B615, M501

Order No.: D26

Federal Project No.: STP-BR02(444)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	700	50320 REMOVE EXISTING 1 POST SIGN PANEL	2.000 EA	_____	_____	_____	_____
0540	700	50430 SIGN POST STP-1, 2", 14 GAUGE	18.000 LF	_____	_____	_____	_____
0550	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	2.000 EA	_____	_____	_____	_____
0560	704	54044 TYPE B CLASS II PAVE. LINE MARKING 6"	16,800.000 LF	_____	_____	_____	_____
0570	704	54056 TYPE B CLASS IV PVMT LINE MRKG 6"	1,071.000 LF	_____	_____	_____	_____
0580	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	14,820.000 LF	_____	_____	_____	_____
0590	512	54240 TEMP. PAVE. MARKER 1 WAY	92.000 EA	_____	_____	_____	_____
0600	512	54543 TYPE D, CLASS III TEMP. PVMT MRKG 6"	16,232.000 LF	_____	_____	_____	_____
0610	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	12,816.000 LF	_____	_____	_____	_____
0620	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	180.510 CY	_____	_____	_____	_____
0630	404	60490 BRIDGE DECK GROOVING	685.000 SY	_____	_____	_____	_____
0640	404	60495 COVER DEPTH SURVEY	685.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110624B15

Oversight/State Project No.: 0011-060-587, B615, M501

Order No.: D26

Federal Project No.: STP-BR02(444)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	406	61713 CORROSION RESISTANT REINF. STEEL CL. III	43,736.000 LB	_____	_____	_____	_____
0660	407	61800 STRUCT. STEEL SHEAR STUD REPLACEMENT	LUMP SUM	LUMP SUM	_____	_____	_____
0670	410	62010 CONCRETE PARAPET	414.000 LF	_____	_____	_____	_____
0680	420	62411 ADHESIVE BASED JOINT SEALER CLASS I, 1-1/2"	34.000 LF	_____	_____	_____	_____
0690	401	64011 STRUCTURE EXCAVATION	14.820 CY	_____	_____	_____	_____
0700	401	64015 SELECT BACKFILL ABUTMENT ZONE	12.900 TON	_____	_____	_____	_____
0710	404	65013 CONCRETE CLASS A3	4.720 CY	_____	_____	_____	_____
0720	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	150.000 LB	_____	_____	_____	_____
0730	217	66920 BRIDGE SUBSTRUCTURE STRUCTURAL GROUT	7.000 CY	_____	_____	_____	_____
0740	413	67900 DISM.& REM. EX. STR. NO. 1026	LUMP SUM	LUMP SUM	_____	_____	_____
0750	430	67910 NBIS ACCESS, UNDER BRIDGE INSPECTION ACCESS	1.000 DAY	_____	_____	_____	_____
0760	407	68115 STRUCT. STEEL BENT PLATE CONNECTOR	600.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110624B15

Oversight/State Project No.: 0011-060-587, B615, M501

Order No.: D26

Federal Project No.: STP-BR02(444)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0770	ATTD	68155 REPLACE DIAPHRAGM	16.000 EA	_____	_____	_____	_____
0780	426	68193 RESET EXIST. ROCKER EXPANSION BEARING	5.000 EA	_____	_____	_____	_____
0790	411	68455 PRE.& SPOT COAT EX. STR. NO. 1026	1,516.000 SF	_____	_____	_____	_____
0800	413	68476 ENV.& WORK. PROTECTION STR. NO. 1026	LUMP SUM	LUMP SUM	_____	_____	_____
0810	411	68490 DISPOSAL OF MATERIAL STR. NO. 1026	LUMP SUM	LUMP SUM	_____	_____	_____
0820	412	68590 JACKING AND BLOCKING BEAM	5.000 EA	_____	_____	_____	_____
0830	412	69500 CONCRETE SUBSTRUCT. SURFACE REPAIR	12.000 SY	_____	_____	_____	_____
0840	ATTD,107	80040 RAILWAY FLAGGER AND WATCHPERSON SERVICE	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____