

Schedule of Items

Proposal ID: C0000111392B46

Oversight/State Project No.: 0743-016-638,M501,B646

Order No.: D30

Federal Project No.: STP-016-6(061)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description                      | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
|                      |          |  |                                | Dollars    | Cents | Dollars    | Cents |
| 0010                 | 513      | 00100 MOBILIZATION                       | LUMP SUM                       | LUMP SUM   |       |            |       |
| 0020                 | 517      | 00102 CONSTRUCTION SURVEYING MIN.-PLAN   | LUMP SUM                       | LUMP SUM   |       |            |       |
| 0030                 | 303      | 00125 GRADING                            | LUMP SUM                       | LUMP SUM   |       |            |       |
| 0040                 | 305      | 00140 BORROW EXCAVATION                  | 285.000 CY                     |            |       |            |       |
| 0050                 | 308      | 10128 AGGR. BASE MATL. TY. I NO. 21B     | 644.000 TON                    |            |       |            |       |
| 0060                 | 502      | 13460 MEDIAN BARRIER MB-7D               | 40.000 LF                      |            |       |            |       |
| 0070                 | ATTD     | 14260 CRUSHER RUN AGGREGATE NO. 25 OR 26 | 18.000 TON                     |            |       |            |       |
| 0080                 | 512      | 24152 TYPE 3 BARRICADE 8'                | 4.000 EA                       |            |       |            |       |
| 0090                 | 512      | 24160 TEMPORARY (CONSTRUCTION) SIGN      | 182.500 SF                     |            |       |            |       |
| 0100                 | 512      | 24278 GROUP 2 CHANNELIZING DEVICES       | 7,300.000 DAY                  |            |       |            |       |
| 0110                 | 512      | 24282 FLAGGER SERVICE                    | 500.000 HR                     |            |       |            |       |
| 0120                 | 508      | 24400 OBSCURING ROADWAY                  | 4.000 UNIT                     |            |       |            |       |
| 0130                 | 514      | 25505 FIELD OFFICE TY.I                  | 9.000 MO                       |            |       |            |       |

Schedule of Items

Proposal ID: C0000111392B46

Oversight/State Project No.: 0743-016-638,M501,B646

Order No.: D30

Federal Project No.: STP-016-6(061)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description                              | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
|                      |          |  |                                | Dollars    | Cents | Dollars    | Cents |
| 0140                 | 603      | 27101<br>TEMPORARY SEED                          | 19.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0150                 | 603      | 27102<br>REGULAR SEED                            | 13.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0160                 | 603      | 27103<br>OVERSEEDING                             | 10.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0170                 | 603      | 27230<br>FERTILIZER NITROGEN - N                 | 10.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0180                 | 603      | 27231<br>FERTILIZER PHOSPHOROUS - P              | 15.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0190                 | 603      | 27232<br>FERTILIZER POTASSIUM - K                | 7.000<br>LB                    | _____      | _____ | _____      | _____ |
| 0200                 | 603      | 27250<br>LIME                                    | 0.470<br>TON                   | _____      | _____ | _____      | _____ |
| 0210                 | 606      | 27318<br>ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1 | 340.000<br>SY                  | _____      | _____ | _____      | _____ |
| 0220                 | 303      | 27415<br>CHECK DAM ROCK TY. II                   | 6.000<br>EA                    | _____      | _____ | _____      | _____ |
| 0230                 | 303      | 27422<br>DEWATERING BASIN EC-8                   | 2.000<br>EA                    | _____      | _____ | _____      | _____ |
| 0240                 | 303      | 27430<br>SILTATION CONTROL EXCAVATION            | 39.000<br>CY                   | _____      | _____ | _____      | _____ |
| 0250                 | 303      | 27505<br>TEMP. SILT FENCE TYPE A                 | 290.000<br>LF                  | _____      | _____ | _____      | _____ |
| 0260                 | 701      | 50108<br>SIGN PANEL                              | 42.250<br>SF                   | _____      | _____ | _____      | _____ |
| 0270                 | 700      | 50300<br>REMOVE EXISTING 1 POST SIGN STRUCTURE   | 7.000<br>EA                    | _____      | _____ | _____      | _____ |

Schedule of Items

Proposal ID: C0000111392B46

Oversight/State Project No.: 0743-016-638,M501,B646

Order No.: D30

Federal Project No.: STP-016-6(061)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description                                | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
|                      |          |  |                                | Dollars    | Cents | Dollars    | Cents |
| 0280                 | 700      | 50430<br>SIGN POST STP-1, 2", 14 GAUGE             | 92.000<br>LF                   | _____      | _____ | _____      | _____ |
| 0290                 | 700      | 50485<br>CONCRETE SIGN FOUNDATION STP-1, TYPE A    | 13.000<br>EA                   | _____      | _____ | _____      | _____ |
| 0300                 | 404      | 60409<br>CONC. CLASS A4 MOD. LOW SHRINKAGE         | 60.000<br>CY                   | _____      | _____ | _____      | _____ |
| 0310                 | 404      | 60490<br>BRIDGE DECK GROOVING                      | 171.100<br>SY                  | _____      | _____ | _____      | _____ |
| 0320                 | 404      | 60495<br>COVER DEPTH SURVEY                        | 171.000<br>SY                  | _____      | _____ | _____      | _____ |
| 0330                 | 405      | 61208<br>PREST.CONC.BEAM,BULB-T 29" DEPTH +60'-70' | 3.000<br>EA                    | _____      | _____ | _____      | _____ |
| 0340                 | 406      | 61711<br>CORROSION RESISTANT REINF. STEEL CL. I    | 10,650.000<br>LB               | _____      | _____ | _____      | _____ |
| 0350                 | 410      | 62033<br>RAILING.KANSAS CORRAL 32" W/OUT CURB      | 150.000<br>LF                  | _____      | _____ | _____      | _____ |
| 0360                 | 401      | 64011<br>STRUCTURE EXCAVATION                      | 356.000<br>CY                  | _____      | _____ | _____      | _____ |
| 0370                 | ATTD     | 64021<br>ELASTIC INCLUSION                         | 3.000<br>CY                    | _____      | _____ | _____      | _____ |
| 0380                 | 401      | 64032<br>GEOCOMPOSITE WALL DRAIN                   | 54.000<br>SY                   | _____      | _____ | _____      | _____ |
| 0390                 | ATTD 403 | 64038<br>PREBORING PILE .                          | 216.000<br>LF                  | _____      | _____ | _____      | _____ |
| 0400                 | 403      | 64110<br>STEEL PILES 10"                           | 234.000<br>LF                  | _____      | _____ | _____      | _____ |

Schedule of Items

Proposal ID: C0000111392B46

Oversight/State Project No.: 0743-016-638,M501,B646

Order No.: D30

Federal Project No.: STP-016-6(061)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description  | Approximate Quantity and Units | Unit Price        |       | Bid Amount |       |
|----------------------|----------|--|--------------------------------|-------------------|-------|------------|-------|
|                      |          |  |                                | Dollars           | Cents | Dollars    | Cents |
| 0410                 | 404      | 65013<br>CONCRETE CLASS A3                                   | 81.100<br>CY                   | _____             | _____ | _____      | _____ |
| 0420                 | 406      | 65200<br>REINF. STEEL  | 8,200.000<br>LB                | _____             | _____ | _____      | _____ |
| 0430                 | ATTD     | 66115<br>TEMP. CAUSEWAY                                      | LUMP SUM                       | LUMP SUM          | _____ | _____      | _____ |
| 0440                 | 414      | 66127<br>DRY RIPRAP CL.I 26"                                 | 180.000<br>TON                 | _____             | _____ | _____      | _____ |
| 0450                 | ATTD     | 67900<br>DISM.& REM. EX. STR.<br>STRUCTURE NO. 6028          | LUMP SUM                       | LUMP SUM          | _____ | _____      | _____ |
| 0460                 | 430      | 67910<br>NBIS ACCESS, UNDER<br>BRIDGE STRUCTURE NO.<br>6028  | 1.000<br>DAY                   | _____             | _____ | _____      | _____ |
| 0470                 | 411      | 68476<br>ENV.& WORK. PROTECTION<br>STRUCTURE NO. 6028        | LUMP SUM                       | LUMP SUM          | _____ | _____      | _____ |
| 0480                 | 401      | 69014<br>SELECT BACKFILL<br>ABUTMENT ZONE                    | 576.000<br>TON                 | _____             | _____ | _____      | _____ |
| 0490                 | ATTD     | 69068<br>TEMP SUPPORT OF<br>EXCAVATION STRUCTURE<br>NO. 6028 | LUMP SUM                       | LUMP SUM          | _____ | _____      | _____ |
| <b>Section: 0001</b> |          |  |                                | <b>Total:</b>     | _____ | _____      | _____ |
|                      |          |  |                                | <b>Total Bid:</b> | _____ | _____      | _____ |