

Schedule of Items

Proposal ID: C0000101043B60      Oversight/State Project No.: 0681-005-644, B660  
 Order No.: D24      Federal Project No.: STP-BR03(342)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	308	10128 AGGR. BASE MATL. TY. I NO. 21B	29.000 TON				
0030	315	10608 ASPHALT CONCRETE TY. SM-12.5D	17.000 TON				
0040	515	10625 FLEXIBLE PAVE. TIE-IN PLANING 0" - 2"	100.000 SY				
0050	315	10642 ASPHALT CONCRETE TY. BM-25.0A	14.000 TON				
0060	315	11070 SAW-CUT ASPH CONC FULL DEPTH	50.000 LF				
0070	502	12030 STD. CURB CG-3	54.000 LF				
0080	505	13280 GUARDRAIL GR-MGS1	13.000 LF				
0090	505	13286 GUARDRAIL TERMINAL GR-MGS2	2.000 EA				
0100	505	13349 GUARDRAIL TERMINAL SITE PREPARATION	2.000 EA				
0110	505	13394 FIXED OBJECT ATTACH. GR-FOA-5	2.000 EA				
0120	512	13495 TRAF. BARR. SER. CONC. SINGLE FACE PAR.MB-10A	120.000 LF				

Schedule of Items

Proposal ID: C0000101043B60      Oversight/State Project No.: 0681-005-644, B660  
 Order No.: D24      Federal Project No.: STP-BR03(342)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	90.000 LF	_____	_____	_____	_____
0140	512	13605 IMPACT ATTEN. SER. TY. 1 TL-2, <40 MPH	4.000 EA	_____	_____	_____	_____
0150	512	24152 TYPE 3 BARRICADE 8'	2.000 EA	_____	_____	_____	_____
0160	512	24160 TEMPORARY (CONSTRUCTION) SIGN	1,660.000 SF	_____	_____	_____	_____
0170	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	20.000 DAY	_____	_____	_____	_____
0180	512	24278 GROUP 2 CHANNELIZING DEVICES	2,520.000 DAY	_____	_____	_____	_____
0190	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	672.000 HR	_____	_____	_____	_____
0200	512	24282 FLAGGER SERVICE	80.000 HR	_____	_____	_____	_____
0210	512	24288 WARNING LIGHT TY. B	600.000 DAY	_____	_____	_____	_____
0220	512	24333 TEMPORARY TRAFFIC CONTROL SIGNAL STR. NO. 6068	LUMP SUM	LUMP SUM	_____	_____	_____
0230	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	62.000 SY	_____	_____	_____	_____
0240	303	27430 SILTATION CONTROL EXCAVATION	66.000 CY	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000101043B60      Oversight/State Project No.: 0681-005-644, B660  
 Order No.: D24      Federal Project No.: STP-BR03(342)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	303	27505 TEMP. SILT FENCE TYPE A	386.000 LF	_____	_____	_____	_____
0260	701	50108 SIGN PANEL	6.000 SF	_____	_____	_____	_____
0270	700	50430 SIGN POST STP-1, 2", 14 GAUGE	18.000 LF	_____	_____	_____	_____
0280	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	2.000 EA	_____	_____	_____	_____
0290	704	54020 TYPE A PVMT LINE MRKG 4"	1,380.000 LF	_____	_____	_____	_____
0300	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	1,380.000 LF	_____	_____	_____	_____
0310	512	54466 TYPE E TEMP. PVMT MRKG 6"	1,200.000 LF	_____	_____	_____	_____
0320	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	1,679.000 LF	_____	_____	_____	_____
0330	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	574.000 LF	_____	_____	_____	_____
0340	512	54548 TYPE D, CLASS III TEMP. PVMT MRKG 24"	66.000 LF	_____	_____	_____	_____
0350	410	62034 RAILING, CPSR 2 RAIL	94.000 LF	_____	_____	_____	_____
0360	ATTD	67400 DECK DRAINAGE SYSTEM	LUMP SUM	LUMP SUM	_____	_____	_____
0370	404	68043 CONC. CLASS A4 MOD.LOW SHRINKAGE	42.200 CY	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000101043B60 Oversight/State Project No.: 0681-005-644, B660

Order No.: D24

Federal Project No.: STP-BR03(342)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	404	68085 COVER DEPTH SURVEY	168.000 SY	_____	_____	_____	_____
0390	404	68090 BRIDGE DECK GROOVING	168.000 SY	_____	_____	_____	_____
0400	406	68091 CORROSION RESISTANT REINF. STEEL CL. I	11,090.000 LB	_____	_____	_____	_____
0410	426	68202 PARTIAL BEAM/GIRDER REPLACEMENT	2,300.000 LB	_____	_____	_____	_____
0420	411	68472 RECOAT EX. STR. STR. NO. 6068	LUMP SUM	LUMP SUM	_____	_____	_____
0430	411	68474 ENV. PROT. & HEALTH & SAFETY STR. NO. 6068	LUMP SUM	LUMP SUM	_____	_____	_____
0440	413	68476 ENV. & WORK. PROTECTION STR. NO. 6068	LUMP SUM	LUMP SUM	_____	_____	_____
0450	411	68490 DISPOSAL OF MATERIAL STR. NO. 6068	LUMP SUM	LUMP SUM	_____	_____	_____
0460	413	68492 MATERIAL DISPOSAL STR. NO. 6068 TYPE B	LUMP SUM	LUMP SUM	_____	_____	_____
0470	413	68900 REM. PORT. OF EX. STR. STR. NO. 6068	LUMP SUM	LUMP SUM	_____	_____	_____
0480	412	69002 EMBEDDED GALVANIC ANODES	20.000 EA	_____	_____	_____	_____
0490	401	69011 STRUCTURE EXCAVATION	12.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101043B60

Oversight/State Project No.: 0681-005-644, B660

Order No.: D24

Federal Project No.: STP-BR03(342)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0500	401	69014 SELECT BACKFILL ABUTMENT ZONE	24.000 TON	_____	_____	_____	_____
0510	412	69030 CONCRETE CLASS A3	1.400 CY	_____	_____	_____	_____
0520	406	69100 REINF. STEEL	160.000 LB	_____	_____	_____	_____
0530	412	69500 CONCRETE SUBSTRUCT. SURFACE REPAIR	4.000 SY	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	
				<b>Total Bid:</b>		_____	