

Schedule of Items

Proposal ID: C0000109537C01 Oversight/State Project No.: 6015-073-616, C501
 Order No.: D28 Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	00096 MOBILIZATION SITE MOBILIZATION FOR UPC: 109535	1.000 EA	_____	_____	_____	_____
0020	ATTD	00096 MOBILIZATION SITE MOBILIZATION FOR UPC: 109537	1.000 EA	_____	_____	_____	_____
0030	303	00120 REGULAR EXCAVATION	15,346.000 CY	_____	_____	_____	_____
0040	303	00136 BORROW EXCAVATION	1,885.000 CY	_____	_____	_____	_____
0050	ATTD	00160 GRADING CLEARING & GRUBBING FOR UPC: 109537	LUMP SUM	LUMP SUM	_____	_____	_____
0060	ATTD	00160 GRADING CLEARING & GRUBBING FOR UPC:109535	LUMP SUM	LUMP SUM	_____	_____	_____
0070	302 504	00525 CONCRETE CLASS A3 MISC.	3.100 CY	_____	_____	_____	_____
0080	509	00529 FLOWABLE BACKFILL	5.530 CY	_____	_____	_____	_____
0090	501	00580 UNDERDRAIN UD-1	1,153.000 LF	_____	_____	_____	_____
0100	501	00595 OUTLET PIPE	80.000 LF	_____	_____	_____	_____
0110	302	01120 12" PIPE	78.000 LF	_____	_____	_____	_____
0120	302	01122 12" CONC. PIPE	22.000 LF	_____	_____	_____	_____
0130	302	01152 15" CONC. PIPE	237.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109537C01

Oversight/State Project No.: 6015-073-616, C501

Order No.: D28

Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	01156 STORM SEWER PIPE 15"	497.000 LF	_____	_____	_____	_____
0150	302	01180 18" PIPE	57.000 LF	_____	_____	_____	_____
0160	302	01182 18" CONC. PIPE	64.000 LF	_____	_____	_____	_____
0170	302	01186 STORM SEWER PIPE 18"	136.000 LF	_____	_____	_____	_____
0180	302	01246 STORM SEWER PIPE 24"	175.000 LF	_____	_____	_____	_____
0190	302	06120 12" END SECTION ES-1 OR 2	4.000 EA	_____	_____	_____	_____
0200	302	06151 15" END SECTION ES-1	3.000 EA	_____	_____	_____	_____
0210	302	06180 18" END SECTION ES-1 OR 2	3.000 EA	_____	_____	_____	_____
0220	302	06181 18" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0230	302	06241 24" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0240	302	06815 DROP INLET DI-3A	4.000 EA	_____	_____	_____	_____
0250	302	06817 DROP INLET DI-3B,L=4'	4.000 EA	_____	_____	_____	_____
0260	302	06818 DROP INLET DI-3B,L=6'	4.000 EA	_____	_____	_____	_____
0270	302	06819 DROP INLET DI-3B,L=8'	4.000 EA	_____	_____	_____	_____
0280	302	06835 DROP INLET DI-3C,L=6'	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109537C01 Oversight/State Project No.: 6015-073-616, C501
 Order No.: D28 Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	302	06836 DROP INLET DI-3C,L=8'	1.000 EA	_____	_____	_____	_____
0300	302	09056 MANHOLE MH-1 OR 2	13.000 LF	_____	_____	_____	_____
0310	302	09057 FRAME & COVER MH-1	3.000 EA	_____	_____	_____	_____
0320	414	09150 EROSION CONTROL STONE CLASS I, EC-1	71.000 TON	_____	_____	_____	_____
0330	308	10128 AGGR. BASE MATL. TY. I NO. 21B	3,624.000 TON	_____	_____	_____	_____
0340	315	10611 ASPHALT CONCRETE TY. IM-19.0D	842.000 TON	_____	_____	_____	_____
0350	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	4,057.000 SY	_____	_____	_____	_____
0360	315	10636 ASPHALT CONC.TY. SM-9.5D	1,142.000 TON	_____	_____	_____	_____
0370	315	10642 ASPHALT CONCRETE TY. BM-25.0A	2,902.000 TON	_____	_____	_____	_____
0380	217 ATTD	10985 HYDRAULIC CEM. CONC. COLORED AND STAMPED	382.000 SY	_____	_____	_____	_____
0390	315	11070 SAW-CUT ASPH CONC SAW CUT TO 10" DEPTH	1,414.000 LF	_____	_____	_____	_____
0400	315	11070 SAW-CUT ASPH CONC SAW CUT TO 12" DEPTH	1,857.000 LF	_____	_____	_____	_____
0410	502	12020 STD. CURB CG-2	148.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109537C01 Oversight/State Project No.: 6015-073-616, C501
 Order No.: D28 Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	502	12022 RADIAL CURB CG-2	217.000 LF	_____	_____	_____	_____
0430	502	12032 RADIAL CURB CG-3	277.000 LF	_____	_____	_____	_____
0440	502	12600 STD. COMB. CURB & GUTTER CG-6	499.000 LF	_____	_____	_____	_____
0450	502	12610 RADIAL COMB. CURB & GUTTER CG-6	1,096.000 LF	_____	_____	_____	_____
0460	521	13215 MAILBOX POST, SINGLE	12.000 EA	_____	_____	_____	_____
0470	521	13217 MAILBOX POST, MULTIPLE	1.000 EA	_____	_____	_____	_____
0480	ATTD	15309 PAVEMENT LIQUID ASPHALT COATING (PAVEMENT MARKER GROOVE)	55.000 SY	_____	_____	_____	_____
0490	315	16300 RUMBLE STRIP, ASPHALT	1,487.000 LF	_____	_____	_____	_____
0500	315	16301 LIQ.ASPH. RUMBLE STRIP COATING	320.000 SY	_____	_____	_____	_____
0510	502	21110 MEDIAN STRIP MS-1A	288.000 SY	_____	_____	_____	_____
0520	511	24100 ALLAYING DUST	800.000 HR	_____	_____	_____	_____
0530	512	24150 TYPE 3 BARRICADE 4'	2.000 EA	_____	_____	_____	_____
0540	512	24152 TYPE 3 BARRICADE 8'	8.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109537C01 Oversight/State Project No.: 6015-073-616, C501
 Order No.: D28 Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0550	512	24160 TEMPORARY (CONSTRUCTION) SIGN	1,988.000 SF	_____	_____	_____	_____
0560	512	24260 CR. RUN AGGR. NO. 25 OR 26	736.000 TON	_____	_____	_____	_____
0570	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	730.000 DAY	_____	_____	_____	_____
0580	512	24278 GROUP 2 CHANNELIZING DEVICES	25,800.000 DAY	_____	_____	_____	_____
0590	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	2,016.000 HR	_____	_____	_____	_____
0600	512	24282 FLAGGER SERVICE	8,260.000 HR	_____	_____	_____	_____
0610	512	24288 WARNING LIGHT TY. B	270.000 DAY	_____	_____	_____	_____
0620	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	4,666.000 SY	_____	_____	_____	_____
0630	510	24502 REMOVE EXIST. / DISPOSE EXISTING FLASHING BEACON ASSEMBLY SIGN FOUNDATION	2.000 EA	_____	_____	_____	_____
0640	510	24502 REMOVE EXIST. & SALVAGE TRAFFIC CAMERA & OPTICON ASSEMBLY	7.000 EA	_____	_____	_____	_____
0650	510 ATTD	24505 RELOCATE EXIST. & RESET EXISTING LIGHT POLES	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109537C01 Oversight/State Project No.: 6015-073-616, C501
 Order No.: D28 Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	510	24801 REMOVE EX. DROP INLET SHOWN ON PLANS	2.000 EA	_____	_____	_____	_____
0670	514	25506 FIELD OFFICE TY.II	21.000 MO	_____	_____	_____	_____
0680	603	27101 TEMPORARY SEED	207.000 LB	_____	_____	_____	_____
0690	603	27102 REGULAR SEED	270.000 LB	_____	_____	_____	_____
0700	603	27103 OVERSEEDING	216.000 LB	_____	_____	_____	_____
0710	603	27104 LEGUME SEED	5.000 LB	_____	_____	_____	_____
0720	603	27105 LEGUME OVERSEEDING	4.000 LB	_____	_____	_____	_____
0730	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	3,140.000 SY	_____	_____	_____	_____
0740	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	14,794.000 SY	_____	_____	_____	_____
0750	603	27230 FERTILIZER NITROGEN - N	140.000 LB	_____	_____	_____	_____
0760	603	27231 FERTILIZER PHOSPHOROUS - P	200.000 LB	_____	_____	_____	_____
0770	603	27232 FERTILIZER POTASSIUM - K	100.000 LB	_____	_____	_____	_____
0780	603	27250 LIME	6.680 TON	_____	_____	_____	_____
0790	303	27284 EROSION CONTROL MULCH	237.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109537C01 Oversight/State Project No.: 6015-073-616, C501
 Order No.: D28 Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	604	27300 SOD	925.000 SY	_____	_____	_____	_____
0810	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	443.000 SY	_____	_____	_____	_____
0820	606	27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	904.000 SY	_____	_____	_____	_____
0830	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	49.000 SY	_____	_____	_____	_____
0840	606	27321 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 4	40.000 SY	_____	_____	_____	_____
0850	303	27410 CHECK DAM, ROCK TY. I	1.000 EA	_____	_____	_____	_____
0860	303	27415 CHECK DAM ROCK TY. II	36.000 EA	_____	_____	_____	_____
0870	303	27430 SILTATION CONTROL EXCAVATION	411.000 CY	_____	_____	_____	_____
0880	303	27461 INLET PROTECTION TYPE B	22.000 EA	_____	_____	_____	_____
0890	303	27505 TEMP. SILT FENCE TYPE A	1,792.000 LF	_____	_____	_____	_____
0900	ATTD	27548 STORM WATER MANAGEMENT (PERNAMENT CHECK DAM)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000109537C01

Oversight/State Project No.: 6015-073-616, C501

Order No.: D28

Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0910	ATTD	27548 STORM WATER MANAGEMENT CONCRETE CHECK DAM, FOUNDATION, ACCESSORIES INCLUDING STONE SPLASH PAD	LUMP SUM	LUMP SUM			
0920	ATTD	27548 STORM WATER MANAGEMENT PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION	LUMP SUM	LUMP SUM			
0930	ATTD	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION .	LUMP SUM	LUMP SUM			
0940	520	45532 6" STEEL ENCASE. PIPE	100.000 LF				
0950	701	50108 SIGN PANEL	300.000 SF				
0960	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	3.000 EA				
0970	700	50430 SIGN POST STP-1, 2", 14 GAUGE	222.000 LF				
0980	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	24.000 LF				
0990	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	88.000 LF				
1000	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	58.000 LF				

Schedule of Items

Proposal ID: C0000109537C01 Oversight/State Project No.: 6015-073-616, C501
 Order No.: D28 Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1010	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	28.000 EA	_____	_____	_____	_____
1020	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	10.000 EA	_____	_____	_____	_____
1030	ATTD	50759 RELOC. EXIST. SIGN PANEL TY. SP-1	4.000 EA	_____	_____	_____	_____
1040	ATTD	50867 REMOVE-DISPOSE SIGN STRUCT. TY. WP-1	28.000 EA	_____	_____	_____	_____
1050	ATTD	50868 REMOVE-DISPOSE SIGN STRUCT. TY. WP-2	4.000 EA	_____	_____	_____	_____
1060	704	50902 TRAFFIC SIGN RELOCATE EXISTING SIGN STRUCTURE TY. STP-1	3.000 EA	_____	_____	_____	_____
1070	703	51933 REMOVE EXISTING POLE	4.000 EA	_____	_____	_____	_____
1080	703	51934 REMOVE EXISTING FOUNDATION	4.000 EA	_____	_____	_____	_____
1090	703	51935 REMOVE EXISTING SIGNAL HEAD	9.000 EA	_____	_____	_____	_____
1100	703	51936 REMOVE EXISTING CONTROLLER	1.000 EA	_____	_____	_____	_____
1110	703	51937 REMOVE EXISTING MANHOLE/JUNCTION BOX	5.000 EA	_____	_____	_____	_____
1120	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	7,629.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109537C01 Oversight/State Project No.: 6015-073-616, C501
 Order No.: D28 Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1130	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	5,822.000 LF	_____	_____	_____	_____
1140	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	981.000 LF	_____	_____	_____	_____
1150	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	2,500.000 LF	_____	_____	_____	_____
1160	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	55.000 EA	_____	_____	_____	_____
1170	512	54428 TEMP. PVMT MRKG, TY. A, 4"	3,400.000 LF	_____	_____	_____	_____
1180	512	54430 TEMP. PVMT MRKG, TY. A, 6"	3,400.000 LF	_____	_____	_____	_____
1190	512	54432 TEMP. PVMT MRKG, TY. A, 8"	800.000 LF	_____	_____	_____	_____
1200	512	54440 TEMP. PVMT MRKG, TY. A, 24"	32.000 LF	_____	_____	_____	_____
1210	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	3,850.000 LF	_____	_____	_____	_____
1220	512	54543 TYPE D, CLASS III TEMP. PVMT MRKG 6"	3,885.000 LF	_____	_____	_____	_____
1230	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	800.000 LF	_____	_____	_____	_____
1240	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109537C01 Oversight/State Project No.: 6015-073-616, C501
 Order No.: D28 Federal Project No.: STP-073-3(050)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1250	704	54626 PVMT SYMB MRKG YIELD (2'x 3') TY B, CL II	40.000 EA	_____	_____	_____	_____
1260	ATTD	70520 ENVIR. PROTECTION MANAGEMENT OF PETROLEUM CONTAMINATED SOIL	LUMP SUM	LUMP SUM	_____	_____	_____
1270	ATTD	70525 ENVIR. PROTECTION TRANSPORTATION AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL	438.000 TON	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____