

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	40,006.000 CY				
0050	303	00128 EXTRA EXCAVATION	24.900 CY				
0060	305	00140 BORROW EXCAVATION	20,635.000 CY				
0070	ATTD	00505 BEDDING MATL. AGGR. NO. 25 OR 26	2.700 TON				
0080	ATTD	00507 BEDDING MATL. AGGR. NO. 57	103.900 TON				
0090	302 504	00525 CONCRETE CLASS A3 MISC.	54.000 CY				
0100	509	00529 FLOWABLE BACKFILL	12.000 CY				
0110	501	00585 UNDERDRAIN UD-2	2,400.000 LF				
0120	501	00588 UNDERDRAIN UD-4	4,857.000 LF				
0130	501	00591 CROSSDRAIN CD-2	128.000 LF				
0140	501	00595 OUTLET PIPE	150.000 LF				

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	01150 15" PIPE	12.000 LF	_____	_____	_____	_____
0160	302	01152 15" CONC. PIPE	1,219.000 LF	_____	_____	_____	_____
0170	302	01180 18" PIPE	54.000 LF	_____	_____	_____	_____
0180	302	01182 18" CONC. PIPE	1,522.000 LF	_____	_____	_____	_____
0190	302	01240 24" PIPE	180.000 LF	_____	_____	_____	_____
0200	302	01242 24" CONC. PIPE	2,637.000 LF	_____	_____	_____	_____
0210	302	01300 30" PIPE	43.000 LF	_____	_____	_____	_____
0220	302	01301 JACKED & BORED 30" PIPE	47.000 LF	_____	_____	_____	_____
0230	302	01302 30" CONC. PIPE	252.000 LF	_____	_____	_____	_____
0240	302	01362 36" CONC. PIPE	172.000 LF	_____	_____	_____	_____
0250	302	06151 15" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0260	302	06181 18" END SECTION ES-1	11.000 EA	_____	_____	_____	_____
0270	302	06241 24" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0280	302	06301 30" END SECTION ES-1	3.000 EA	_____	_____	_____	_____
0290	302	06817 DROP INLET DI-3B,L=4'	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0300	302	06818 DROP INLET DI-3B,L=6'	27.000 EA	_____	_____	_____	_____
0310	302	06819 DROP INLET DI-3B,L=8'	3.000 EA	_____	_____	_____	_____
0320	302	06820 DROP INLET DI-3B,L=10'	1.000 EA	_____	_____	_____	_____
0330	302	07114 DROP INLET DI-4B,L=10'	1.000 EA	_____	_____	_____	_____
0340	302	07130 DROP INLET DI-4BB,L=10'	1.000 EA	_____	_____	_____	_____
0350	302	07506 DROP INLET DI-5	2.000 EA	_____	_____	_____	_____
0360	302	07508 DROP INLET DI-7	1.000 EA	_____	_____	_____	_____
0370	302	07510 DROP INLET DI-7A	3.000 EA	_____	_____	_____	_____
0380	302	08185 DROP INLET DI-10G TY.I	2.000 EA	_____	_____	_____	_____
0390	302	09056 MANHOLE MH-1 OR 2	3.500 LF	_____	_____	_____	_____
0400	302	09057 FRAME & COVER MH-1	3.000 EA	_____	_____	_____	_____
0410	302	09065 MANHOLE PRECAST MANHOLE WITH WEIR WALL AND SWM-DR ORIFICE AND TRASH RACK	5.900 LF	_____	_____	_____	_____
0420	414	09150 EROSION CONTROL STONE CLASS I, EC-1	71.100 TON	_____	_____	_____	_____
0430	502	09215 PAVED DITCH PG-5	24.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0440	303	09250 SLOPE DRAIN	4.000 EA	_____	_____	_____	_____
0445	307	10011 HYDRAULIC CEMENT	351.000 TON	_____	_____	_____	_____
0450	307	10037 MANIPULATION 10"	15,608.000 SY	_____	_____	_____	_____
0460	313	10062 ASPH-STAB. OPEN-GRADED MATERIAL	1,697.000 TON	_____	_____	_____	_____
0470	308	10128 AGGR. BASE MATL. TY. I NO. 21B	5,979.000 TON	_____	_____	_____	_____
0480	315	10607 ASPHALT CONCRETE TY. SM-12.5A	540.000 TON	_____	_____	_____	_____
0490	315	10608 ASPHALT CONCRETE TY. SM-12.5D	4,519.000 TON	_____	_____	_____	_____
0500	315	10610 ASPHALT CONCRETE TY. IM-19.0A	3,516.000 TON	_____	_____	_____	_____
0510	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	22,667.000 SY	_____	_____	_____	_____
0520	315	10642 ASPHALT CONCRETE TY. BM-25.0A	5,170.000 TON	_____	_____	_____	_____
0530	315	11070 SAW-CUT ASPH CONC FULL DEPTH	9,517.000 LF	_____	_____	_____	_____
0540	502	12020 STD. CURB CG-2	405.000 LF	_____	_____	_____	_____
0550	502	12022 RADIAL CURB CG-2	20.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0560	502	12030 STD. CURB CG-3	92.000 LF	_____	_____	_____	_____
0570	502	12600 STD. COMB. CURB & GUTTER CG-6	4,453.000 LF	_____	_____	_____	_____
0580	502	12610 RADIAL COMB. CURB & GUTTER CG-6	1,212.000 LF	_____	_____	_____	_____
0590	504	13108 CG-12 DETECTABLE WARNING SURFACE	36.000 SY	_____	_____	_____	_____
0600	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	1,802.000 SY	_____	_____	_____	_____
0610	505	13280 GUARDRAIL GR-MGS1	718.000 LF	_____	_____	_____	_____
0620	505	13282 GUARDRAIL GR-MGS1, 9' POST	100.000 LF	_____	_____	_____	_____
0630	505	13283 RADIAL GUARDRAIL GR-MGS1	292.000 LF	_____	_____	_____	_____
0640	505	13286 GUARDRAIL TERMINAL GR-MGS2	4.000 EA	_____	_____	_____	_____
0650	505	13287 GUARDRAIL END ANCHORAGE GR-MGS3	1.000 EA	_____	_____	_____	_____
0660	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	5.000 EA	_____	_____	_____	_____
0670	505	13315 GUARDRAIL TERMINAL GR-11	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0680	505	13320 GUARDRAIL GR-2	152.000 LF	_____	_____	_____	_____
0690	505	13345 ALTERNATE BREAKAWAY CABLE TERMINAL GR-9	2.000 EA	_____	_____	_____	_____
0700	505	13383 FIXED OBJECT ATTACH. GR- FOA-1 TY. I	2.000 EA	_____	_____	_____	_____
0710	505	13384 FIXED OBJECT ATTACH. GR- FOA-1 TY. II	2.000 EA	_____	_____	_____	_____
0720	505	13394 FIXED OBJECT ATTACH. GR- FOA-5	2.000 EA	_____	_____	_____	_____
0730	502	13461 MEDIAN BARRIER MB-7E	406.000 LF	_____	_____	_____	_____
0740	512	13495 TRAF. BARR. SER. CONC. SINGLE FACE PAR.MB-10A	1,427.000 LF	_____	_____	_____	_____
0750	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	4,045.000 LF	_____	_____	_____	_____
0760	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	10.000 EA	_____	_____	_____	_____
0770	512	13605 IMPACT ATTEN. SER. TY. 1 TL-2, <40 MPH	6.000 EA	_____	_____	_____	_____
0780	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	800.000 TON	_____	_____	_____	_____
0790	ATTD	14280 COARSE AGGREGATE NO.8	1,808.000 TON	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	502	21020 MEDIAN STRIP MS-1	970.000 SY	_____	_____	_____	_____
0810	502	21215 MEDIAN STRIP MS-2	650.000 LF	_____	_____	_____	_____
0820	507	22501 FENCE FE-W1	1,190.000 LF	_____	_____	_____	_____
0830	507	22541 LINE BRACE UNIT FE-W1,FE- W2	1.000 EA	_____	_____	_____	_____
0840	507	22581 CORNER BRACE UNIT FE- W1,FE-W2	8.000 EA	_____	_____	_____	_____
0850	507	22643 FENCE FE-CL	1,078.000 LF	_____	_____	_____	_____
0860	507	22663 CORNER BRACE UNIT FE-CL	8.000 EA	_____	_____	_____	_____
0870	507	22676 GATE FE-CL L=12'	1.000 EA	_____	_____	_____	_____
0880	511	24100 ALLAYING DUST	981.000 HR	_____	_____	_____	_____
0890	512	24152 TYPE 3 BARRICADE 8'	6.000 EA	_____	_____	_____	_____
0900	512	24160 TEMPORARY (CONSTRUCTION) SIGN	2,000.000 SF	_____	_____	_____	_____
0910	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	240.000 DAY	_____	_____	_____	_____
0920	512	24272 TRUCK MOUNTED ATTENUATOR	2,944.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01      Oversight/State Project No.: 0017-088-R72, C501, B616  
 Order No.: C73      Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	512	24278 GROUP 2 CHANNELIZING DEVICES	95,668.000 DAY	_____	_____	_____	_____
0940	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	1,344.000 HR	_____	_____	_____	_____
0950	512	24281 ELECTRONIC ARROW BOARD	5,888.000 HR	_____	_____	_____	_____
0960	512	24282 FLAGGER SERVICE	1,952.000 HR	_____	_____	_____	_____
0970	512	24289 WARNING LIGHT TY. C	368.000 DAY	_____	_____	_____	_____
0980	ATTD	24355 POLICE PATROL UNIFORMED FLAGGERS	640.000 HR	_____	_____	_____	_____
0990	508	24400 OBSCURING ROADWAY	4.000 UNIT	_____	_____	_____	_____
1000	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	11,277.000 SY	_____	_____	_____	_____
1010	510	24503 REMOVE EXIST. SIGNAL EQUIPMENT	LUMP SUM	LUMP SUM	_____	_____	_____
1020	ATTD	24505 RELOCATE EXIST. MAILBOX	1.000 EA	_____	_____	_____	_____
1025	505	24600 REMOVE EXISTING GUARDRAIL	3,884.000 LF	_____	_____	_____	_____
1030	ATTD	24602 REMOVE EXIST. FENCE EXISTING LIMITED ACCESS FENCE	1,192.000 LF	_____	_____	_____	_____
1040	514	25505 FIELD OFFICE TY.I	27.000 MO	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1050	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM			
1060	ATTD	25567 PROGRESS SCHEDULE UPDATES	39.000 EA				
1070	414	26127 DRY RIPRAP CL.I 26"	104.400 TON				
1080	602	27012 TOPSOIL CLASS A 2"	7.390 ACRE				
1090	602	27013 TOPSOIL CLASS A	817.000 CY				
1100	301	27024 TOPSOIL 2 FT OF TOP SOIL	1.400 ACRE				
1110	603	27101 TEMPORARY SEED	828.000 LB				
1120	603	27102 REGULAR SEED	1,802.000 LB				
1130	603	27103 OVERSEEDING	1,442.000 LB				
1140	603	27110 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	38,841.000 SY				
1150	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	51,328.000 SY				
1160	603	27230 FERTILIZER NITROGEN - N	792.000 LB				
1170	603	27231 FERTILIZER PHOSPHOROUS - P	1,087.000 LB				

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1180	603	27232 FERTILIZER POTASSIUM - K	544.000 LB	_____	_____	_____	_____
1190	603	27250 LIME	58.000 TON	_____	_____	_____	_____
1200	303	27284 EROSION CONTROL MULCH	9,557.000 SY	_____	_____	_____	_____
1210	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	5,405.000 SY	_____	_____	_____	_____
1220	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	78.000 SY	_____	_____	_____	_____
1230	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	93.000 SY	_____	_____	_____	_____
1240	303	27410 CHECK DAM, ROCK TY. I	25.000 EA	_____	_____	_____	_____
1250	303	27415 CHECK DAM ROCK TY. II	62.000 EA	_____	_____	_____	_____
1260	303	27430 SILTATION CONTROL EXCAVATION	2,452.000 CY	_____	_____	_____	_____
1270	608	27440 MOWING	100.000 HR	_____	_____	_____	_____
1280	303	27451 INLET PROTECTION TYPE A	6.000 EA	_____	_____	_____	_____
1290	303	27461 INLET PROTECTION TYPE B	44.000 EA	_____	_____	_____	_____
1300	303	27505 TEMP. SILT FENCE TYPE A	11,785.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1310	244	27543 STORM WATER MANAGEMENT COMPOST SOIL AMENDMENTS	1,600.000 SY	_____	_____	_____	_____
1320	303	27544 STORM WATER MGT. BIORETENTION SOIL MIXTURE	2,340.000 CY	_____	_____	_____	_____
1330	303	27545 STORM WATER MANAGEMENT BASIN EXCAVATION	9,706.000 CY	_____	_____	_____	_____
1340	302	27551 SWM DR. STR. PERMANENT CHECK DAM TYPE 1 (TIMBER)	8.000 LF	_____	_____	_____	_____
1350	ATTD	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION (CONSTRUCTION RECORD DOCUMENTS)	LUMP SUM	LUMP SUM	_____	_____	_____
1360	302	27568 STORM WATER MANAGEMENT RISER PIPE 60"	15.500 LF	_____	_____	_____	_____
1370	520	40061 6" DI WATER MAIN	13.000 LF	_____	_____	_____	_____
1380	520	40121 12" DI WATER MAIN	25.000 LF	_____	_____	_____	_____
1390	520	40161 16" DI WATER MAIN	538.000 LF	_____	_____	_____	_____
1400	520	40406 16" BEND	5.000 EA	_____	_____	_____	_____
1410	520	40422 16" BRANCH	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1420	520	40460 16" REDUCER	2.000 EA	_____	_____	_____	_____
1430	520	41006 6" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1440	520	41012 12" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1450	520	41413 12"X12" TAPPING SLEEVE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1460	520	41820 FIRE HYDRANT	1.000 EA	_____	_____	_____	_____
1470	520	41981 WATER FACILITIES NS 30" JACKED STEEL ENCASEMENT PIPE	280.000 LF	_____	_____	_____	_____
1480	701	50108 SIGN PANEL	465.000 SF	_____	_____	_____	_____
1490	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	26.000 EA	_____	_____	_____	_____
1500	700	50302 REMOVE EXISTING 2 POST SIGN STRUCTURE	2.000 EA	_____	_____	_____	_____
1510	700	50320 REMOVE EXISTING 1 POST SIGN PANEL	29.000 EA	_____	_____	_____	_____
1520	700	50322 REMOVE EXISTING 2 POST SIGN PANEL	3.000 EA	_____	_____	_____	_____
1530	700	50430 SIGN POST STP-1, 2", 14 GAUGE	61.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1540	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	36.000 LF	_____	_____	_____	_____
1550	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	160.000 LF	_____	_____	_____	_____
1560	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	200.000 LF	_____	_____	_____	_____
1570	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	8.000 EA	_____	_____	_____	_____
1580	700	50487 CONCRETE SIGN FOUNDATION STP-1, TYPE C	3.000 EA	_____	_____	_____	_____
1590	700	50488 CONCRETE SIGN FOUNDATION STP-1, TYPE D	5.000 EA	_____	_____	_____	_____
1600	700	50489 CONCRETE SIGN FOUNDATION STP-1, TYPE E	14.000 EA	_____	_____	_____	_____
1610	700	51170 ELECTRICAL SERVICE SE-5	1.000 EA	_____	_____	_____	_____
1620	703	51185 TRAFFIC SIGNAL HEAD SECTION 12" HVS BACKPLATE	53.000 EA	_____	_____	_____	_____
1630	700	51210 PEDESTAL POLE PF-2 10'	14.000 EA	_____	_____	_____	_____
1640	700	51238 CONCRETE FOUNDATION SIGNAL POLE PF-8	48.000 CY	_____	_____	_____	_____
1650	700	51240 CONCRETE FOUNDATION PF-2	14.000 EA	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1660	703	51243 CONC FOUNDATION CF-5	1.000 EA	_____	_____	_____	_____
1670	700	51476 SIGNAL MAST ARM POLE MP- 3, TYPE B1	3.000 EA	_____	_____	_____	_____
1680	700	51488 MAST ARM 60'	1.000 EA	_____	_____	_____	_____
1690	700	51491 MAST ARM 75' CASE 1 LOADING	2.000 EA	_____	_____	_____	_____
1700	703	51524 EVP DETECTION SYSTEM 4- WAY	1.000 EA	_____	_____	_____	_____
1710	703	51525 EVP DETECTOR CABLE	1,085.000 LF	_____	_____	_____	_____
1720	703	51540 LOOP DETECTOR AMPLIFIER	20.000 EA	_____	_____	_____	_____
1730	700	51598 8/3 CONDUCTOR CABLE	40.000 LF	_____	_____	_____	_____
1740	700	51600 14/2 CONDUCTOR CABLE	3,115.000 LF	_____	_____	_____	_____
1750	700	51602 14/4 CONDUCTOR CABLE	5,090.000 LF	_____	_____	_____	_____
1760	700	51607 14/7 CONDUCTOR CABLE	830.000 LF	_____	_____	_____	_____
1770	700	51615 14/1 ENCLOSED COND. CABLE	6,105.000 LF	_____	_____	_____	_____
1780	700	51700 14/2 CONDUCTOR CABLE SHIELDED	4,815.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1790	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	16.000 EA	_____	_____	_____	_____
1800	703	51834 HANGER ASSEMBLY SMB-2, ONE WAY	14.000 EA	_____	_____	_____	_____
1810	703	51912 LOOP SAW CUT 3/8"	1,312.000 LF	_____	_____	_____	_____
1820	703	51913 LOOP SAWCUT 5/8"	420.000 LF	_____	_____	_____	_____
1830	703	51980 TRAFFIC CONTROL SIGNAL TEMPORARY SIGNAL	LUMP SUM	LUMP SUM	_____	_____	_____
1840	703	51993 UNINTERRUPTIBLE POWER SUPPLY TYPE 1	1.000 EA	_____	_____	_____	_____
1850	703	51995 UNINTERRUPTIBLE POWER SUPPLY BATTERY PACK	1.000 EA	_____	_____	_____	_____
1860	703	51997 UNINTERRUPTIBLE POWER SUPPLY CABINET DETACHED	1.000 EA	_____	_____	_____	_____
1870	ATTD	52002 TRAFFIC SIGNALIZATION ACCESSIBLE PEDESTRIAN SYSTEM PUSHBUTTON STATIONS	14.000 EA	_____	_____	_____	_____
1880	703	52002 TRAFFIC SIGNALIZATION ATC CABINET 5-DOOR CONFIGURATION	1.000 EA	_____	_____	_____	_____
1890	703	52002 TRAFFIC SIGNALIZATION LOCAL CONTROLLER	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1900	703	52002 TRAFFIC SIGNALIZATION MODIFY SIGNAL	2.000 EA	_____	_____	_____	_____
1910	ATTD	52002 TRAFFIC SIGNALIZATION MOUNTING EXTENDER	7.000 EA	_____	_____	_____	_____
1920	703	52404 PEDESTRIAN SIGNAL HEAD SP-9	14.000 EA	_____	_____	_____	_____
1930	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	27,055.000 LF	_____	_____	_____	_____
1940	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	1,880.000 LF	_____	_____	_____	_____
1950	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	1,880.000 LF	_____	_____	_____	_____
1960	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	440.000 LF	_____	_____	_____	_____
1970	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	500.000 LF	_____	_____	_____	_____
1980	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	49,492.000 LF	_____	_____	_____	_____
1990	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	161.000 EA	_____	_____	_____	_____
2000	704	54393 PVMT MSG. MARK. "ONLY" TY B, CL II, 6'	2.000 EA	_____	_____	_____	_____
2010	512	54443 TEMP. PVMT SYMBOL MRKG THRU ARROW TY. A	136.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2020	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	42.000 EA	_____	_____	_____	_____
2030	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	46,738.000 LF	_____	_____	_____	_____
2040	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	1,938.000 LF	_____	_____	_____	_____
2050	512	54548 TYPE D, CLASS III TEMP. PVMT MRKG 24"	816.000 LF	_____	_____	_____	_____
2060	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	32.000 EA	_____	_____	_____	_____
2070	704	54578 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL II	3.000 EA	_____	_____	_____	_____
2080	704	54590 PVMT SYMB MRKG LANE REDUCTION ARROW TY B, CL II	2.000 EA	_____	_____	_____	_____
2090	700	55385 ELECTRICAL SERVICE WORK PAD	1.000 EA	_____	_____	_____	_____
2100	700	55586 JUNCTION BOX JB-S1	9.000 EA	_____	_____	_____	_____
2110	700	55587 JUNCTION BOX JB-S2	7.000 EA	_____	_____	_____	_____
2120	700	55588 JUNCTION BOX JB-S3	1.000 EA	_____	_____	_____	_____
2130	700	56014 ELECT. SER. GRD. ELECTRODE 10'	5.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2140	700	56021 1" PVC CONDUIT	130.000 LF	_____	_____	_____	_____
2150	700	56050 BORED CONDUIT 2"	50.000 LF	_____	_____	_____	_____
2160	700	56052 BORED CONDUIT 4"	995.000 LF	_____	_____	_____	_____
2170	700	56053 2" PVC CONDUIT	1,655.000 LF	_____	_____	_____	_____
2180	700	56054 3" PVC CONDUIT	70.000 LF	_____	_____	_____	_____
2190	700	56055 4" PVC CONDUIT	30.000 LF	_____	_____	_____	_____
2200	700	56200 TRENCH EXCAVATION ECI-1	1,695.000 LF	_____	_____	_____	_____
2210	700	56205 TEST BORE	3.000 EA	_____	_____	_____	_____
2220	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	684.200 CY	_____	_____	_____	_____
2230	316	60450 CONC. CLASS A4 BRIDGE APPR. SLAB	226.700 CY	_____	_____	_____	_____
2240	316	60452 REINF. STEEL BRIDGE APPR. SLAB	31,880.000 LB	_____	_____	_____	_____
2250	404	60490 BRIDGE DECK GROOVING	1,824.000 SY	_____	_____	_____	_____
2260	404	60495 COVER DEPTH SURVEY	2,332.000 SY	_____	_____	_____	_____
2270	406	61713 CORROSION RESISTANT REINF. STEEL CL. III	145,550.000 LB	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2280	407	61812 STR.STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM			
2290	ATTD	62004 ARCHITECTURAL TREATMENT (RAILINGS)	118.000 SY				
2300	410	62034 RAILING, CPSR 2 RAIL	528.000 LF				
2310	410	62035 RAILING, CPSR 3 RAIL	264.000 LF				
2320	420	62414 ADHESIVE BASED JOINT SEALER CLASS I, 3"	176.000 LF				
2330	ATTD	62534 BRIDGE SUPERSTRUCTURE ELASTIC INCLUSION 14" THICK	48.000 SY				
2340	401	64011 STRUCTURE EXCAVATION	2,029.000 CY				
2350	401	64015 SELECT BACKFILL ABUTMENT ZONE	1,720.000 TON				
2360	401	64032 GEOCOMPOSITE WALL DRAIN	72.000 SY				
2370	401	64036 PIPE UNDERDRAIN 6"	202.000 LF				
2380	403	64101 DYNAMIC PILE TEST	10.000 EA				
2390	403	64414 PRESTR. CONC. CARBON STEEL STRAND PILES 14"	7,343.000 LF				

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2400	403	64818 DRIVING TEST FOR 14" PRESTR. CONC. PILE	609.000 LF	_____	_____	_____	_____
2410	ATTD	64901 RETAINING STRUCTURE MSE WALL	3,370.000 SF	_____	_____	_____	_____
2420	ATTD	64901 RETAINING STRUCTURE SOIL NAIL WALL	2,635.000 SF	_____	_____	_____	_____
2430	ATTD	65004 ARCHITECTURAL TREATMENT (MSE WALL)	375.000 SY	_____	_____	_____	_____
2440	ATTD	65004 ARCHITECTURAL TREATMENT (RAILING)	35.000 SY	_____	_____	_____	_____
2450	ATTD	65004 ARCHITECTURAL TREATMENT (SOIL NAIL WALL)	293.000 SY	_____	_____	_____	_____
2460	404	65013 CONCRETE CLASS A3	593.800 CY	_____	_____	_____	_____
2470	406	65200 REINF. STEEL	22,330.000 LB	_____	_____	_____	_____
2480	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	53,260.000 LB	_____	_____	_____	_____
2490	ATTD	65720 PARAPET PIER PROTECTION SYSTEM, 54"	499.000 LF	_____	_____	_____	_____
2500	414	66124 DRY RIPRAP CL. A1 20"	875.000 TON	_____	_____	_____	_____
2510	ATTD	66921 BRIDGE SUBSTRUCTURE DENSIFIED AGGREGATE PIER, 2'-0" DIA.	5,066.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2520	410	66921 BRIDGE SUBSTRUCTURE RAILING, CPSR 2 RAIL, ON SUBSTRUCTURE	138.000 LF	_____	_____	_____	_____
2530	410	66921 BRIDGE SUBSTRUCTURE RAILING, CPSR 3 RAIL, ON SUBSTRUCTURE	48.000 LF	_____	_____	_____	_____
2540	ATTD	66924 BRIDGE SUBSTRUCTURE LOAD TEST FOR D.A.P.	2.000 EA	_____	_____	_____	_____
2550	ATTD	66924 BRIDGE SUBSTRUCTURE SOIL VERIFICATION TEST NAILS	2.000 EA	_____	_____	_____	_____
2560	ATTD	66925 BRIDGE SUBSTRUCTURE LOAD TRANSFER PLATFORM BACKFILL	407.000 TON	_____	_____	_____	_____
2570	ATTD	66926 BRIDGE SUBSTRUCTURE GEOSYNTHETIC REINF. FOR PLATFORM	861.000 SY	_____	_____	_____	_____
2580	ATTD	66927 BRIDGE SUBSTRUCTURE TEMPORARY RETAINING STRUCTURE (ABUTMENT A)	LUMP SUM	LUMP SUM	_____	_____	_____
2590	ATTD	66927 BRIDGE SUBSTRUCTURE TEMPORARY RETAINING STRUCTURE (ABUTMENT B)	LUMP SUM	LUMP SUM	_____	_____	_____
2600	ATTD	66927 BRIDGE SUBSTRUCTURE TEMPORARY RETAINING STRUCTURE (PIERS)	LUMP SUM	LUMP SUM	_____	_____	_____
2610	507	67088 PED. FENCE 8'	524.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107140B01

Oversight/State Project No.: 0017-088-R72, C501, B616

Order No.: C73

Federal Project No.: NHPP-5111(375)

Contractor: \_\_\_\_\_

SECTION: 0001                      REGULAR BID ITEMS

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2620	413	67900 DISM.& REM. EX. STR. STRUCTURE NO. 1033	LUMP SUM	LUMP SUM		_____.	_____.
2630	430	67910 NBIS ACCESS, UNDER BRIDGE B616	2.000 DAY		_____.	_____.	_____.
<b>Section: 0001</b>				<b>Total:</b>		_____.	_____.
				<b>Total Bid:</b>		_____.	_____.