

Schedule of Items

Proposal ID: CM820BRA117425

Oversight/State Project No.: 0610-081-841,B684, B685

Order No.: U99

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00102 CONSTRUCTION SURVEYING MIN.-PLAN	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00118 EXCAVATION EXCESS SEDIMENT REMOVAL	3.900 CY				
0050	207	00306 SELECT MATERIAL TY. OGB	500.000 TON				
0060	308	10100 AGGR. MATL. NO. 21B	300.000 TON				
0070	315	16335 ASPHALT CONC. TY. SM-9.5A	22.000 TON				
0080	315	16390 ASPH. CONC. TY. BM-25.0A	90.000 TON				
0090	512	24152 TYPE 3 BARRICADE 8'	8.000 EA				
0100	512	24160 TEMPORARY (CONSTRUCTION) SIGN	320.000 SF				
0110	512	24278 GROUP 2 CHANNELIZING DEVICES	9,000.000 DAY				
0120	512	24282 FLAGGER SERVICE	300.000 HR				
0130	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	96.000 LF				

Schedule of Items

Proposal ID: CM820BRA117425

Oversight/State Project No.: 0610-081-841,B684, B685

Order No.: U99

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM			
0150	ATTD	25567 PROGRESS SCHEDULE UPDATES	16.000 EA				
0160	244	27024 TOPSOIL CLASS B 3"	0.230 ACRE				
0170	603	27101 TEMPORARY SEED	23.000 LB				
0180	603	27102 REGULAR SEED	49.000 LB				
0190	603	27103 OVERSEEDING	39.000 LB				
0200	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,210.000 SY				
0210	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	1,113.000 SY				
0220	603	27113 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	182.000 SY				
0230	603	27230 FERTILIZER NITROGEN - N	19.000 LB				
0240	603	27231 FERTILIZER PHOSPHOROUS - P	12.000 LB				
0250	603	27232 FERTILIZER POTASSIUM - K	12.000 LB				
0260	603	27250 LIME	1.040 TON				

Schedule of Items

Proposal ID: CM820BRA117425

Oversight/State Project No.: 0610-081-841,B684, B685

Order No.: U99

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	303	27422 DEWATERING BASIN EC-8	4.000 EA	_____	_____	_____	_____
0280	303	27430 SILTATION CONTROL EXCAVATION	92.000 CY	_____	_____	_____	_____
0290	303	27500 GEOTEXTILE FABRIC	711.000 SY	_____	_____	_____	_____
0300	303	27505 TEMP. SILT FENCE TYPE A	467.000 LF	_____	_____	_____	_____
0310	701	50108 SIGN PANEL	76.000 SF	_____	_____	_____	_____
0320	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	4.000 EA	_____	_____	_____	_____
0330	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	100.000 LF	_____	_____	_____	_____
0340	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	12.000 EA	_____	_____	_____	_____
0350	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	36.000 LF	_____	_____	_____	_____
0360	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	400.000 LF	_____	_____	_____	_____
0370	414	66239 DRY RIPRAP CL.II 38"	233.000 TON	_____	_____	_____	_____
0380	ATTD;413	67900 DISM.& REM. EX. STR. STR. NO. 6044	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: CM820BRA117425

Oversight/State Project No.: 0610-081-841,B684, B685

Order No.: U99

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	ATTD;413	67900 DISM.& REM. EX. STR. STR. NO. 6046	LUMP SUM	LUMP SUM			
0400	ATTD;405	68133 PRESTRESSED CONCRETE SLAB 3'-10" x 18" x 43'	7.000 EA				
0410	416	68405 WATERPROOFING - EPOXY RESIN TYPE EP-7	181.000 SY				
0420	ATTD	68904 SUPERSTR. WID./REPAIR PRECAST CONCRETE SLAB 3'-10" x 18" x 22'-2"	7.000 EA				
0430	401	69008 GEOCOMPOSITE WALL DRAIN	56.000 SY				
0440	401	69010 PIPE UNDERDRAIN 6"	161.000 LF				
0450	401	69011 STRUCTURE EXCAVATION	425.000 CY				
0460	401	69014 SELECT BACKFILL ABUTMENT ZONE	237.000 TON				
0470	404,ATTD	69025 CONCRETE CLASS A3 (UNREINFORCED)	34.800 CY				
0480	412	69030 CONCRETE CLASS A3	65.900 CY				
0490	ATTD;410	69070 PARAPET LOW PROFILE CONCRETE PARAPET	130.330 LF				
0500	406	69100 REINF. STEEL	5,760.000 LB				

Schedule of Items

Proposal ID: CM820BRA117425

Oversight/State Project No.: 0610-081-841,B684, B685

Order No.: U99

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	ATTD	69614 TEMP. CAUSEWAY STR. NO. 6044	LUMP SUM	LUMP SUM		_____.	_____
0520	ATTD	69614 TEMP. CAUSEWAY STR. NO. 6046	LUMP SUM	LUMP SUM		_____.	_____
0530	401	69620 COFFERDAM	6.000 EA		_____.	_____.	_____
Section: 0001				Total:		_____.	_____
				Total Bid:		_____.	_____