

Proposal Schedule of Items

Proposal ID: C0000117822N01

Oversight/State Project No.: PM9Z-029-F21, N501

Order No.: 943

Federal Project No.: PM09(361)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	31,824.000 GAL	_____	_____	_____	_____
0020	315	16335 ASPHALT CONC. TY. SM-9.5A	9,176.110 TON	_____	_____	_____	_____
0030	315	16340 ASPHALT CONC. TY. SM-9.5D	27,855.190 TON	_____	_____	_____	_____
0040	315	16365 ASPHALT CONC. TY. IM-19.0A	1,543.170 TON	_____	_____	_____	_____
0050	ATTD	16502 SURF. PREPARATION & RESTORATION TYPE II	2,044.000 TON	_____	_____	_____	_____
0060	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	398,529.340 SY	_____	_____	_____	_____
0070	515	16523 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	12,859.730 SY	_____	_____	_____	_____
0080	ATTD	24265 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____
0090	512	24282 FLAGGER SERVICE	1,262.000 HR	_____	_____	_____	_____
0100	700	51615 14/1 ENCLOSED COND. CABLE	31,993.000 LF	_____	_____	_____	_____
0110	700	51700 14/2 CONDUCTOR CABLE SHIELDED	3,000.000 LF	_____	_____	_____	_____
0120	703	51912 LOOP SAW CUT 3/8"	14,733.000 LF	_____	_____	_____	_____
0130	703	51913 LOOP SAWCUT 5/8"	3,536.000 LF	_____	_____	_____	_____

Proposal Schedule of Items

Proposal ID: C0000117822N01

Oversight/State Project No.: PM9Z-029-F21, N501

Order No.: 943

Federal Project No.: PM09(361)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	149,560.000 LF	_____	_____	_____	_____
0150	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	31,252.000 LF	_____	_____	_____	_____
0160	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	6,696.000 LF	_____	_____	_____	_____
0170	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	3,981.000 LF	_____	_____	_____	_____
0180	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	6,161.000 LF	_____	_____	_____	_____
0190	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	80.000 EA	_____	_____	_____	_____
0200	704	54400 PVMT MESSAGE MARK. ONLY	23.000 EA	_____	_____	_____	_____
0210	704	54401 PVMT MESSAGE MARK. SCHOOL ZONE	1.000 EA	_____	_____	_____	_____
0220	704	54402 PAVE. MESSAGE MARKING BICYCLE DETECTOR SYMBOL (FOLLOW STD. TYPICAL)	9.000 EA	_____	_____	_____	_____
0230	512	54428 TEMP. PVMT MRKG, TY. A, 4"	171,280.000 LF	_____	_____	_____	_____
0240	512	54440 TEMP. PVMT MRKG, TY. A, 24"	3,759.000 LF	_____	_____	_____	_____

Proposal Schedule of Items

Page 3 of 3

Proposal ID: C0000117822N01

Oversight/State Project No.: PM9Z-029-F21, N501

Order No.: 943

Federal Project No.: PM09(361)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	704	54574 PVT SYMB MRKG SGL TURN ARROW TY B, CL I	271.000 EA	_____	_____	_____	_____
0260	704	54577 PVT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	17.000 EA	_____	_____	_____	_____
0270	704	54589 PVT SYMB MRKG LANE REDUCTION ARROW TY B, CL I	4.000 EA	_____	_____	_____	_____
0280	704	54651 PVT SYMB MRKG BICYCLE THRU ARROW TY B, CL I	64.000 EA	_____	_____	_____	_____
0290	704	54659 PVT SYMB MRKG HELMETED BICYCLIST TY B CL I	64.000 EA	_____	_____	_____	_____
0300	700	56022 1" METAL CONDUIT	421.000 LF	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	