Proposal ID: CM221LME117437 **Oversight/State Project No.:** LM2E-962-F21, P401
Order No.: 271 **Federal Project No.:** PM02(461)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0010	310	10417 TACK COAT	3,050.000 GAL	_____	_____	_____	_____
0020	ATTD	10497 PAVEMENT CRACK SEALANT/FILLER TYPE B	98,840.000 LB	_____	_____	_____	_____
0030	ATTD	10505 PAVEMENT FLEXIBLE LATEX MOD. EMUL. TREAT. TYPE C	3,203.290 TON	_____	_____	_____	_____
0040	ATTD	15309 PAVEMENT LIQUID ASPHALT COATING (PAVEMENT MARKER GROOVE)	757.500 SY	_____	_____	_____	_____
0050	ATTD	16145 LATEX MOD. EMULSION TREAT. TYPE C	4,397.100 TON	_____	_____	_____	_____
0060	315	16370 ASPHALT CONC. TY. IM-19.0D	4,055.350 TON	_____	_____	_____	_____
0070	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	30,406.930 SY	_____	_____	_____	_____
0080	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	120.000 DAY	_____	_____	_____	_____
0090	ATTD	24265 MAINTENANCE OF TRAFFIC LATEX MODIFIED	LUMP SUM	LUMP SUM		_____	_____
0100	512	24282 FLAGGER SERVICE	4,405.000 HR	_____	_____	_____	_____
0110	704	54022 TYPE A PVMT LINE MRKG 6"	2,300.000 LF	_____	_____	_____	_____
0120	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	294,216.000 LF	_____	_____	_____	_____

Proposal ID: CM221LME117437 **Oversight/State Project No.:** LM2E-962-F21, P401

Order No.: 271 **Federal Project No.:** PM02(461)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0130	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	277,260.000 LF	_____	_____	_____	_____
0140	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	412.000 LF	_____	_____	_____	_____
0150	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	3,689.000 LF	_____	_____	_____	_____
0160	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	1,408.500 LF	_____	_____	_____	_____
0170	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	546,888.000 LF	_____	_____	_____	_____
0180	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	4,760.000 SF	_____	_____	_____	_____
0190	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	2,156.000 EA	_____	_____	_____	_____
0200	704	54396 PVMT MSG. MARK. “SCHOOL” TY B, CL II, 6’	3.000 EA	_____	_____	_____	_____
0210	512	54428 TEMP. PVMT MRKG, TY. A, 4"	821,798.000 LF	_____	_____	_____	_____
0220	512	54430 TEMP. PVMT MRKG, TY. A, 6"	824.000 LF	_____	_____	_____	_____
0230	512	54432 TEMP. PVMT MRKG, TY. A, 8"	7,378.000 LF	_____	_____	_____	_____
0240	ATTD	54530 TEMP PVMT MRKG TEMP. PAVE. MESS. MARK (STOP BAR 12"Â)	671.500 LF	_____	_____	_____	_____

Proposal ID: CM221LME117437 **Oversight/State Project No.:** LM2E-962-F21, P401

Order No.: 271 **Federal Project No.:** PM02(461)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0250	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	64.000 EA	_____	_____	_____	_____
0260	704	54578 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL II	3.000 EA	_____	_____	_____	_____

Section: 0001 **Total:** _____.____

Total Bid: _____.____