

Schedule of Items

Proposal ID: CM22PMW117589B Oversight/State Project No.: PM2W-962-F21, P401

Order No.: 280

Federal Project No.: PM02(461)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	24,668.000 GAL	_____	_____	_____	_____
0020	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	2,369.400 TON	_____	_____	_____	_____
0030	315	16335 ASPHALT CONC. TY. SM-9.5A	23,041.670 TON	_____	_____	_____	_____
0040	ATTD	16368 PAVEMENT SHOULDER WEDGE PREP.	216,266.000 LF	_____	_____	_____	_____
0050	515	16516 FLEXIBLE PAVE. TIE-IN PLANING 0" - 2"	5,835.380 SY	_____	_____	_____	_____
0060	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	39,403.610 SY	_____	_____	_____	_____
0070	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	174.000 DAY	_____	_____	_____	_____
0080	ATTD	24265 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____
0090	512	24282 FLAGGER SERVICE	3,000.000 HR	_____	_____	_____	_____
0100	704	54020 TYPE A PVMT LINE MRKG 4"	249,458.000 LF	_____	_____	_____	_____
0110	704	54022 TYPE A PVMT LINE MRKG 6"	9,717.000 LF	_____	_____	_____	_____
0120	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	307.000 LF	_____	_____	_____	_____
0130	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	562.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM22PMW117589B Oversight/State Project No.: PM2W-962-F21, P401

Order No.: 280

Federal Project No.: PM02(461)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	704	54396 PVMT MSG. MARK. "SCHOOL" TY B, CL II, 6'	1.000 EA	_____	_____	_____	_____
0150	512	54428 TEMP. PVMT MRKG, TY. A, 4"	88,511.000 LF	_____	_____	_____	_____
0160	512	54430 TEMP. PVMT MRKG, TY. A, 6"	9,717.000 LF	_____	_____	_____	_____
0170	ATTD	54530 TEMP PVMT MRKG TEMP. PAVE. MESS. MARK (STOP BAR 12")	75.000 LF	_____	_____	_____	_____
0180	704	54572 PVMT SYMB MRKG THRU ARROW TY B, CL II	3.000 EA	_____	_____	_____	_____
0190	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	14.000 EA	_____	_____	_____	_____
0200	704	54578 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL II	2.000 EA	_____	_____	_____	_____

Section: 0001 Total: _____

SECTION: 0002 ALTERNATE CATEGORY "A" BID ITEM

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0210	ATTD	16243 SHOULDER MAINTENANCE MATERIAL	1.000 TON	_____	_____	_____	_____

Section: 0002 Total: _____

Total Bid: _____