

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	49,238.000 CY				
0050	305	00140 BORROW EXCAVATION	13,606.000 CY				
0060	303	00211 MINOR STRUCTURE EXCAV. PIPE CULVERT	1,424.000 CY				
0070	305	00272 SELECT MATL. TY. I MIN. CBR-30	662.000 CY				
0080	ATTD	00500 BEDDING MATL. FINE AGGR.	116.000 TON				
0090	ATTD	00505 BEDDING MATL. AGGR. NO. 25 OR 26	200.000 TON				
0100	ATTD	00507 BEDDING MATL. AGGR. NO. 57	795.000 TON				
0110	302 406	00540 REINF. STEEL	25,980.000 LB				
0120	501	00588 UNDERDRAIN UD-4	2,860.000 LF				
0130	501	00595 OUTLET PIPE	300.000 LF				

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	01156 STORM SEWER PIPE 15"	1,534.000 LF	_____	_____	_____	_____
0150	302	01186 STORM SEWER PIPE 18"	686.000 LF	_____	_____	_____	_____
0160	302	01246 STORM SEWER PIPE 24"	534.000 LF	_____	_____	_____	_____
0170	302	01306 STORM SEWER PIPE 30"	570.000 LF	_____	_____	_____	_____
0180	302	01486 STORM SEWER PIPE 48"	400.000 LF	_____	_____	_____	_____
0190	302	01600 60" PIPE	300.000 LF	_____	_____	_____	_____
0200	ATTD	02092 SPEC. DES. WHEEL STOP	42.000 EA	_____	_____	_____	_____
0210	ATTD	02112 DRAINAGE CONSTRUCTION RECORD DOCUMENTS	1.000 EA	_____	_____	_____	_____
0220	302	06151 15" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0230	302	06180 18" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0240	302	06480 48" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0250	302	06815 DROP INLET DI-3A	2.000 EA	_____	_____	_____	_____
0260	302	06816 DROP INLET DI-3AA	1.000 EA	_____	_____	_____	_____
0270	302	06818 DROP INLET DI-3B,L=6'	9.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	302	06819 DROP INLET DI-3B,L=8'	9.000 EA	_____	_____	_____	_____
0290	302	06820 DROP INLET DI-3B,L=10'	6.000 EA	_____	_____	_____	_____
0300	302	06828 DROP INLET DI-3BB,L=8'	1.000 EA	_____	_____	_____	_____
0310	302	06829 DROP INLET DI-3BB,L=10'	2.000 EA	_____	_____	_____	_____
0320	302	06830 DROP INLET DI-3BB,L=12'	1.000 EA	_____	_____	_____	_____
0330	302	06835 DROP INLET DI-3C,L=6'	2.000 EA	_____	_____	_____	_____
0340	302	07110 DROP INLET DI-4B,L=6'	1.000 EA	_____	_____	_____	_____
0350	302	07114 DROP INLET DI-4B,L=10'	1.000 EA	_____	_____	_____	_____
0360	302	07506 DROP INLET DI-5	1.000 EA	_____	_____	_____	_____
0370	302	08990 DROP INLET MODIFIED DI-3B, L=6'	1.000 EA	_____	_____	_____	_____
0380	302	09055 MANHOLE MH-2	36.000 LF	_____	_____	_____	_____
0390	302	09056 MANHOLE MH-1 OR 2	6.000 LF	_____	_____	_____	_____
0400	302	09057 FRAME & COVER MH-1	7.000 EA	_____	_____	_____	_____
0410	302	09060 DI-PRECAST TOP VARIOUS TYPES CONST	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	502	09125 ENERGY DISSIPATOR EG-1	1.000 EA	_____	_____	_____	_____
0430	414	09150 EROSION CONTROL STONE CLASS I, EC-1	295.000 TON	_____	_____	_____	_____
0440	502	09225 PAVED FLUME PG-4	27.000 SY	_____	_____	_____	_____
0450	306	10000 LIME	727.000 TON	_____	_____	_____	_____
0460	307	10027 MANIPULATION 12"	22,426.000 SY	_____	_____	_____	_____
0470	307	10034 CEM. STAB. 3% BY DRY WEIGHT	363.000 TON	_____	_____	_____	_____
0480	305	10113 AGGR. BASE MATL. TY. I NO. 21A OR 21B	11,085.000 TON	_____	_____	_____	_____
0490	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	13,790.000 SY	_____	_____	_____	_____
0500	315	10642 ASPHALT CONCRETE TY. BM-25.0A	906.000 TON	_____	_____	_____	_____
0510	315	11070 SAW-CUT ASPH CONC SAWCUT	2,882.000 LF	_____	_____	_____	_____
0520	502	12020 STD. CURB CG-2	1,710.000 LF	_____	_____	_____	_____
0530	502	12022 RADIAL CURB CG-2	166.000 LF	_____	_____	_____	_____
0540	502	12600 STD. COMB. CURB & GUTTER CG-6	2,848.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0550	502	12610 RADIAL COMB. CURB & GUTTER CG-6	254.000 LF	_____	_____	_____	_____
0560	502	12700 STD. COMB. CURB & GUTTER CG-7	1,504.000 LF	_____	_____	_____	_____
0570	502	12710 RADIAL COMB. CURB & GUTTER CG-7	329.000 LF	_____	_____	_____	_____
0580	502	13102 RADIAL COMB. CURB & GUTTER CG-11	426.000 LF	_____	_____	_____	_____
0590	504	13108 CG-12 DETECTABLE WARNING SURFACE	56.000 SY	_____	_____	_____	_____
0600	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	1,367.000 SY	_____	_____	_____	_____
0610	504	13232 GEOTEXTILE DRAINAGE FABRIC	3,876.000 SY	_____	_____	_____	_____
0620	506	13530 RETAINING WALL RW-3	548.100 CY	_____	_____	_____	_____
0630	401	13561 POROUS BACKFILL	40.000 CY	_____	_____	_____	_____
0640	506	13565 RETAINING WALL EXCAVATION	335.000 CY	_____	_____	_____	_____
0650	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	1.000 EA	_____	_____	_____	_____
0660	315	16350 ASPHALT CONC. TY. SM-12.5A	4,765.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	315	16365 ASPHALT CONC. TY. IM-19.0A	3,144.000 TON	_____	_____	_____	_____
0680	502	21022 MEDIAN STRIP MS-1	630.000 LF	_____	_____	_____	_____
0690	511	24100 ALLAYING DUST	720.000 HR	_____	_____	_____	_____
0700	512	24152 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0710	512	24160 TEMPORARY (CONSTRUCTION) SIGN	670.000 SF	_____	_____	_____	_____
0720	512	24260 CR. RUN AGGR. NO. 25 OR 26	50.000 TON	_____	_____	_____	_____
0730	512	24272 TRUCK MOUNTED ATTENUATOR	1,600.000 HR	_____	_____	_____	_____
0740	512	24278 GROUP 2 CHANNELIZING DEVICES	86,400.000 DAY	_____	_____	_____	_____
0750	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	2,688.000 HR	_____	_____	_____	_____
0760	512	24281 ELECTRONIC ARROW BOARD	1,536.000 HR	_____	_____	_____	_____
0770	512	24282 FLAGGER SERVICE	64.000 HR	_____	_____	_____	_____
0780	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	500.000 LF	_____	_____	_____	_____
0790	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	3,127.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	505	24600 REMOVE EXISTING GUARDRAIL	750.000 LF	_____	_____	_____	_____
0810	510	24825 MODIFY EXIST. CURB INLET	2.000 EA	_____	_____	_____	_____
0820	504	25003 HANDRAIL HR-1 TYPE II	253.000 LF	_____	_____	_____	_____
0830	504	25004 HANDRAIL HR-1 TYPE III	395.000 LF	_____	_____	_____	_____
0840	514	25505 FIELD OFFICE TY.I	26.000 MO	_____	_____	_____	_____
0850	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____
0860	ATTD	25567 PROGRESS SCHEDULE UPDATES	26.000 EA	_____	_____	_____	_____
0870	602	27022 TOPSOIL CLASS B 2"	4.000 ACRE	_____	_____	_____	_____
0880	603	27101 TEMPORARY SEED	1,040.000 LB	_____	_____	_____	_____
0890	603	27102 REGULAR SEED	750.000 LB	_____	_____	_____	_____
0900	603	27103 OVERSEEDING	600.000 LB	_____	_____	_____	_____
0910	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	15,730.000 SY	_____	_____	_____	_____
0920	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	58,806.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	603	27230 FERTILIZER NITROGEN - N	503.000 LB	_____	_____	_____	_____
0940	603	27231 FERTILIZER PHOSPHOROUS - P	765.000 LB	_____	_____	_____	_____
0950	603	27232 FERTILIZER POTASSIUM - K	383.000 LB	_____	_____	_____	_____
0960	603	27250 LIME	24.400 TON	_____	_____	_____	_____
0970	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	230.000 SY	_____	_____	_____	_____
0980	606	27327 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	12,707.000 SY	_____	_____	_____	_____
0990	303	27345 TEMPORARY DIVERSION DIKE	903.000 LF	_____	_____	_____	_____
1000	303	27415 CHECK DAM ROCK TY. II	26.000 EA	_____	_____	_____	_____
1010	303	27422 DEWATERING BASIN EC-8	8.000 EA	_____	_____	_____	_____
1020	303	27430 SILTATION CONTROL EXCAVATION	1,333.000 CY	_____	_____	_____	_____
1030	303	27451 INLET PROTECTION TYPE A	3.000 EA	_____	_____	_____	_____
1040	303	27461 INLET PROTECTION TYPE B	42.000 EA	_____	_____	_____	_____
1050	303	27505 TEMP. SILT FENCE TYPE A	6,281.000 LF	_____	_____	_____	_____



Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1060	ATTD	27548 STORM WATER MANAGEMENT HYDRODYNAMIC SEPARATOR	LUMP SUM	LUMP SUM			
1070	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	2,160.000 CY				
1080	ATTD	38910 BIKE RACK .	1.000 EA				
1090	ATTD	38925 TRASH RECEPTACLE .	5.000 EA				
1100	ATTD	38935 COMMUTER BUS SHELTER	1.000 EA				
1110	520	40002 3/4" WATER SERVICE LINE	72.000 LF				
1120	520	40061 6" DI WATER MAIN	129.000 LF				
1130	520	40081 8" DI WATER MAIN	1,273.000 LF				
1140	520	40121 12" DI WATER MAIN	677.000 LF				
1150	520	41006 6" GATE VALVE & BOX	6.000 EA				
1160	520	41008 8" GATE VALVE & BOX	1.000 EA				
1170	520	41012 12" GATE VALVE & BOX	1.000 EA				
1180	520	41820 FIRE HYDRANT	6.000 EA				
1190	520	41830 1" AIR RELEASE VALVE & BOX	2.000 EA				

## Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001

BASE BID

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1200	520	41967 5/8" WATER METER BOX & YOKE	4.000 EA	_____	_____	_____	_____
1210	520	42150 15" SAN. SEWER PIPE	220.000 LF	_____	_____	_____	_____
1220	520	42755 SANITARY SEWER MANHOLE	19.000 LF	_____	_____	_____	_____
1230	520	42764 MANHOLE FRAME & COVER F&C-1	2.000 EA	_____	_____	_____	_____
1240	701	50108 SIGN PANEL	146.000 SF	_____	_____	_____	_____
1250	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	3.000 EA	_____	_____	_____	_____
1260	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	3.000 EA	_____	_____	_____	_____
1270	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	264.000 LF	_____	_____	_____	_____
1280	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	22.000 EA	_____	_____	_____	_____
1290	700	51246 CONCRETE FOUND. CF-2	1.000 EA	_____	_____	_____	_____
1300	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	26,655.000 LF	_____	_____	_____	_____
1310	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	6,430.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1320	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	1,830.000 LF	_____	_____	_____	_____
1330	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	345.000 LF	_____	_____	_____	_____
1340	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	445.000 LF	_____	_____	_____	_____
1350	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	49,345.000 LF	_____	_____	_____	_____
1360	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	972.000 SF	_____	_____	_____	_____
1370	704	54107 PAVEMENT MARKING SYMBOL HANDICAP PARKING TY B, CL 1	14.000 EA	_____	_____	_____	_____
1380	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	185.000 EA	_____	_____	_____	_____
1390	704	54392 PVMT MSG. MARK. "ONLY" TY B, CL. I, 6'	3.000 EA	_____	_____	_____	_____
1400	704	54402 PAVE. MESSAGE MARKING "MERGE", TY B CL 1	1.000 EA	_____	_____	_____	_____
1410	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	18.000 EA	_____	_____	_____	_____
1420	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	66,600.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1430	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	15,100.000 LF	_____	_____	_____	_____
1440	512	54548 TYPE D, CLASS III TEMP. PVMT MRKG 24"	105.000 LF	_____	_____	_____	_____
1450	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	14.000 EA	_____	_____	_____	_____
1460	704	54589 PVMT SYMB MRKG LANE REDUCTION ARROW TY B, CL I	2.000 EA	_____	_____	_____	_____
1470	700	55060 6 CONDUCTOR CABLE	5,600.000 LF	_____	_____	_____	_____
1480	700	55080 8 CONDUCTOR CABLE	15,780.000 LF	_____	_____	_____	_____
1490	700	55110 12 CONDUCTOR CABLE	2,160.000 LF	_____	_____	_____	_____
1500	700	55140 CONCRETE FOUNDATION LF- 1 TY. A	24.000 EA	_____	_____	_____	_____
1510	700	55348 ELECT. SERVICE SE-9 TYPE A	1.000 EA	_____	_____	_____	_____
1520	705	55351 CONTROL CENTER CCW-1 TYPE B	1.000 EA	_____	_____	_____	_____
1530	700	55586 JUNCTION BOX JB-S1	6.000 EA	_____	_____	_____	_____
1540	700	56021 1" PVC CONDUIT	240.000 LF	_____	_____	_____	_____
1550	700	56054 3" PVC CONDUIT	2,705.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1560	700	56200 TRENCH EXCAVATION ECI-1	2,845.000 LF	_____	_____	_____	_____
1570	705	59000 LIGHTING LUMINAIRE 173 WATT LED	9.000 EA	_____	_____	_____	_____
1580	705	59000 LIGHTING LUMINAIRE 279 WATT LED	28.000 EA	_____	_____	_____	_____
1590	700	59000 LIGHTING POLE LP-2 30' MH	24.000 EA	_____	_____	_____	_____
1600	401	60120 STRUCTURE EXCAVATION	268.000 CY	_____	_____	_____	_____
1610	404	60404 CONCRETE CLASS A4	186.700 CY	_____	_____	_____	_____
1620	401	64036 PIPE UNDERDRAIN 6"	154.000 LF	_____	_____	_____	_____
1630	403	64112 STEEL PILES 12"	1,785.000 LF	_____	_____	_____	_____
1640	401	69620 COFFERDAM	2.000 EA	_____	_____	_____	_____
1650	516	70000 DEMO. OF BLDG. D-700	LUMP SUM	LUMP SUM	_____	_____	_____
1660	516	70000 DEMO. OF BLDG. D-701	LUMP SUM	LUMP SUM	_____	_____	_____
1670	516	70000 DEMO. OF BLDG. D-702	LUMP SUM	LUMP SUM	_____	_____	_____
1680	516	70000 DEMO. OF BLDG. D-703	LUMP SUM	LUMP SUM	_____	_____	_____
1690	516	70000 DEMO. OF BLDG. D-900	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0001 BASE BID

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1700	516	70000 DEMO. OF BLDG. D-901	LUMP SUM	LUMP SUM			_____.
1710	516	70000 DEMO. OF BLDG. D-902	LUMP SUM	LUMP SUM			_____.
1720	516	70000 DEMO. OF BLDG. D-903	LUMP SUM	LUMP SUM			_____.
1730	516	70000 DEMO. OF BLDG. D-904	LUMP SUM	LUMP SUM			_____.
<b>Section: 0001</b>				<b>Total:</b>			_____.

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0002

BID ADDITIVE A

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1740	303	00120 REGULAR EXCAVATION	19,405.000 CY	_____	_____	_____	_____
1750	305	00140 BORROW EXCAVATION	607.000 CY	_____	_____	_____	_____
1760	ATTD	00507 BEDDING MATL. AGGR. NO. 57	18.000 TON	_____	_____	_____	_____
1770	501	00588 UNDERDRAIN UD-4	270.000 LF	_____	_____	_____	_____
1780	501	00595 OUTLET PIPE	60.000 LF	_____	_____	_____	_____
1790	302	01156 STORM SEWER PIPE 15"	188.000 LF	_____	_____	_____	_____
1800	302	01186 STORM SEWER PIPE 18"	250.000 LF	_____	_____	_____	_____
1810	302	06815 DROP INLET DI-3A	1.000 EA	_____	_____	_____	_____
1820	302	06817 DROP INLET DI-3B,L=4'	2.000 EA	_____	_____	_____	_____
1830	302	06819 DROP INLET DI-3B,L=8'	2.000 EA	_____	_____	_____	_____
1840	302	06820 DROP INLET DI-3B,L=10'	1.000 EA	_____	_____	_____	_____
1850	306	10000 LIME	149.000 TON	_____	_____	_____	_____
1860	306	10027 MANIPULATION 12"	4,608.000 SY	_____	_____	_____	_____
1870	307	10034 CEM. STAB. 3% BY DRY WEIGHT	75.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01      Oversight/State Project No.: 0001-088-281, C501, D611  
 Order No.: C40      Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0002      BID ADDITIVE A

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1880	305	10113 AGGR. BASE MATL. TY. I NO. 21A OR 21B	1,650.000 TON	_____	_____	_____	_____
1890	502	12020 STD. CURB CG-2	460.000 LF	_____	_____	_____	_____
1900	502	12022 RADIAL CURB CG-2	170.000 LF	_____	_____	_____	_____
1910	502	12600 STD. COMB. CURB & GUTTER CG-6	1,011.000 LF	_____	_____	_____	_____
1920	502	12610 RADIAL COMB. CURB & GUTTER CG-6	111.000 LF	_____	_____	_____	_____
1930	504	13232 GEOTEXTILE DRAINAGE FABRIC	183.000 SY	_____	_____	_____	_____
1940	315	16350 ASPHALT CONC. TY. SM-12.5A	507.000 TON	_____	_____	_____	_____
1950	315	16365 ASPHALT CONC. TY. IM-19.0A	507.000 TON	_____	_____	_____	_____
1960	606	27327 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	2,420.000 SY	_____	_____	_____	_____
1970	303	27461 INLET PROTECTION TYPE B	6.000 EA	_____	_____	_____	_____
1980	ATTD	38925 TRASH RECEPTACLE .	1.000 EA	_____	_____	_____	_____
1990	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	2,106.000 LF	_____	_____	_____	_____
2000	700	55080 8 CONDUCTOR CABLE	1,280.000 LF	_____	_____	_____	_____



Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0002

BID ADDITIVE A

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2010	700	55110 12 CONDUCTOR CABLE	270.000 LF	_____	_____	_____	_____
2020	700	55140 CONCRETE FOUNDATION LF-1 TY. A	3.000 EA	_____	_____	_____	_____
2030	700	56021 1" PVC CONDUIT	30.000 LF	_____	_____	_____	_____
2040	700	56054 3" PVC CONDUIT	325.000 LF	_____	_____	_____	_____
2050	700	56200 TRENCH EXCAVATION ECI-1	325.000 LF	_____	_____	_____	_____
2060	705	59000 LIGHTING LUMINAIRE 173 WATT LED	1.000 EA	_____	_____	_____	_____
2070	705	59000 LIGHTING LUMINAIRE 279 WATT LED	4.000 EA	_____	_____	_____	_____
2080	705	59000 LIGHTING POLE LP-2 30' MH	3.000 EA	_____	_____	_____	_____
2090	403	64112 STEEL PILES 12"	3,150.000 LF	_____	_____	_____	_____
<b>Section: 0002</b>				<b>Total:</b>		_____	

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0003

BID ADDITIVE B

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2100	303	00120 REGULAR EXCAVATION	5,474.000 CY	_____	_____	_____	_____
2110	305	00140 BORROW EXCAVATION	641.000 CY	_____	_____	_____	_____
2120	ATTD	00507 BEDDING MATL. AGGR. NO. 57	25.000 TON	_____	_____	_____	_____
2130	501	00588 UNDERDRAIN UD-4	410.000 LF	_____	_____	_____	_____
2140	501	00595 OUTLET PIPE	40.000 LF	_____	_____	_____	_____
2150	306	10000 LIME	105.000 TON	_____	_____	_____	_____
2160	306	10027 MANIPULATION 12"	3,228.000 SY	_____	_____	_____	_____
2170	307	10034 CEM. STAB. 3% BY DRY WEIGHT	52.000 TON	_____	_____	_____	_____
2180	305	10113 AGGR. BASE MATL. TY. I NO. 21A OR 21B	1,148.000 TON	_____	_____	_____	_____
2190	502	12600 STD. COMB. CURB & GUTTER CG-6	601.000 LF	_____	_____	_____	_____
2200	502	12610 RADIAL COMB. CURB & GUTTER CG-6	47.000 LF	_____	_____	_____	_____
2210	504	13232 GEOTEXTILE DRAINAGE FABRIC	250.000 SY	_____	_____	_____	_____
2220	315	16350 ASPHALT CONC. TY. SM-12.5A	355.000 TON	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0003

BID ADDITIVE B

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2230	315	16365 ASPHALT CONC. TY. IM-19.0A	355.000 TON	_____	_____	_____	_____
2240	606	27327 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	1,070.000 SY	_____	_____	_____	_____
2250	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	2,430.000 LF	_____	_____	_____	_____
2260	700	55060 6 CONDUCTOR CABLE	2,455.000 LF	_____	_____	_____	_____
2270	700	55110 12 CONDUCTOR CABLE	540.000 LF	_____	_____	_____	_____
2280	700	55140 CONCRETE FOUNDATION LF- 1 TY. A	6.000 EA	_____	_____	_____	_____
2290	700	55586 JUNCTION BOX JB-S1	2.000 EA	_____	_____	_____	_____
2300	700	56021 1" PVC CONDUIT	60.000 LF	_____	_____	_____	_____
2310	700	56054 3" PVC CONDUIT	635.000 LF	_____	_____	_____	_____
2320	700	56200 TRENCH EXCAVATION ECI-1	635.000 LF	_____	_____	_____	_____
2330	705	59000 LIGHTING LUMINAIRE 173 WATT LED	3.000 EA	_____	_____	_____	_____
2340	705	59000 LIGHTING LUMINAIRE 279 WATT LED	5.000 EA	_____	_____	_____	_____
2350	705	59000 LIGHTING POLE LP-2 30' MH	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109474C01

Oversight/State Project No.: 0001-088-281, C501, D611

Order No.: C40

Federal Project No.: NHPP - 5111 (374)

Contractor: \_\_\_\_\_

SECTION: 0003 BID ADDITIVE B

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2360	403	64112 STEEL PILES 12"	1,435.000 LF	_____	_____	_____	_____
<b>Section: 0003</b>				<b>Total:</b>	_____	_____	_____
				<b>Total Bid:</b>	_____	_____	_____