

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0010 | 513 | 00100 MOBILIZATION | LUMP SUM | LUMP SUM | | | |
| 0020 | 517 | 00101 CONSTRUCTION SURVEYING CONSTRUCTION | LUMP SUM | LUMP SUM | | | |
| 0030 | 301 | 00111 CLEARING AND GRUBBING | 17.000 ACRE | | | | |
| 0040 | 303 | 00120 REGULAR EXCAVATION | 787,113.000 CY | | | | |
| 0050 | 602 ATTD | 00170 SOIL BIORETENTION MEDIA | 662.000 CY | | | | |
| 0060 | 303 | 00211 MINOR STRUCTURE EXCAV. PIPE CULVERT | 661.000 CY | | | | |
| 0070 | 303 | 00212 MINOR STRUCTURE EXCAV. BOX CULVERT | 46.000 CY | | | | |
| 0080 | ATTD | 00504 BEDDING MATL. FINE AGGR. OR AGGR. NO. 8 | 139.000 TON | | | | |
| 0090 | ATTD | 00507 BEDDING MATL. AGGR. NO. 57 | 622.000 TON | | | | |
| 0100 | 302 | 00522 CONCRETE CLASS A4 BOX CULVERT | 21.800 CY | | | | |
| 0110 | 302 504 | 00525 CONCRETE CLASS A3 MISC. | 91.950 CY | | | | |
| 0120 | 509 | 00529 FLOWABLE BACKFILL | 138.000 CY | | | | |
| 0130 | 302 406 | 00540 REINF. STEEL | 2,113.000 LB | | | | |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---------------------------------------|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0140 | 501 | 00580 UNDERDRAIN UD-1 | 148.000 LF | _____ | _____ | _____ | _____ |
| 0150 | 501 | 00588 UNDERDRAIN UD-4 | 2,079.000 LF | _____ | _____ | _____ | _____ |
| 0160 | 501 | 00590 CROSSDRAIN CD-1 | 180.000 LF | _____ | _____ | _____ | _____ |
| 0170 | 501 | 00595 OUTLET PIPE | 128.000 LF | _____ | _____ | _____ | _____ |
| 0180 | 302 | 00596 ENDWALL EW-12 | 6.000 EA | _____ | _____ | _____ | _____ |
| 0190 | 501 | 00598 UNDERDRAIN 6" NON-PERFORATED | 38.000 LF | _____ | _____ | _____ | _____ |
| 0200 | 501 | 00598 UNDERDRAIN 6" PERFORATED | 893.000 LF | _____ | _____ | _____ | _____ |
| 0210 | 302 | 01180 18" PIPE | 350.000 LF | _____ | _____ | _____ | _____ |
| 0220 | 302 | 01182 18" CONC. PIPE | 43.000 LF | _____ | _____ | _____ | _____ |
| 0230 | 302 | 01186 STORM SEWER PIPE 18" | 1,312.000 LF | _____ | _____ | _____ | _____ |
| 0240 | 302 | 01240 24" PIPE | 25.000 LF | _____ | _____ | _____ | _____ |
| 0250 | 302 | 01242 24" CONC. PIPE | 58.000 LF | _____ | _____ | _____ | _____ |
| 0260 | 302 | 01246 STORM SEWER PIPE 24" | 1,352.000 LF | _____ | _____ | _____ | _____ |
| 0270 | 302 | 01302 30" CONC. PIPE | 116.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------------|-------------|---|--------------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0280 | 302 | 01422 42" CONC. PIPE | 321.000 LF | _____ | _____ | _____ | _____ |
| 0290 | 302 | 01482 48" CONC. PIPE | 116.000 LF | _____ | _____ | _____ | _____ |
| 0300 | 302 | 01602 60" CONC. PIPE | 158.000 LF | _____ | _____ | _____ | _____ |
| 0310 | 302 | 02090 PIPE 24" REINFORCED CONCRETE O-RING PIPE | 131.000 LF | _____ | _____ | _____ | _____ |
| 0320 | 302 | 02110 DRAINAGE LOW PERMEABILITY LINER (GEOTEXTILE) | 1,780.000 SY | _____ | _____ | _____ | _____ |
| 0330 | 302 | 06180 18" END SECTION ES-1 OR 2 | 24.000 EA | _____ | _____ | _____ | _____ |
| 0340 | 302 | 06181 18" END SECTION ES-1 | 5.000 EA | _____ | _____ | _____ | _____ |
| 0350 | 302 | 06240 24" END SECTION ES-1 OR 2 | 2.000 EA | _____ | _____ | _____ | _____ |
| 0360 | 302 | 06241 24" END SECTION ES-1 | 9.000 EA | _____ | _____ | _____ | _____ |
| 0370 | 302 | 06822 DROP INLET DI-3B,L=14' | 6.000 EA | _____ | _____ | _____ | _____ |
| 0380 | 302 | 07506 DROP INLET DI-5 | 12.000 EA | _____ | _____ | _____ | _____ |
| 0390 | 302 | 07510 DROP INLET DI-7A | 9.000 EA | _____ | _____ | _____ | _____ |
| 0400 | 302 | 07512 DROP INLET DI-7B | 1.000 EA | _____ | _____ | _____ | _____ |
| 0410 | 302 | 08938 DROP INLET DI-12C,L=4' | 1.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0420 | 302 | 09056 MANHOLE MH-1 OR 2 | 5.900 LF | _____ | _____ | _____ | _____ |
| 0430 | 302 | 09057 FRAME & COVER MH-1 | 1.000 EA | _____ | _____ | _____ | _____ |
| 0440 | 414 | 09148 EROSION CONTROL STONE CLASS A1 EC-1 | 20.000 TON | _____ | _____ | _____ | _____ |
| 0450 | 414 | 09150 EROSION CONTROL STONE CLASS I, EC-1 | 590.000 TON | _____ | _____ | _____ | _____ |
| 0460 | 502 | 09185 PAVED DITCH PG-2A | 935.000 SY | _____ | _____ | _____ | _____ |
| 0470 | 502 | 09215 PAVED DITCH PG-5 | 249.000 SY | _____ | _____ | _____ | _____ |
| 0480 | 308 | 10065 AGGR. MATL. NO. 1 | 11,910.000 TON | _____ | _____ | _____ | _____ |
| 0490 | 308 | 10128 AGGR. BASE MATL. TY. I NO. 21B | 33,910.000 TON | _____ | _____ | _____ | _____ |
| 0500 | 309 | 10239 AGGR. MATL. NO. 25 OR 26 | 508.000 TON | _____ | _____ | _____ | _____ |
| 0510 | 315 | 10607 ASPHALT CONCRETE TY. SM- 12.5A | 6,581.000 TON | _____ | _____ | _____ | _____ |
| 0520 | 315 | 10610 ASPHALT CONCRETE TY. IM- 19.0A | 6,416.000 TON | _____ | _____ | _____ | _____ |
| 0530 | 515 | 10628 FLEXIBLE PAVEMENT PLANING 0" - 2" | 13,460.000 SY | _____ | _____ | _____ | _____ |
| 0540 | 315 | 10642 ASPHALT CONCRETE TY. BM- 25.0A | 20,413.000 TON | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0550 | 315 | 11070 SAW-CUT ASPH CONC FULL DEPTH | 12,285.000 LF | _____ | _____ | _____ | _____ |
| 0560 | 502 | 12030 STD. CURB CG-3 | 116.000 LF | _____ | _____ | _____ | _____ |
| 0570 | 502 | 12322 ASPHALT CONC. CURB TY. MC-3B | 813.000 LF | _____ | _____ | _____ | _____ |
| 0580 | 315 | 12505 ASPHALT CONCRETE, CURB BACKUP MATERIAL | 47.000 TON | _____ | _____ | _____ | _____ |
| 0590 | 504 | 13232 GEOTEXTILE DRAINAGE FABRIC | 28,129.000 SY | _____ | _____ | _____ | _____ |
| 0600 | 505 | 13280 GUARDRAIL GR-MGS1 | 7,487.500 LF | _____ | _____ | _____ | _____ |
| 0610 | 505 | 13286 GUARDRAIL TERMINAL GR-MGS2 | 15.000 EA | _____ | _____ | _____ | _____ |
| 0620 | 505 | 13287 GUARDRAIL END ANCHORAGE GR-MGS3 | 8.000 EA | _____ | _____ | _____ | _____ |
| 0630 | 505 | 13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4 | 5.000 EA | _____ | _____ | _____ | _____ |
| 0640 | 505 | 13323 GUARDRAIL GR-2A | 850.000 LF | _____ | _____ | _____ | _____ |
| 0650 | 505 | 13355 GUARDRAIL GR-10 | 150.000 LF | _____ | _____ | _____ | _____ |
| 0660 | 505 | 13394 FIXED OBJECT ATTACH. GR-FOA-5 | 8.000 EA | _____ | _____ | _____ | _____ |
| 0670 | 505 | 13480 CABLE BARRICADE CR-1 | 2.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0680 | 512 | 13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A | 1,630.000 LF | _____ | _____ | _____ | _____ |
| 0690 | 512 | 13604 IMPACT ATTEN. SER. TY. 1 TL- 3, >=40 MPH | 27.000 EA | _____ | _____ | _____ | _____ |
| 0700 | 507 | 23570 HIGH VISIBILITY FENCE, 4' | 3,200.000 LF | _____ | _____ | _____ | _____ |
| 0710 | 511 | 24100 ALLAYING DUST | 1,400.000 HR | _____ | _____ | _____ | _____ |
| 0720 | 512 | 24152 TYPE 3 BARRICADE 8' | 21.000 EA | _____ | _____ | _____ | _____ |
| 0730 | 512 | 24160 TEMPORARY (CONSTRUCTION) SIGN | 1,223.000 SF | _____ | _____ | _____ | _____ |
| 0740 | ATTD | 24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY | 1,500.000 DAY | _____ | _____ | _____ | _____ |
| 0750 | 512 ATTD | 24265 MAINTENANCE OF TRAFFIC CREEPER TRAIL TRAFFIC CONTROL | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0760 | 512 ATTD | 24265 MAINTENANCE OF TRAFFIC NAVIGATION S.F. HOLSTON RIVER | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0770 | 512 | 24272 TRUCK MOUNTED ATTENUATOR | 8,640.000 HR | _____ | _____ | _____ | _____ |
| 0780 | 512 | 24278 GROUP 2 CHANNELIZING DEVICES | 65,220.000 DAY | _____ | _____ | _____ | _____ |
| 0790 | 512 | 24279 PORTABLE CHANGEABLE MESSAGE SIGN | 3,360.000 HR | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0800 | 512 | 24281 ELECTRONIC ARROW BOARD | 4,160.000 HR | _____ | _____ | _____ | _____ |
| 0810 | 512 | 24282 FLAGGER SERVICE | 6,450.000 HR | _____ | _____ | _____ | _____ |
| 0820 | 512 | 24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC | 8,110.000 LF | _____ | _____ | _____ | _____ |
| 0830 | 508 | 24400 OBSCURING ROADWAY | 58.000 UNIT | _____ | _____ | _____ | _____ |
| 0840 | 508 | 24410 DEMOLITION OF PAVEMENT COMBINATION | 8,630.000 SY | _____ | _____ | _____ | _____ |
| 0850 | 505 | 24600 REMOVE EXISTING GUARDRAIL | 2,490.000 LF | _____ | _____ | _____ | _____ |
| 0860 | 514 | 25506 FIELD OFFICE TY.II | 27.000 MO | _____ | _____ | _____ | _____ |
| 0870 | 512 ATTD | 25515 TRANSPORTATION CREEPER TRAIL CLOSURE PORTAGE | 2.000 MO | _____ | _____ | _____ | _____ |
| 0880 | ATTD | 25565 PROGRESS SCHEDULE BASELINE | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0890 | ATTD | 25567 PROGRESS SCHEDULE UPDATES | 30.000 EA | _____ | _____ | _____ | _____ |
| 0900 | 414 | 26127 DRY RIPRAP CL.I 26" | 641.000 TON | _____ | _____ | _____ | _____ |
| 0910 | 602 | 27023 TOPSOIL CLASS B | 199.000 CY | _____ | _____ | _____ | _____ |
| 0920 | 603 | 27101 TEMPORARY SEED | 2,700.000 LB | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0930 | 603 | 27102 REGULAR SEED | 4,894.000 LB | _____ | _____ | _____ | _____ |
| 0940 | 603 | 27103 OVERSEEDING | 3,915.000 LB | _____ | _____ | _____ | _____ |
| 0950 | 603 | 27104 LEGUME SEED | 288.000 LB | _____ | _____ | _____ | _____ |
| 0960 | 603 | 27105 LEGUME OVERSEEDING | 230.000 LB | _____ | _____ | _____ | _____ |
| 0970 | 603 | 27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2 | 19,360.000 SY | _____ | _____ | _____ | _____ |
| 0980 | 603 | 27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3 | 242,000.000 SY | _____ | _____ | _____ | _____ |
| 0990 | 603 | 27230 FERTILIZER NITROGEN - N | 2,326.000 LB | _____ | _____ | _____ | _____ |
| 1000 | 603 | 27231 FERTILIZER PHOSPHOROUS - P | 3,038.000 LB | _____ | _____ | _____ | _____ |
| 1010 | 603 | 27232 FERTILIZER POTASSIUM - K | 1,519.000 LB | _____ | _____ | _____ | _____ |
| 1020 | 603 | 27250 LIME | 122.000 TON | _____ | _____ | _____ | _____ |
| 1030 | 606 | 27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2 | 7,226.000 SY | _____ | _____ | _____ | _____ |
| 1040 | 606 | 27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3 | 236.000 SY | _____ | _____ | _____ | _____ |
| 1050 | 303 | 27345 TEMPORARY DIVERSION DIKE | 3,767.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1060 | 303 | 27410 CHECK DAM, ROCK TY. I | 8.000 EA | _____ | _____ | _____ | _____ |
| 1070 | 303 | 27415 CHECK DAM ROCK TY. II | 384.000 EA | _____ | _____ | _____ | _____ |
| 1080 | 303 | 27422 DEWATERING BASIN EC-8 | 8.000 EA | _____ | _____ | _____ | _____ |
| 1090 | 303 | 27430 SILTATION CONTROL EXCAVATION | 5,891.000 CY | _____ | _____ | _____ | _____ |
| 1100 | 303 | 27451 INLET PROTECTION TYPE A | 23.000 EA | _____ | _____ | _____ | _____ |
| 1110 | 303 | 27461 INLET PROTECTION TYPE B | 6.000 EA | _____ | _____ | _____ | _____ |
| 1120 | 303 | 27505 TEMP. SILT FENCE TYPE A | 25,988.000 LF | _____ | _____ | _____ | _____ |
| 1130 | 401 | 27510 COFFERDAM | 4.000 EA | _____ | _____ | _____ | _____ |
| 1140 | 303 | 27545 STORM WATER MANAGEMENT BASIN EXCAVATION | 1,182.700 CY | _____ | _____ | _____ | _____ |
| 1150 | 302 | 27550 STORM WATER MANAGEMENT DRAINAGE STR. SWM-1 | 13.600 LF | _____ | _____ | _____ | _____ |
| 1160 | ATTD | 27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONSTRUCTION RECORDS | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 1170 | 303 | 27580 TEMP. SEDIMENT BASIN EXCAVATION | 2,253.000 CY | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------------|-------------|--|--------------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1180 | 520 | 40002 3/4" WATER SERVICE LINE | 395.000 LF | _____ | _____ | _____ | _____ |
| 1190 | 520 | 40003 1" WATER SERVICE LINE | 325.000 LF | _____ | _____ | _____ | _____ |
| 1200 | 520 | 40020 2" WATER MAIN | 713.000 LF | _____ | _____ | _____ | _____ |
| 1210 | 520 | 40061 6" DI WATER MAIN | 1,623.000 LF | _____ | _____ | _____ | _____ |
| 1220 | 520 | 40081 8" DI WATER MAIN | 1,954.000 LF | _____ | _____ | _____ | _____ |
| 1230 | 520 | 41002 2" GATE VALVE & BOX | 1.000 EA | _____ | _____ | _____ | _____ |
| 1240 | 520 | 41006 6" GATE VALVE & BOX | 6.000 EA | _____ | _____ | _____ | _____ |
| 1250 | 520 | 41008 8" GATE VALVE & BOX | 2.000 EA | _____ | _____ | _____ | _____ |
| 1260 | 520 | 41820 FIRE HYDRANT | 1.000 EA | _____ | _____ | _____ | _____ |
| 1270 | 520 | 41835 1" AIR RELEASE VALVE & MANHOLE | 2.000 EA | _____ | _____ | _____ | _____ |
| 1280 | 520 | 41967 5/8" WATER METER BOX & YOKE | 5.000 EA | _____ | _____ | _____ | _____ |
| 1290 | 520 | 42060 6" SAN. SEWER PIPE | 133.000 LF | _____ | _____ | _____ | _____ |
| 1300 | 520 | 42846 6" SEWER CLEANOUT | 1.000 EA | _____ | _____ | _____ | _____ |
| 1310 | ATTD | 45505 CONNECT TO EXIST. A/C PIPE | 1.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1320 | 520 | 45552 12" STEEL ENCASE. PIPE | 258.000 LF | _____ | _____ | _____ | _____ |
| 1330 | 520 | 45562 16" STEEL ENCASE. PIPE | 95.000 LF | _____ | _____ | _____ | _____ |
| 1340 | 509 | 45640 FLOWABLE BACKFILL UTILITY | 3.000 CY | _____ | _____ | _____ | _____ |
| 1350 | 701 | 50108 SIGN PANEL | 702.000 SF | _____ | _____ | _____ | _____ |
| 1360 | 700 | 50300 REMOVE EXISTING 1 POST SIGN STRUCTURE | 8.000 EA | _____ | _____ | _____ | _____ |
| 1370 | 700 | 50430 SIGN POST STP-1, 2", 14 GAUGE | 480.000 LF | _____ | _____ | _____ | _____ |
| 1380 | 700 | 50436 SIGN POST STP-1, 2 1/2", 12 GAUGE | 170.000 LF | _____ | _____ | _____ | _____ |
| 1390 | 700 | 50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A | 60.000 EA | _____ | _____ | _____ | _____ |
| 1400 | 704 | 54032 TYPE B CLASS I PVMT LINE MRKG 4" | 2,950.000 LF | _____ | _____ | _____ | _____ |
| 1410 | 704 | 54034 TYPE B CLASS I PVMT LINE MRKG 6" | 62,350.000 LF | _____ | _____ | _____ | _____ |
| 1420 | 704 | 54048 TYPE B CLASS II PAVE. LINE MARKING 24" | 507.000 LF | _____ | _____ | _____ | _____ |
| 1430 | 704 | 54080 TYPE B CLASS VI CONTRAST PVMT MRKG 6" | 3,000.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
 Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
 Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1440 | 512 | 54105 ERADICATE EXIST. LINEAR PVMT MARKING | 34,000.000 LF | _____ | _____ | _____ | _____ |
| 1450 | ATTD | 54219 INLAID PAVEMENT MARKER ASPHALT | 213.000 EA | _____ | _____ | _____ | _____ |
| 1460 | 512 | 54240 TEMP. PAVE. MARKER 1 WAY | 273.000 EA | _____ | _____ | _____ | _____ |
| 1470 | 512 | 54242 TEMP. PAVE. MARKER 2 WAY | 137.000 EA | _____ | _____ | _____ | _____ |
| 1480 | 512 | 54428 TEMP. PVMT MRKG, TY. A, 4" | 82,000.000 LF | _____ | _____ | _____ | _____ |
| 1490 | 512 | 54432 TEMP. PVMT MRKG, TY. A, 8" | 6,900.000 LF | _____ | _____ | _____ | _____ |
| 1500 | 512 | 54440 TEMP. PVMT MRKG, TY. A, 24" | 150.000 LF | _____ | _____ | _____ | _____ |
| 1510 | 704 | 54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I | 19.000 EA | _____ | _____ | _____ | _____ |
| 1520 | ATTD | 60125 BRIDGE TEMPORARY WORKBRIDGE | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 1530 | 404 | 60409 CONC. CLASS A4 MOD. LOW SHRINKAGE | 971.000 CY | _____ | _____ | _____ | _____ |
| 1540 | 316 | 60450 CONC. CLASS A4 BRIDGE APPR. SLAB | 159.600 CY | _____ | _____ | _____ | _____ |
| 1550 | 316 | 60452 REINF. STEEL BRIDGE APPR. SLAB | 23,620.000 LB | _____ | _____ | _____ | _____ |
| 1560 | 404 | 60490 BRIDGE DECK GROOVING | 3,540.000 SY | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1570 | 404 | 60495 COVER DEPTH SURVEY | 3,512.000 SY | _____ | _____ | _____ | _____ |
| 1580 | 406 | 61713 CORROSION RESISTANT REINF. STEEL CL. III | 194,440.000 LB | _____ | _____ | _____ | _____ |
| 1590 | 407 | 61812 STR.STEEL PLATE GIRDER ASTM A709 GRADE 50W | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 1600 | 410 | 62032 RAILING,KANSAS CORRAL 32" W/CURB | 86.000 LF | _____ | _____ | _____ | _____ |
| 1610 | 410 | 62033 RAILING.KANSAS CORRAL 32" W/OUT CURB | 1,822.000 LF | _____ | _____ | _____ | _____ |
| 1620 | 420 | 62414 ADHESIVE BASED JOINT SEALER CLASS I, 3" | 126.000 LF | _____ | _____ | _____ | _____ |
| 1630 | 401 | 64011 STRUCTURE EXCAVATION | 4,426.000 CY | _____ | _____ | _____ | _____ |
| 1640 | 401 | 64015 SELECT BACKFILL ABUTMENT ZONE | 2,308.000 TON | _____ | _____ | _____ | _____ |
| 1650 | ATTD | 64021 ELASTIC INCLUSION | 108.000 CY | _____ | _____ | _____ | _____ |
| 1660 | 401 | 64032 GEOCOMPOSITE WALL DRAIN | 172.000 SY | _____ | _____ | _____ | _____ |
| 1670 | 401 | 64036 PIPE UNDERDRAIN 6" | 182.000 LF | _____ | _____ | _____ | _____ |
| 1680 | 403 | 64875 PILE STEEL PIPE 18" | 1,139.000 LF | _____ | _____ | _____ | _____ |
| 1690 | ATTD | 64901 RETAINING STRUCTURE MSE WALL | 12,416.000 SF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1700 | 404 | 65013 CONCRETE CLASS A3 | 926.600 CY | _____ | _____ | _____ | _____ |
| 1710 | 406 | 65200 REINF. STEEL | 158,180.000 LB | _____ | _____ | _____ | _____ |
| 1720 | 401 | 66120 COFFERDAM | 4.000 EA | _____ | _____ | _____ | _____ |
| 1730 | 414 | 66127 DRY RIPRAP CL.I 26" | 248.000 TON | _____ | _____ | _____ | _____ |
| 1740 | ATTD | 66921 BRIDGE SUBSTRUCTURE ROCK SOCKET 24" DIA. | 100.000 LF | _____ | _____ | _____ | _____ |
| 1750 | ATTD | 66924 BRIDGE SUBSTRUCTURE EXPLORATORY FOUNDATION PROBE HOLES | 24.000 EA | _____ | _____ | _____ | _____ |
| 1760 | 507 | 67086 PED. FENCE 6' | 243.000 LF | _____ | _____ | _____ | _____ |
| 1770 | 413 | 67900 DISM.& REM. EX. STR. 1065 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 1780 | ATTD | 67904 BRIDGE INCIDENTALS CONSTRUCTION ACCESS | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 1790 | ATTD | 67910 NBIS ACCESS, UNDER BRIDGE B605 | 4.000 DAY | _____ | _____ | _____ | _____ |
| 1800 | ATTD | 67910 NBIS ACCESS, UNDER BRIDGE B606 | 4.000 DAY | _____ | _____ | _____ | _____ |
| 1810 | 413 | 68476 ENV.& WORK. PROTECTION STR. 1065 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 1820 | 413 | 68492 MATERIAL DISPOSAL STR. 1065 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|---------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1830 | 516 | 70000 DEMO. OF BLDG. D10 | LUMP SUM | LUMP SUM | | | |
| 1840 | 516 | 70000 DEMO. OF BLDG. D20 | LUMP SUM | LUMP SUM | | | |
| 1850 | 516 | 70000 DEMO. OF BLDG. D81 | LUMP SUM | LUMP SUM | | | |
| 1860 | 516 | 70000 DEMO. OF BLDG. D82 | LUMP SUM | LUMP SUM | | | |
| 1870 | 516 | 70000 DEMO. OF BLDG. D84 | LUMP SUM | LUMP SUM | | | |
| 1880 | 516 | 70000 DEMO. OF BLDG. D86 | LUMP SUM | LUMP SUM | | | |
| 1890 | ATTD | 70005 DEMOLITION WITH ACM D83 | LUMP SUM | LUMP SUM | | | |
| 1900 | ATTD | 70012 CLOSE SEPTIC TANK | 1.000 EA | | | | |
| 1910 | ATTD | 70113 CAT II NF ACM | 19.000 LF | | | | |
| 1920 | 516 | 70200 CLEARING PARCEL NO. 023 SEPTIC FIELD LINES | LUMP SUM | LUMP SUM | | | |
| 1930 | 516 | 70200 CLEARING PARCEL NO. 058 | LUMP SUM | LUMP SUM | | | |
| 1940 | 516 | 70200 CLEARING PARCEL NO. 093 | LUMP SUM | LUMP SUM | | | |
| Section: 0001 | | | | Total: | | | |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1950 | 517 | 00101 CONSTRUCTION SURVEYING CONSTRUCTION | LUMP SUM | LUMP SUM | | | |
| 1960 | 301 | 00111 CLEARING AND GRUBBING | 5.000 ACRE | | | | |
| 1970 | 303 | 00120 REGULAR EXCAVATION | 96,354.000 CY | | | | |
| 1980 | 303 | 00211 MINOR STRUCTURE EXCAV. PIPE CULVERT | 367.000 CY | | | | |
| 1990 | 303 | 00212 MINOR STRUCTURE EXCAV. BOX CULVERT | 1,438.000 CY | | | | |
| 2000 | 302 | 00522 CONCRETE CLASS A4 BOX CULVERT | 480.950 CY | | | | |
| 2010 | 302 504 | 00525 CONCRETE CLASS A3 MISC. | 31.950 CY | | | | |
| 2020 | 509 | 00529 FLOWABLE BACKFILL | 11.000 CY | | | | |
| 2030 | 302 406 | 00540 REINF. STEEL | 74,430.000 LB | | | | |
| 2040 | 501 | 00588 UNDERDRAIN UD-4 | 652.000 LF | | | | |
| 2050 | 501 | 00590 CROSSDRAIN CD-1 | 108.000 LF | | | | |
| 2060 | 501 | 00595 OUTLET PIPE | 66.000 LF | | | | |
| 2070 | 302 | 00596 ENDWALL EW-12 | 4.000 EA | | | | |
| 2080 | 302 | 01180 18" PIPE | 33.000 LF | | | | |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 2090 | 302 | 01182 18" CONC. PIPE | 94.000 LF | _____ | _____ | _____ | _____ |
| 2100 | 302 | 01186 STORM SEWER PIPE 18" | 1,240.000 LF | _____ | _____ | _____ | _____ |
| 2110 | 302 | 01242 24" CONC. PIPE | 105.000 LF | _____ | _____ | _____ | _____ |
| 2120 | 302 | 01246 STORM SEWER PIPE 24" | 227.000 LF | _____ | _____ | _____ | _____ |
| 2130 | 302 | 01306 STORM SEWER PIPE 30" | 103.000 LF | _____ | _____ | _____ | _____ |
| 2140 | 302 | 01482 48" CONC. PIPE | 64.000 LF | _____ | _____ | _____ | _____ |
| 2150 | 302 | 02090 PIPE 24" REINFORCED CONCRETE O-RING PIPE | 84.000 LF | _____ | _____ | _____ | _____ |
| 2160 | 302 | 02110 DRAINAGE LOW PERMEABILITY LINER (GEOTEXTILE) | 2,241.000 SY | _____ | _____ | _____ | _____ |
| 2170 | 302 | 06180 18" END SECTION ES-1 OR 2 | 2.000 EA | _____ | _____ | _____ | _____ |
| 2180 | 302 | 06181 18" END SECTION ES-1 | 5.000 EA | _____ | _____ | _____ | _____ |
| 2190 | 302 | 06241 24" END SECTION ES-1 | 5.000 EA | _____ | _____ | _____ | _____ |
| 2200 | 302 | 06750 DROP INLET DI-2B,L=10' | 4.000 EA | _____ | _____ | _____ | _____ |
| 2210 | 302 | 06822 DROP INLET DI-3B,L=14' | 1.000 EA | _____ | _____ | _____ | _____ |
| 2220 | 302 | 07506 DROP INLET DI-5 | 8.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 2230 | 302 | 07510 DROP INLET DI-7A | 4.000 EA | _____ | _____ | _____ | _____ |
| 2240 | 414 | 09148 EROSION CONTROL STONE CLASS A1 EC-1 | 20.000 TON | _____ | _____ | _____ | _____ |
| 2250 | 414 | 09150 EROSION CONTROL STONE CLASS I, EC-1 | 170.000 TON | _____ | _____ | _____ | _____ |
| 2260 | 414 | 09152 EROSION CONTROL STONE CLASS II, EC-1 | 595.000 TON | _____ | _____ | _____ | _____ |
| 2270 | 502 | 09185 PAVED DITCH PG-2A | 992.000 SY | _____ | _____ | _____ | _____ |
| 2280 | 308 | 10065 AGGR. MATL. NO. 1 | 6,110.000 TON | _____ | _____ | _____ | _____ |
| 2290 | 308 | 10128 AGGR. BASE MATL. TY. I NO. 21B | 20,186.000 TON | _____ | _____ | _____ | _____ |
| 2300 | 309 | 10239 AGGR. MATL. NO. 25 OR 26 | 80.000 TON | _____ | _____ | _____ | _____ |
| 2310 | 315 | 10607 ASPHALT CONCRETE TY. SM-12.5A | 3,887.000 TON | _____ | _____ | _____ | _____ |
| 2320 | 315 | 10610 ASPHALT CONCRETE TY. IM-19.0A | 4,093.000 TON | _____ | _____ | _____ | _____ |
| 2330 | 515 | 10628 FLEXIBLE PAVEMENT PLANING 0" - 2" | 9,155.000 SY | _____ | _____ | _____ | _____ |
| 2340 | 315 | 10642 ASPHALT CONCRETE TY. BM-25.0A | 12,490.000 TON | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 2350 | 315 | 11070 SAW-CUT ASPH CONC FULL DEPTH | 8,090.000 LF | _____ | _____ | _____ | _____ |
| 2360 | 502 | 12030 STD. CURB CG-3 | 190.000 LF | _____ | _____ | _____ | _____ |
| 2370 | 502 | 12032 RADIAL CURB CG-3 | 198.000 LF | _____ | _____ | _____ | _____ |
| 2380 | 502 | 12322 ASPHALT CONC. CURB TY. MC-3B | 1,383.000 LF | _____ | _____ | _____ | _____ |
| 2390 | 315 | 12505 ASPHALT CONCRETE, CURB BACKUP MATERIAL | 80.000 TON | _____ | _____ | _____ | _____ |
| 2400 | 504 | 13232 GEOTEXTILE DRAINAGE FABRIC | 13,940.000 SY | _____ | _____ | _____ | _____ |
| 2410 | 505 | 13280 GUARDRAIL GR-MGS1 | 2,162.500 LF | _____ | _____ | _____ | _____ |
| 2420 | 505 | 13286 GUARDRAIL TERMINAL GR-MGS2 | 7.000 EA | _____ | _____ | _____ | _____ |
| 2430 | 505 | 13287 GUARDRAIL END ANCHORAGE GR-MGS3 | 7.000 EA | _____ | _____ | _____ | _____ |
| 2440 | 505 | 13355 GUARDRAIL GR-10 | 75.000 LF | _____ | _____ | _____ | _____ |
| 2450 | 505 | 13480 CABLE BARRICADE CR-1 | 2.000 EA | _____ | _____ | _____ | _____ |
| 2460 | 512 | 13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A | 960.000 LF | _____ | _____ | _____ | _____ |
| 2470 | 512 | 13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH | 16.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 2480 | 502 | 21110 MEDIAN STRIP MS-1A | 99.000 SY | _____ | _____ | _____ | _____ |
| 2490 | 511 | 24100 ALLAYING DUST | 700.000 HR | _____ | _____ | _____ | _____ |
| 2500 | 512 | 24160 TEMPORARY (CONSTRUCTION) SIGN | 235.000 SF | _____ | _____ | _____ | _____ |
| 2510 | ATTD | 24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY | 700.000 DAY | _____ | _____ | _____ | _____ |
| 2520 | 512 | 24272 TRUCK MOUNTED ATTENUATOR | 4,320.000 HR | _____ | _____ | _____ | _____ |
| 2530 | 512 | 24278 GROUP 2 CHANNELIZING DEVICES | 47,190.000 DAY | _____ | _____ | _____ | _____ |
| 2540 | 512 | 24282 FLAGGER SERVICE | 3,150.000 HR | _____ | _____ | _____ | _____ |
| 2550 | 512 | 24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC | 6,880.000 LF | _____ | _____ | _____ | _____ |
| 2560 | 508 | 24410 DEMOLITION OF PAVEMENT COMBINATION | 8,805.000 SY | _____ | _____ | _____ | _____ |
| 2570 | 414 | 26127 DRY RIPRAP CL.I 26" | 1,088.000 TON | _____ | _____ | _____ | _____ |
| 2580 | 602 | 27023 TOPSOIL CLASS B | 250.000 CY | _____ | _____ | _____ | _____ |
| 2590 | 603 | 27101 TEMPORARY SEED | 1,100.000 LB | _____ | _____ | _____ | _____ |
| 2600 | 603 | 27102 REGULAR SEED | 1,994.000 LB | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 2610 | 603 | 27103 OVERSEEDING | 1,595.000 LB | _____ | _____ | _____ | _____ |
| 2620 | 603 | 27104 LEGUME SEED | 113.000 LB | _____ | _____ | _____ | _____ |
| 2630 | 603 | 27105 LEGUME OVERSEEDING | 90.000 LB | _____ | _____ | _____ | _____ |
| 2640 | 603 | 27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2 | 9,680.000 SY | _____ | _____ | _____ | _____ |
| 2650 | 603 | 27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3 | 96,800.000 SY | _____ | _____ | _____ | _____ |
| 2660 | 603 | 27230 FERTILIZER NITROGEN - N | 948.000 LB | _____ | _____ | _____ | _____ |
| 2670 | 603 | 27231 FERTILIZER PHOSPHOROUS - P | 1,238.000 LB | _____ | _____ | _____ | _____ |
| 2680 | 603 | 27232 FERTILIZER POTASSIUM - K | 619.000 LB | _____ | _____ | _____ | _____ |
| 2690 | 603 | 27250 LIME | 50.000 TON | _____ | _____ | _____ | _____ |
| 2700 | 606 | 27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2 | 3,703.000 SY | _____ | _____ | _____ | _____ |
| 2710 | 606 | 27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3 | 477.000 SY | _____ | _____ | _____ | _____ |
| 2720 | 303 | 27345 TEMPORARY DIVERSION DIKE | 159.000 LF | _____ | _____ | _____ | _____ |
| 2730 | 303 | 27415 CHECK DAM ROCK TY. II | 101.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 2740 | 303 | 27422 DEWATERING BASIN EC-8 | 1.000 EA | _____ | _____ | _____ | _____ |
| 2750 | 303 | 27430 SILTATION CONTROL EXCAVATION | 3,647.000 CY | _____ | _____ | _____ | _____ |
| 2760 | 303 | 27451 INLET PROTECTION TYPE A | 11.000 EA | _____ | _____ | _____ | _____ |
| 2770 | 303 | 27461 INLET PROTECTION TYPE B | 6.000 EA | _____ | _____ | _____ | _____ |
| 2780 | 303 | 27505 TEMP. SILT FENCE TYPE A | 19,570.000 LF | _____ | _____ | _____ | _____ |
| 2790 | 401 | 27510 COFFERDAM | 1.000 EA | _____ | _____ | _____ | _____ |
| 2800 | 303 | 27545 STORM WATER MANAGEMENT BASIN EXCAVATION | 2,398.400 CY | _____ | _____ | _____ | _____ |
| 2810 | 302 | 27550 STORM WATER MANAGEMENT DRAINAGE STR. SWM-1 | 16.000 LF | _____ | _____ | _____ | _____ |
| 2820 | ATTD | 27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONSTRUCTION RECORDS | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 2830 | 516 | 27600 CLOSING WELL | 1.000 EA | _____ | _____ | _____ | _____ |
| 2840 | 520 | 40002 3/4" WATER SERVICE LINE | 107.000 LF | _____ | _____ | _____ | _____ |
| 2850 | 520 | 40003 1" WATER SERVICE LINE | 892.000 LF | _____ | _____ | _____ | _____ |
| 2860 | 520 | 40020 2" WATER MAIN | 15.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 2870 | 520 | 40061 6" DI WATER MAIN | 349.000 LF | _____ | _____ | _____ | _____ |
| 2880 | 520 | 40121 12" DI WATER MAIN | 1,717.000 LF | _____ | _____ | _____ | _____ |
| 2890 | 520 | 41002 2" GATE VALVE & BOX | 1.000 EA | _____ | _____ | _____ | _____ |
| 2900 | 520 | 41006 6" GATE VALVE & BOX | 3.000 EA | _____ | _____ | _____ | _____ |
| 2910 | 520 | 41012 12" GATE VALVE & BOX | 4.000 EA | _____ | _____ | _____ | _____ |
| 2920 | 520 | 41835 1" AIR RELEASE VALVE & MANHOLE | 1.000 EA | _____ | _____ | _____ | _____ |
| 2930 | 520 | 41967 5/8" WATER METER BOX & YOKE | 3.000 EA | _____ | _____ | _____ | _____ |
| 2940 | 510 | 42765 ADJUST EXIST FRAME & COVER | 1.000 EA | _____ | _____ | _____ | _____ |
| 2950 | 520 | 45512 CONCRETE ENCASEMENT NS CONCRETE ENCASEMENT | 28.000 LF | _____ | _____ | _____ | _____ |
| 2960 | 520 | 45552 12" STEEL ENCASE. PIPE | 117.000 LF | _____ | _____ | _____ | _____ |
| 2970 | 520 | 45582 24" STEEL ENCASE. PIPE | 88.000 LF | _____ | _____ | _____ | _____ |
| 2980 | 509 | 45640 FLOWABLE BACKFILL UTILITY | 20.000 CY | _____ | _____ | _____ | _____ |
| 2990 | 701 | 50108 SIGN PANEL | 647.000 SF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01

Oversight/State Project No.: 0058-095-108, B605, B606, C501

Order No.: D13

Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 3000 | 700 | 50430 SIGN POST STP-1, 2", 14 GAUGE | 460.000 LF | _____ | _____ | _____ | _____ |
| 3010 | 700 | 50436 SIGN POST STP-1, 2 1/2", 12 GAUGE | 150.000 LF | _____ | _____ | _____ | _____ |
| 3020 | 700 | 50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A | 60.000 EA | _____ | _____ | _____ | _____ |
| 3030 | 704 | 54032 TYPE B CLASS I PVMT LINE MRKG 4" | 220.000 LF | _____ | _____ | _____ | _____ |
| 3040 | 704 | 54034 TYPE B CLASS I PVMT LINE MRKG 6" | 38,000.000 LF | _____ | _____ | _____ | _____ |
| 3050 | 704 | 54037 TYPE B CLASS I PVMT LINE MRKG 8" | 410.000 LF | _____ | _____ | _____ | _____ |
| 3060 | 704 | 54048 TYPE B CLASS II PAVE. LINE MARKING 24" | 88.000 LF | _____ | _____ | _____ | _____ |
| 3070 | 512 | 54105 ERADICATE EXIST. LINEAR PVMT MARKING | 2,000.000 LF | _____ | _____ | _____ | _____ |
| 3080 | ATTD | 54219 INLAID PAVEMENT MARKER ASPHALT | 166.000 EA | _____ | _____ | _____ | _____ |
| 3090 | 512 | 54240 TEMP. PAVE. MARKER 1 WAY | 13.000 EA | _____ | _____ | _____ | _____ |
| 3100 | 512 | 54242 TEMP. PAVE. MARKER 2 WAY | 6.000 EA | _____ | _____ | _____ | _____ |
| 3110 | 704 | 54400 PVMT MESSAGE MARK. ONLY | 1.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000016382C01
Order No.: D13

Oversight/State Project No.: 0058-095-108, B605, B606, C501
Federal Project No.: NONE

Contractor: _____

SECTION: 0002 ADDITIVE ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|---------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 3120 | 512 | 54428 TEMP. PVMT MRKG, TY. A, 4" | 23,600.000 LF | _____ | _____ | _____ | _____ |
| 3130 | 512 | 54432 TEMP. PVMT MRKG, TY. A, 8" | 2,400.000 LF | _____ | _____ | _____ | _____ |
| 3140 | 512 | 54440 TEMP. PVMT MRKG, TY. A, 24" | 180.000 LF | _____ | _____ | _____ | _____ |
| 3150 | 704 | 54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I | 14.000 EA | _____ | _____ | _____ | _____ |
| 3160 | 516 | 70000 DEMO. OF BLDG. D32 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 3170 | 516 | 70000 DEMO. OF BLDG. D33 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 3180 | 516 | 70000 DEMO. OF BLDG. D34 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 3190 | 516 | 70000 DEMO. OF BLDG. D61 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 3200 | ATTD | 70012 CLOSE SEPTIC TANK | 1.000 EA | _____ | _____ | _____ | _____ |
| 3210 | ATTD | 70110 FRIABLE ACM | 10.000 SF | _____ | _____ | _____ | _____ |
| 3220 | ATTD | 70112 CAT II NF ACM | 1,261.000 SF | _____ | _____ | _____ | _____ |
| 3230 | 516 | 70200 CLEARING PARCEL NO. 43 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 3240 | 516 | 70200 CLEARING PARCEL NO. 52 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 3250 | 516 | 70200 CLEARING PARCEL NO. 82 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| Section: 0002 | | | | Total: | _____ | _____ | _____ |

Total Bid: _____.