

Schedule of Items

Proposal ID: C0000093093B23

Oversight/State Project No.: 0046-012-722,C501,B623

Order No.: F06

Federal Project No.: BR-012-4(052)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0020 | 513 | 00100 MOBILIZATION | LUMP SUM | LUMP SUM | | | |
| 0030 | 517 | 00101 CONSTRUCTION SURVEYING CONSTRUCTION | LUMP SUM | LUMP SUM | | | |
| 0040 | 301 | 00110 CLEARING AND GRUBBING | LUMP SUM | LUMP SUM | | | |
| 0050 | 303 | 00120 REGULAR EXCAVATION | 594.000 CY | | | | |
| 0060 | 305 | 00140 BORROW EXCAVATION | 511.000 CY | | | | |
| 0070 | 308 | 10103 AGGR. MATL. NO. 25 OR 26 | 37.000 TON | | | | |
| 0080 | 308 | 10128 AGGR. BASE MATL. TY. I NO. 21B | 1,449.000 TON | | | | |
| 0090 | 315 | 10607 ASPHALT CONCRETE TY. SM- 12.5A | 176.000 TON | | | | |
| 0100 | 315 | 10610 ASPHALT CONCRETE TY. IM- 19.0A | 152.000 TON | | | | |
| 0110 | 515 | 10628 FLEXIBLE PAVEMENT PLANING 0" - 2" | 1,149.000 SY | | | | |
| 0120 | 315 | 10642 ASPHALT CONCRETE TY. BM- 25.0A | 196.000 TON | | | | |
| 0130 | 315 | 11070 SAW-CUT ASPH CONC FULL DEPTH | 1,074.000 LF | | | | |
| 0140 | 502 | 12030 STD. CURB CG-3 | 82.000 LF | | | | |

Schedule of Items

Proposal ID: C0000093093B23

Oversight/State Project No.: 0046-012-722,C501,B623

Order No.: F06

Federal Project No.: BR-012-4(052)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0150 | 505 | 13282 GUARDRAIL GR-MGS1, 9' POST | 507.000 LF | _____ | _____ | _____ | _____ |
| 0160 | 505 | 13286 GUARDRAIL TERMINAL GR- MGS2 | 3.000 EA | _____ | _____ | _____ | _____ |
| 0170 | 505 | 13394 FIXED OBJECT ATTACH. GR- FOA-5 | 3.000 EA | _____ | _____ | _____ | _____ |
| 0180 | 505 | 13607 IMPACT ATTEN. STD. IA-1, TL- 3>=40 MPH DES.SP. | 1.000 EA | _____ | _____ | _____ | _____ |
| 0190 | 507 | 22643 FENCE FE-CL | 40.000 LF | _____ | _____ | _____ | _____ |
| 0200 | 507 | 22653 LINE BRACE UNIT FE-CL | 2.000 EA | _____ | _____ | _____ | _____ |
| 0210 | 507 | 22663 CORNER BRACE UNIT FE-CL | 2.000 EA | _____ | _____ | _____ | _____ |
| 0220 | ATTD | 23517 BARBED WIRE | 40.000 LF | _____ | _____ | _____ | _____ |
| 0230 | 511 | 24100 ALLAYING DUST | 540.000 HR | _____ | _____ | _____ | _____ |
| 0240 | 512 | 24150 TYPE 3 BARRICADE 4' | 10.000 EA | _____ | _____ | _____ | _____ |
| 0250 | 512 | 24152 TYPE 3 BARRICADE 8' | 4.000 EA | _____ | _____ | _____ | _____ |
| 0260 | 512 | 24160 TEMPORARY (CONSTRUCTION) SIGN | 1,294.000 SF | _____ | _____ | _____ | _____ |
| 0270 | 512 | 24278 GROUP 2 CHANNELIZING DEVICES | 2,920.000 DAY | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000093093B23

Oversight/State Project No.: 0046-012-722,C501,B623

Order No.: F06

Federal Project No.: BR-012-4(052)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0280 | 512 | 24279 PORTABLE CHANGEABLE MESSAGE SIGN | 1,008.000 HR | _____ | _____ | _____ | _____ |
| 0290 | 512 | 24282 FLAGGER SERVICE | 160.000 HR | _____ | _____ | _____ | _____ |
| 0300 | 512 | 24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC | 40.000 LF | _____ | _____ | _____ | _____ |
| 0310 | 508 | 24430 DEMOLITION OF PAVEMENT FLEXIBLE | 371.000 SY | _____ | _____ | _____ | _____ |
| 0320 | 505 | 24600 REMOVE EXISTING GUARDRAIL | 891.000 LF | _____ | _____ | _____ | _____ |
| 0330 | 504 | 25003 HANDRAIL HR-1 TYPE II | 71.000 LF | _____ | _____ | _____ | _____ |
| 0340 | 514 | 25505 FIELD OFFICE TY.I | 12.000 MO | _____ | _____ | _____ | _____ |
| 0350 | ATTD | 25565 PROGRESS SCHEDULE BASELINE | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0360 | ATTD | 25567 PROGRESS SCHEDULE UPDATES | 18.000 EA | _____ | _____ | _____ | _____ |
| 0370 | 602 | 27013 TOPSOIL CLASS A | 307.000 CY | _____ | _____ | _____ | _____ |
| 0380 | 603 | 27101 TEMPORARY SEED | 76.000 LB | _____ | _____ | _____ | _____ |
| 0390 | 603 | 27102 REGULAR SEED | 219.000 LB | _____ | _____ | _____ | _____ |
| 0400 | 603 | 27103 OVERSEEDING | 175.000 LB | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000093093B23

Oversight/State Project No.: 0046-012-722,C501,B623

Order No.: F06

Federal Project No.: BR-012-4(052)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------------|-------------|--|--------------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0410 | 603 | 27104 LEGUME SEED | 10.000 LB | _____ | _____ | _____ | _____ |
| 0420 | 603 | 27105 LEGUME OVERSEEDING | 8.000 LB | _____ | _____ | _____ | _____ |
| 0430 | 603 | 27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2 | 2,299.000 SY | _____ | _____ | _____ | _____ |
| 0440 | 603 | 27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3 | 5,977.000 SY | _____ | _____ | _____ | _____ |
| 0450 | 603 | 27230 FERTILIZER NITROGEN - N | 73.000 LB | _____ | _____ | _____ | _____ |
| 0460 | 603 | 27231 FERTILIZER PHOSPHOROUS - P | 100.000 LB | _____ | _____ | _____ | _____ |
| 0470 | 603 | 27232 FERTILIZER POTASSIUM - K | 50.000 LB | _____ | _____ | _____ | _____ |
| 0480 | 603 | 27250 LIME | 3.420 TON | _____ | _____ | _____ | _____ |
| 0490 | 303 | 27422 DEWATERING BASIN EC-8 | 2.000 EA | _____ | _____ | _____ | _____ |
| 0500 | 303 | 27430 SILTATION CONTROL EXCAVATION | 246.000 CY | _____ | _____ | _____ | _____ |
| 0510 | 303 | 27505 TEMP. SILT FENCE TYPE A | 1,400.000 LF | _____ | _____ | _____ | _____ |
| 0520 | 520 | 45512 CONCRETE ENCASEMENT TOWN OF BLACKSTONE | 13.000 LF | _____ | _____ | _____ | _____ |
| 0530 | 702 | 50012 ROAD EDGE DELINEATOR, ED-2 | 2.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000093093B23

Oversight/State Project No.: 0046-012-722,C501,B623

Order No.: F06

Federal Project No.: BR-012-4(052)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------------|-------------|---|--------------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0540 | 700 | 50320 REMOVE EXISTING 1 POST SIGN PANEL | 4.000 EA | _____ | _____ | _____ | _____ |
| 0550 | 700 | 50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL | 10.000 EA | _____ | _____ | _____ | _____ |
| 0560 | 700 | 50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A | 10.000 EA | _____ | _____ | _____ | _____ |
| 0570 | 704 | 54032 TYPE B CLASS I PVMT LINE MRKG 4" | 1,474.000 LF | _____ | _____ | _____ | _____ |
| 0580 | 704 | 54034 TYPE B CLASS I PVMT LINE MRKG 6" | 1,044.000 LF | _____ | _____ | _____ | _____ |
| 0590 | 404 ATTD | 60420 CONCRETE LOW SHRINKAGE CLASS A4 MODIFIED (LIGHTWEIGHT) | 392.600 CY | _____ | _____ | _____ | _____ |
| 0600 | 404 ATTD | 60420 CONCRETE LOW SHRINKAGE CLASS A4 MODIFIED (LIGHTWEIGHT) (CATWALK) | 4.800 CY | _____ | _____ | _____ | _____ |
| 0610 | 316 | 60450 CONC. CLASS A4 BRIDGE APPR. SLAB | 27.400 CY | _____ | _____ | _____ | _____ |
| 0620 | 316 | 60452 REINF. STEEL BRIDGE APPR. SLAB | 5,270.000 LB | _____ | _____ | _____ | _____ |
| 0630 | 404 | 60490 BRIDGE DECK GROOVING | 1,495.000 SY | _____ | _____ | _____ | _____ |
| 0640 | 404 | 60495 COVER DEPTH SURVEY | 1,597.000 SY | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000093093B23

Oversight/State Project No.: 0046-012-722,C501,B623

Order No.: F06

Federal Project No.: BR-012-4(052)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0650 | 406 | 61711 CORROSION RESISTANT REINF. STEEL CL. I | 87,340.000 LB | _____ | _____ | _____ | _____ |
| 0660 | 407 ATTD | 61801 STRUCT. STEEL PIER CAPS- GRADE 50CR | 173,300.000 LB | _____ | _____ | _____ | _____ |
| 0670 | 407 | 61822 STR. STEEL ROLLED BEAM ASTM A709 GRADE 50W | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0680 | 410 | 62034 RAILING, CPSR 2 RAIL | 928.000 LF | _____ | _____ | _____ | _____ |
| 0690 | 420 | 62413 ADHESIVE BASED JOINT SEALER CLASS I, 2-1/2" | 84.000 LF | _____ | _____ | _____ | _____ |
| 0700 | 406 | 62533 BRIDGE SUPERSTRUCTURE CORROSION RESISTANT REINF. STEEL CL. I (CATWALK) | 440.000 LB | _____ | _____ | _____ | _____ |
| 0710 | 401 | 64011 STRUCTURE EXCAVATION | 704.000 CY | _____ | _____ | _____ | _____ |
| 0720 | 401 | 64015 SELECT BACKFILL ABUTMENT ZONE | 434.000 TON | _____ | _____ | _____ | _____ |
| 0730 | 401 | 64032 GEOCOMPOSITE WALL DRAIN | 16.000 SY | _____ | _____ | _____ | _____ |
| 0740 | 401 ATTD | 64037 NS PIPE UNDERDRAIN 4" | 105.000 LF | _____ | _____ | _____ | _____ |
| 0750 | 403 | 64038 PREBORING PILE 10" | 845.000 LF | _____ | _____ | _____ | _____ |
| 0760 | ATTD | 64102 DYNAMIC PILE TEST END BEARING PILES | 2.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000093093B23

Oversight/State Project No.: 0046-012-722,C501,B623

Order No.: F06

Federal Project No.: BR-012-4(052)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0770 | 403 | 64110 STEEL PILES 10" | 845.000 LF | _____ | _____ | _____ | _____ |
| 0780 | 403 | 64755 PILE POINT FOR 10" STEEL PILE | 42.000 EA | _____ | _____ | _____ | _____ |
| 0790 | 403 | 64759 DRIVING TEST FOR 10" STEEL PILE | 40.000 LF | _____ | _____ | _____ | _____ |
| 0800 | 404 | 65013 CONCRETE CLASS A3 | 83.300 CY | _____ | _____ | _____ | _____ |
| 0810 | 406 | 65200 REINF. STEEL | 4,220.000 LB | _____ | _____ | _____ | _____ |
| 0820 | 406 | 65211 CORROSION RESISTANT REINF. STEEL CL. I | 5,250.000 LB | _____ | _____ | _____ | _____ |
| 0830 | 410 | 65840 RAILING, CPSR 2 RAIL | 44.000 LF | _____ | _____ | _____ | _____ |
| 0840 | 414 | 66126 DRY RIPRAP CL.I 26" | 235.000 SY | _____ | _____ | _____ | _____ |
| 0850 | ATTD | 66924 BRIDGE SUBSTRUCTURE STAINLESS STEEL UNDERCUT ANCHOR, 1 1/4" | 108.000 EA | _____ | _____ | _____ | _____ |
| 0860 | 507 | 67088 PED. FENCE 8' | 108.000 LF | _____ | _____ | _____ | _____ |
| 0870 | ATTD | 67400 DECK DRAINAGE SYSTEM | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0875 | 412 | 68180 EMBEDDED GALVANIC ANODES | 278.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000093093B23

Oversight/State Project No.: 0046-012-722,C501,B623

Order No.: F06

Federal Project No.: BR-012-4(052)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|-------------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0880 | ATTD | 67904 BRIDGE INCIDENTALS PUMP HOUSE ACCESS AND MAINTENANCE | LUMP SUM | LUMP SUM | | | |
| 0890 | 427 | 68408 SILICONE JOINT SEALANT 1" | 78.000 LF | | | | |
| 0900 | 413 ATTD | 68900 REM. PORT. OF EX. STR. 1916 | LUMP SUM | LUMP SUM | | | |
| 0910 | 412 | 69500 CONCRETE SUBSTRUCT. SURFACE REPAIR | 80.000 SY | | | | |
| 0920 | 416 | 69835 WATERPROOFING - EPOXY RESIN TYPE EP-3B/EP-3T | 235.000 SY | | | | |
| 0930 | 412 | 69901 BR. SUBSTR. WID./REPAIR CRACK REPAIR TYPE B | 475.000 LF | | | | |
| 0935 | ATTD | 69903 BR. SUBSTR. WID./REPAIR HIGH STRENGTH GROUT | 72.000 CF | | | | |
| 0940 | ATTD | 69906 BR. SUBSTR. WID./REPAIR UNDERCUT ANCHOR TESTING | LUMP SUM | LUMP SUM | | | |
| Section: 0001 | | | | Total: | | | |
| | | | | Total Bid: | | | |