

Schedule of Items

Proposal ID: C0000115484C01

Oversight/State Project No.: 6058-140-286,C501

Order No.: J91

Federal Project No.: STP-5140(224); (223)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	302	302SD20-0028 18" PIPE	60.000 LF				
0030	302	302SD20-0198 15" END SECTION ES-1 OR 2	3.000 EA				
0040	302	302SD20-0200 18" END SECTION ES-1 OR 2	2.000 EA				
0050	ATTD	302SX20-0013 PIPE 15" PIPE	34.000 LF				
0060	303	303SD20-0007 BORROW EXCAVATION	130.000 CY				
0070	303	303SD20-0023 CHECK DAM ROCK TY. II	18.000 EA				
0080	303	303SD20-0025 CHECK DAM SEDIMENT RETENTION ROLL 20"	46.000 EA				
0090	303	303SD20-0029 SILTATION CONTROL EXCAVATION	262.000 CY				
0100	303	303SD20-0030 INLET PROTECTION TYPE A	2.000 EA				
0110	303	303SD20-0031 INLET PROTECTION TYPE B	1.000 EA				
0120	303	303SD20-0034 TEMP. SILT FENCE TYPE A	1,329.000 LF				
0130	ATTD	303SX20-0003 EXCAVATION REGULAR EXCAVATION	311.000 CY				
0140	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	493.000 TON				

Schedule of Items

Proposal ID: C0000115484C01

Oversight/State Project No.: 6058-140-286,C501

Order No.: J91

Federal Project No.: STP-5140(224); (223)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	315	315SD20-0001 ASPHALT CONCRETE TY. SM- 12.5A CONST	334.000 TON	_____	_____	_____	_____
0160	315	315SD20-0010 ASPHALT CONCRETE TY. BM- 25.0A CONST	195.000 TON	_____	_____	_____	_____
0170	315	315SX20-0011 SAW-CUT ASPH CONC SAW- CUT 5" DEPTH	225.000 LF	_____	_____	_____	_____
0180	310	315SX20-0011 SAW-CUT ASPH CONC SAW- CUT ASPH CONC (5" DEPTH)	209.000 LF	_____	_____	_____	_____
0190	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	14.000 TON	_____	_____	_____	_____
0200	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	350.000 LF	_____	_____	_____	_____
0210	508	508SD20-0001 OBSCURING ROADWAY	8.000 UNIT	_____	_____	_____	_____
0220	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	1,410.000 SY	_____	_____	_____	_____
0230	510	510SD20-0038 ADJUST EXIST. VALVE & BOX	2.000 EA	_____	_____	_____	_____
0240	510	510SD20-0050 ADJUST EXIST FRAME & COVER	2.000 EA	_____	_____	_____	_____
0250	510	510SX20-0039 REMOVE EXIST. REMOVAL OF EXISTING PIPE	15.000 LF	_____	_____	_____	_____
0260	511	511SD20-0001 ALLAYING DUST	170.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115484C01

Oversight/State Project No.: 6058-140-286,C501

Order No.: J91

Federal Project No.: STP-5140(224); (223)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	512	512SD20-0012 TYPE 3 BARRICADE 4'	2.000 EA	_____	_____	_____	_____
0280	512	512SD20-0013 TYPE 3 BARRICADE 8'	14.000 EA	_____	_____	_____	_____
0290	512	512SD20-0014 TEMPORARY SIGN	512.000 SF	_____	_____	_____	_____
0300	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	968.000 DAY	_____	_____	_____	_____
0310	512	512SD20-0027 FLAGGER SERVICE	920.000 HR	_____	_____	_____	_____
0320	512	512SD20-0029 WARNING LIGHT TY. B	310.000 DAY	_____	_____	_____	_____
0330	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	20.000 LF	_____	_____	_____	_____
0340	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	32.000 DAY	_____	_____	_____	_____
0350	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0360	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	1,780.000 SY	_____	_____	_____	_____
0370	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0380	602	602SD20-0004 TOPSOIL CLASS B	536.000 CY	_____	_____	_____	_____
0390	603	603SD20-0002 TEMPORARY SEED	123.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115484C01

Oversight/State Project No.: 6058-140-286,C501

Order No.: J91

Federal Project No.: STP-5140(224); (223)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	603	603SD20-0003 REGULAR SEED	297.000 LB	_____	_____	_____	_____
0410	603	603SD20-0004 OVERSEEDING	237.000 LB	_____	_____	_____	_____
0420	603	603SD20-0005 LEGUME SEED	5.000 LB	_____	_____	_____	_____
0430	603	603SD20-0006 LEGUME OVERSEEDING	4.000 LB	_____	_____	_____	_____
0440	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	5,022.000 SY	_____	_____	_____	_____
0450	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	6,558.000 SY	_____	_____	_____	_____
0460	603	603SD20-0014 FERTILIZER NITROGEN - N	123.000 LB	_____	_____	_____	_____
0470	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	86.000 LB	_____	_____	_____	_____
0480	603	603SD20-0016 FERTILIZER POTASSIUM - K	86.000 LB	_____	_____	_____	_____
0490	603	603SD20-0017 LIME	6.770 TON	_____	_____	_____	_____
0500	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	157.000 SY	_____	_____	_____	_____
0510	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	4.000 EA	_____	_____	_____	_____
0520	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	20.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115484C01

Oversight/State Project No.: 6058-140-286,C501

Order No.: J91

Federal Project No.: STP-5140(224); (223)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	18.000 LF	_____	_____	_____	_____
0540	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	4.000 EA	_____	_____	_____	_____
0550	700	700SX20-0029 RELOCATE EXISTING SIGN PANEL RELOCATE SIGN	1.000 EA	_____	_____	_____	_____
0560	701	701SD20-0001 SIGN PANEL	44.000 SF	_____	_____	_____	_____
0570	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	1,700.000 LF	_____	_____	_____	_____
0580	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	80.000 LF	_____	_____	_____	_____
0590	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	63.000 LF	_____	_____	_____	_____
0600	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	2.000 EA	_____	_____	_____	_____

Section: 0001

Total: _____

Total Bid: _____