

Schedule of Items

Proposal ID: C0000119937N01

Oversight/State Project No.: DP3A-015-F24, N501

Order No.: P43

Federal Project No.: NONE

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	302	302SD20-0023 15" PIPE	130.000 LF	_____	_____	_____	_____
0020	302	302SD20-0028 18" PIPE	75.000 LF	_____	_____	_____	_____
0030	302	302SD20-0029 18" JACKED & BORED PIPE	243.000 LF	_____	_____	_____	_____
0040	302	302SD20-0198 15" END SECTION ES-1 OR 2	2.000 EA	_____	_____	_____	_____
0050	302	302SD20-0200 18" END SECTION ES-1 OR 2	3.000 EA	_____	_____	_____	_____
0060	302	302SD20-0446 DROP INLET DI-5	1.000 EA	_____	_____	_____	_____
0070	302	302SD20-0662 MANHOLE MH-1 OR 2	6.000 LF	_____	_____	_____	_____
0080	302	302SD20-0663 FRAME & COVER MH-1	1.000 EA	_____	_____	_____	_____
0090	303	303SD20-0004 GRADING	LUMP SUM	LUMP SUM		_____	_____
0100	303	303SD20-0006 EXTRA EXCAVATION	50.000 CY	_____	_____	_____	_____
0110	303	303SD20-0023 CHECK DAM ROCK TY. II	6.000 EA	_____	_____	_____	_____
0120	303	303SD20-0029 SILTATION CONTROL EXCAVATION	100.000 CY	_____	_____	_____	_____
0130	303	303SD20-0034 TEMP. SILT FENCE TYPE A	350.000 LF	_____	_____	_____	_____
0140	308	308SD20-0001 AGGR. MATL. NO. 1	900.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119937N01

Oversight/State Project No.: DP3A-015-F24, N501

Order No.: P43

Federal Project No.: NONE

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	255.000 TON	_____	_____	_____	_____
0160	315	315SD20-0034 ASPH. CONC. TY. SM-12.5D MAINT	10.000 TON	_____	_____	_____	_____
0170	315	315SD20-0047 ASPH. CONC. TY. BM-25.0A MAINT	54.000 TON	_____	_____	_____	_____
0180	ATTD	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH SAW-CUT	105.000 LF	_____	_____	_____	_____
0190	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	8.000 TON	_____	_____	_____	_____
0200	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	11.000 TON	_____	_____	_____	_____
0210	502	502SD20-0003 PAVED DITCH PG-2A	22.000 SY	_____	_____	_____	_____
0220	302 504	504SD20-0001 CONCRETE CLASS A3 MISC.	1.478 CY	_____	_____	_____	_____
0230	507	507SD20-0001 FENCE FE-W1	325.000 LF	_____	_____	_____	_____
0240	507	507SD20-0003 LINE BRACE UNIT FE-W1 OR FE-W2	2.000 EA	_____	_____	_____	_____
0250	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	430.000 LF	_____	_____	_____	_____
0260	ATTD, 507	507SX20-0001 FENCE WOOD BOARD	68.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119937N01

Oversight/State Project No.: DP3A-015-F24, N501

Order No.: P43

Federal Project No.: NONE

Contractor: _____

SECTION: 1

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	65.000 SY	_____	_____	_____	_____
0280	509	509SD20-0001 FLOWABLE BACKFILL	15.000 CY	_____	_____	_____	_____
0290	511	511SD20-0001 ALLAYING DUST	24.000 HR	_____	_____	_____	_____
0300	512	512SD20-0014 TEMPORARY SIGN	164.000 SF	_____	_____	_____	_____
0310	512	512SD20-0015 AGGREGATE MATERIAL NO. 25 OR 26	100.000 TON	_____	_____	_____	_____
0320	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	2,208.000 HR	_____	_____	_____	_____
0330	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	2,950.000 DAY	_____	_____	_____	_____
0340	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	2,688.000 HR	_____	_____	_____	_____
0350	512	512SD20-0026 ELECTRONIC ARROW BOARD	672.000 HR	_____	_____	_____	_____
0360	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	70.000 LF	_____	_____	_____	_____
0370	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	36.000 DAY	_____	_____	_____	_____
0380	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0390	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000119937N01

Oversight/State Project No.: DP3A-015-F24, N501

Order No.: P43

Federal Project No.: NONE

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	602	602SD20-0002 TOPSOIL CLASS A	138.000 CY	_____	_____	_____	_____
0410	603	603SD20-0002 TEMPORARY SEED	25.000 LB	_____	_____	_____	_____
0420	603	603SD20-0003 REGULAR SEED	250.000 LB	_____	_____	_____	_____
0430	603	603SD20-0004 OVERSEEDING	200.000 LB	_____	_____	_____	_____
0440	603	603SD20-0005 LEGUME SEED	2.000 LB	_____	_____	_____	_____
0450	603	603SD20-0006 LEGUME OVERSEEDING	2.000 LB	_____	_____	_____	_____
0460	603	603SD20-0014 FERTILIZER NITROGEN - N	72.000 LB	_____	_____	_____	_____
0470	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	47.000 LB	_____	_____	_____	_____
0480	603	603SD20-0016 FERTILIZER POTASSIUM - K	47.000 LB	_____	_____	_____	_____
0490	603	603SD20-0017 LIME	3.000 TON	_____	_____	_____	_____
0500	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	4.000 EA	_____	_____	_____	_____
0510	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	28.000 LF	_____	_____	_____	_____
0520	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	4.000 EA	_____	_____	_____	_____
0530	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	70.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119937N01

Oversight/State Project No.: DP3A-015-F24, N501

Order No.: P43

Federal Project No.: NONE

Contractor: _____

Section: 1

Total: _____

Total Bid: _____