

Schedule of Items

Proposal ID: C000001852M01D

Oversight/State Project No.: 0602-167-181, M501

Order No.: J31

Federal Project No.: STP-5167(003); STP-065(037)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0002 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION .	LUMP SUM	LUMP SUM			
0020	302 406	302SD20-0005 REINF. STEEL	4.000 LB				
0030	302	302SD20-0023 15" PIPE	554.000 LF				
0040	302	302SD20-0025 15" CONC. PIPE	166.000 LF				
0050	302	302SD20-0027 15" STORM SEWER PIPE	38.000 LF				
0060	302	302SD20-0028 18" PIPE	24.000 LF				
0070	302	302SD20-0133 23" X 14" ELLIPTICAL CONC. PIPE	58.000 LF				
0080	302	302SD20-0143 45" X 29" ELLIPTICAL CONC. PIPE	54.000 LF				
0090	302	302SD20-0198 15" END SECTION ES-1 OR 2	1.000 EA				
0100	302	302SD20-0199 15" END SECTION ES-1	2.000 EA				
0110	302	302SD20-0221 23" X 14" END SECTION ES-1A	4.000 EA				
0120	302	302SD20-0225 45" X 29" END SECTION ES-1A	1.000 EA				
0130	302	302SD20-0662 MANHOLE MH-1 OR 2	4.800 LF				

Schedule of Items

Proposal ID: C000001852M01D

Oversight/State Project No.: 0602-167-181, M501

Order No.: J31

Federal Project No.: STP-5167(003); STP-065(037)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	302SD20-0663 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0150	302	302SD20-0673 STORMWATER MAN.DRAIN.STR.SWM-1	13.100 LF	_____	_____	_____	_____
0160	303	303SD20-0004 GRADING	LUMP SUM	LUMP SUM		_____	_____
0170	303	303SD20-0006 EXTRA EXCAVATION	50.000 CY	_____	_____	_____	_____
0180	303	303SD20-0021 TEMPORARY DIVERSION DIKE	217.000 LF	_____	_____	_____	_____
0190	303	303SD20-0023 CHECK DAM ROCK TY. II	66.000 EA	_____	_____	_____	_____
0200	303	303SD20-0028 DEWATERING BASIN EC-8	1.000 EA	_____	_____	_____	_____
0210	303	303SD20-0029 SILTATION CONTROL EXCAVATION	778.000 CY	_____	_____	_____	_____
0220	303	303SD20-0030 INLET PROTECTION TYPE A	1.000 EA	_____	_____	_____	_____
0230	303	303SD20-0034 TEMP. SILT FENCE TYPE A	8,186.000 LF	_____	_____	_____	_____
0240	303	303SD20-0035 TEMP. SEDIMENT BASIN EXCAVATION	1,455.000 CY	_____	_____	_____	_____
0250	303	303SD20-0036 STORM WATER MAN. BASIN EXCAV.	295.000 CY	_____	_____	_____	_____
0260	303	303SX20-0006 BORROW EXCAVATION MIN CBR-15	4,795.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000001852M01D

Oversight/State Project No.: 0602-167-181, M501

Order No.: J31

Federal Project No.: STP-5167(003); STP-065(037)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	305	305SD20-0012 AGGR.BASE MAT.TY. I NO.21A OR 21B	71.000 TON	_____	_____	_____	_____
0280	ATTD	305SP20-0005 MACHINING SHOULDERS	12,038.000 LF	_____	_____	_____	_____
0290	211	305SX20-0002 AGGR. MATL RECLAIMED ASPHALT PAVEMENT (RAP) MATERIAL	4,933.000 TON	_____	_____	_____	_____
0300	307	307SD20-0001 HYDRAULIC CEMENT	466.000 TON	_____	_____	_____	_____
0310	308	308SD20-0001 AGGR. MATL. NO. 1	0.600 TON	_____	_____	_____	_____
0320	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	457.000 TON	_____	_____	_____	_____
0330	310	310SD20-0001 TACK COAT	455.000 GAL	_____	_____	_____	_____
0340	312	312SD20-0003 CO.MAT.FINE AGGR.OR AGGR.NO.10	107.000 TON	_____	_____	_____	_____
0350	312	312SD20-0004 LIQUID ASPHALT	4,225.000 GAL	_____	_____	_____	_____
0360	ATTD	314SP20-0003 BLOTTED SEAL COAT TY. C-1	12,038.000 SY	_____	_____	_____	_____
0370	315	315SD20-0007 ASPHALT CONCRETE TY. SM-9.5A CONST	999.000 TON	_____	_____	_____	_____
0380	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	122.000 LF	_____	_____	_____	_____
0390	ATTD	315SX20-0013 FULL DEPTH RECLAMATION 8"	21,119.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000001852M01D

Oversight/State Project No.: 0602-167-181, M501

Order No.: J31

Federal Project No.: STP-5167(003); STP-065(037)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	316	316SD20-0030 CONCRETE ENTRANCE PAVE. 7"	64.000 SY	_____	_____	_____	_____
0410	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	2.000 TON	_____	_____	_____	_____
0420	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	8.000 TON	_____	_____	_____	_____
0430	414	414SD20-0010 DRY RIPRAP CL.I 18"	182.000 TON	_____	_____	_____	_____
0440	414	414SD20-0012 DRY RIPRAP CL.I 26"	24.000 TON	_____	_____	_____	_____
0450	502	502SD20-0014 CURB, STD. CG-3	469.000 LF	_____	_____	_____	_____
0460	502	502SD20-0024 COMB. CURB & GUTTER, STD. CG-7	574.000 LF	_____	_____	_____	_____
0470	502	502SD20-0025 COMB. CURB & GUTTER, RAD. CG-7	24.000 LF	_____	_____	_____	_____
0480	502	502SD20-0029 ENTRANCE GUTTER CG-9D	22.000 SY	_____	_____	_____	_____
0490	ATTD	502SX20-0006 PAVED DITCH FLEXIBLE CONC MAT	442.000 SY	_____	_____	_____	_____
0500	502	502SX20-0010 SAW CUT H.C.C. ITEMS (FULL DEPTH) CURB &/OR SIDEWALK	22.000 LF	_____	_____	_____	_____
0510	302 504	504SD20-0001 CONCRETE CLASS A3 MISC.	29.900 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000001852M01D

Oversight/State Project No.: 0602-167-181, M501

Order No.: J31

Federal Project No.: STP-5167(003); STP-065(037)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	1.000 SY	_____	_____	_____	_____
0530	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	22.000 SY	_____	_____	_____	_____
0540	504	504SD20-0005 GEOTEXTILE DRAINAGE FABRIC	163.200 SY	_____	_____	_____	_____
0550	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	246.000 SY	_____	_____	_____	_____
0560	509	509SD20-0001 FLOWABLE BACKFILL	1.340 CY	_____	_____	_____	_____
0570	511	511SD20-0001 ALLAYING DUST	50.000 HR	_____	_____	_____	_____
0580	512	512SD20-0013 TYPE 3 BARRICADE 8'	24.000 EA	_____	_____	_____	_____
0590	512	512SD20-0014 TEMPORARY SIGN	929.000 SF	_____	_____	_____	_____
0600	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	3,360.000 DAY	_____	_____	_____	_____
0610	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	336.000 HR	_____	_____	_____	_____
0620	512	512SD20-0027 FLAGGER SERVICE	968.000 HR	_____	_____	_____	_____
0630	512	512SD20-0029 WARNING LIGHT TY. B	994.000 DAY	_____	_____	_____	_____
0640	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	384.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000001852M01D

Oversight/State Project No.: 0602-167-181, M501

Order No.: J31

Federal Project No.: STP-5167(003); STP-065(037)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM			
0660	514	514SD20-0003 FIELD OFFICE TY.III	9.000 MO				
0670	ATTD	516SX20-0008 DEMO. OF BLDG. DEMOLITION OF LIGHT POLE	LUMP SUM	LUMP SUM			
0680	517	517SD20-0002 CONSTRUCTION SURVEYING MIN. PLAN	LUMP SUM	LUMP SUM			
0690	ATTD	523SP20-0002 STORM WATER MANAGEMENT LOW PERMEABILITY LINER	300.000 SY				
0700	602	602SD20-0003 TOPSOIL CLASS B 2"	4.060 ACRE				
0710	603	603SD20-0002 TEMPORARY SEED	406.000 LB				
0720	603	603SD20-0003 REGULAR SEED	609.000 LB				
0730	603	603SD20-0004 OVERSEEDING	487.000 LB				
0740	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	15,851.000 SY				
0750	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	28,362.000 SY				
0760	603	603SD20-0014 FERTILIZER NITROGEN - N	388.000 LB				
0770	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	533.000 LB				

Proposal ID: C000001852M01D

Oversight/State Project No.: 0602-167-181, M501

Order No.: J31

Federal Project No.: STP-5167(003); STP-065(037)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0780	603	603SD20-0016 FERTILIZER POTASSIUM - K	266.000 LB	_____	_____	_____	_____
0790	603	603SD20-0017 LIME	18.270 TON	_____	_____	_____	_____
0800	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	894.000 SY	_____	_____	_____	_____
0810	700	700SD20-0002 SIGN POST WOOD 6" X 6"	20.000 LF	_____	_____	_____	_____
0820	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	7.000 EA	_____	_____	_____	_____
0830	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	120.000 LF	_____	_____	_____	_____
0840	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	14.000 EA	_____	_____	_____	_____
0850	701	701SD20-0001 SIGN PANEL	106.160 SF	_____	_____	_____	_____
0860	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	24,530.000 LF	_____	_____	_____	_____
0870	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	24.000 LF	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	