

Schedule of Items

Proposal ID: C00000111066B18 Oversight/State Project No.: 0311-080-913, B618

Order No.: K12

Federal Project No.: HSIP-080-2(031)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0002 CLEARING AND GRUBBING	0.620 ACRE	_____	_____	_____	_____
0020	302	302SD20-0013 ENDWALL EW-12	1.000 EA	_____	_____	_____	_____
0030	303	303SD20-0001 REGULAR EXCAVATION	496.000 CY	_____	_____	_____	_____
0040	303	303SD20-0029 SILTATION CONTROL EXCAVATION	100.000 CY	_____	_____	_____	_____
0050	303	303SD20-0034 TEMP. SILT FENCE TYPE A	625.000 LF	_____	_____	_____	_____
0060	305	305SD20-0001 BORROW EXCAVATION	114.000 CY	_____	_____	_____	_____
0070	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	40.000 TON	_____	_____	_____	_____
0080	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	1,083.000 CY	_____	_____	_____	_____
0090	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	732.000 TON	_____	_____	_____	_____
0100	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	200.000 SY	_____	_____	_____	_____
0110	401	401SD20-0007 COFFERDAM	1.000 EA	_____	_____	_____	_____
0120	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST.	23.000 CY	_____	_____	_____	_____
0130	404	404SD20-0010 COVER DEPTH SURVEY CONST.	100.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00000111066B18 Oversight/State Project No.: 0311-080-913, B618

Order No.: K12

Federal Project No.: HSIP-080-2(031)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	269.700 CY	_____	_____	_____	_____
0150	406	406SD20-0003 CR REINF. STEEL CL. I SPR. STRUCT. CONST.	5,200.000 LB	_____	_____	_____	_____
0160	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	8,470.000 LB	_____	_____	_____	_____
0170	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	33,340.000 LB	_____	_____	_____	_____
0180	407	407SD20-0012 STR. STEEL ROLLED BEAM ASTM A709 GRADE50W	LUMP SUM	LUMP SUM	_____	_____	_____
0190	410, ATTD	410SX20-0001 ARCHITECTURAL TREATMENT .	255.000 SY	_____	_____	_____	_____
0200	ATTD	410SX20-0012 BRIDGE INCIDENTALS PARAPETS WITH NO RAILING	180.000 LF	_____	_____	_____	_____
0210	ATTD	410SX20-0014 BRIDGE INCIDENTALS METAL STAIRS	LUMP SUM	LUMP SUM	_____	_____	_____
0220	ATTD	410SX20-0017 BRIDGE INCIDENTALS STEEL BOLLARDS	4.000 EA	_____	_____	_____	_____
0230	412, ATTD	412SX20-0025 CONC. SURFACE COLOR COATING CONST. (VA STR. NO. B618)	375.000 SY	_____	_____	_____	_____
0240	414	414SD20-0010 DRY RIPRAP CL. I 18"	511.000 TON	_____	_____	_____	_____
0250	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE B618	3.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00000111066B18 Oversight/State Project No.: 0311-080-913, B618

Order No.: K12

Federal Project No.: HSIP-080-2(031)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	501	501SD20-0001 UNDERDRAIN UD-1	257.000 LF	_____	_____	_____	_____
0270	501	501SD20-0009 OUTLET PIPE	53.000 LF	_____	_____	_____	_____
0280	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	168.000 SY	_____	_____	_____	_____
0290	504	504SD20-0005 GEOTEXTILE DRAINAGE FABRIC	526.000 SY	_____	_____	_____	_____
0300	504	504SD20-0010 CONCRETE CLASS A-3 MISC	8.200 CY	_____	_____	_____	_____
0310	504	504SD20-0013 HANDRAIL HR-1 TYPE I	87.000 LF	_____	_____	_____	_____
0320	504	504SD20-0014 HANDRAIL HR-1 TYPE II	230.000 LF	_____	_____	_____	_____
0330	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	506.000 LF	_____	_____	_____	_____
0340	507	507SD20-0032 PEDESTRIAN FENCE 8'	177.000 LF	_____	_____	_____	_____
0350	ATTD	507SX20-0013 FENCE 6' TEMPORARY	1,080.000 LF	_____	_____	_____	_____
0360	511	511SD20-0001 ALLAYING DUST	10.000 HR	_____	_____	_____	_____
0370	512	512SD20-0014 TEMPORARY SIGN	270.000 SF	_____	_____	_____	_____
0380	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	56.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00000111066B18 Oversight/State Project No.: 0311-080-913, B618

Order No.: K12

Federal Project No.: HSIP-080-2(031)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	1,274.000 DAY	_____	_____	_____	_____
0400	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	1,500.000 HR	_____	_____	_____	_____
0410	512	512SD20-0027 FLAGGER SERVICE	1,500.000 HR	_____	_____	_____	_____
0420	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	100.000 DAY	_____	_____	_____	_____
0430	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0440	514	514SD20-0002 FIELD OFFICE TY.II	12.000 MO	_____	_____	_____	_____
0450	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0460	ATTD	520SX20-0004 SEWER CLEANOUT 6"	1.000 EA	_____	_____	_____	_____
0470	602	602SD20-0004 TOPSOIL CLASS B	43.000 CY	_____	_____	_____	_____
0480	603	603SD20-0002 TEMPORARY SEED	19.200 LB	_____	_____	_____	_____
0490	603	603SD20-0003 REGULAR SEED	44.000 LB	_____	_____	_____	_____
0500	603	603SD20-0004 OVERSEEDING	35.000 LB	_____	_____	_____	_____
0510	603	603SD20-0005 LEGUME SEED	2.000 LB	_____	_____	_____	_____
0520	603	603SD20-0006 LEGUME OVERSEEDING	2.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00000111066B18 Oversight/State Project No.: 0311-080-913, B618
 Order No.: K12 Federal Project No.: HSIP-080-2(031)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	1,742.000 SY	_____	_____	_____	_____
0540	603	603SD20-0014 FERTILIZER NITROGEN - N	16.000 LB	_____	_____	_____	_____
0550	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	11.000 LB	_____	_____	_____	_____
0560	603	603SD20-0016 FERTILIZER POTASSIUM - K	11.000 LB	_____	_____	_____	_____
0570	603	603SD20-0017 LIME	0.880 TON	_____	_____	_____	_____
0580	701	701SD20-0001 SIGN PANEL	13.500 SF	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	