

Schedule of Items

Proposal ID: C0000122213B32

Oversight/State Project No.: 0095-042-793,B632, B633

Order No.: J88

Federal Project No.: BFP-964-4(169)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	315	315SD20-0002 ASPHALT CONCRETE TY. SM-12.5D CONST	846.000 TON	_____	_____	_____	_____
0020	315	315SD20-0005 ASPHALT CONCRETE TY. IM-19.0D CONST	846.000 TON	_____	_____	_____	_____
0030	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	5,660.000 LF	_____	_____	_____	_____
0040	404	404SD20-0020 BRIDGE DECK GROOVING MAINT.	2,340.000 SY	_____	_____	_____	_____
0050	412	412SD20-0013 CRACK REPAIR TYPE B	731.000 LF	_____	_____	_____	_____
0060	412	412SD20-0017 EMBEDDED GALVANIC ANODES	101.000 EA	_____	_____	_____	_____
0070	412	412SD20-0032 H.E.S. PATCHING TYPE A	4.000 SY	_____	_____	_____	_____
0080	412	412SD20-0034 H.E.S. PATCHING TYPE B	20.000 SY	_____	_____	_____	_____
0090	412	412SD20-0049 CONC. SUPERSTR. SURFACE REPAIR	9.000 SY	_____	_____	_____	_____
0100	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR	6.000 SY	_____	_____	_____	_____
0110	412	412SD20-0062 RECONSTRUCT BRIDGE SEAT TYPE A	18.000 EA	_____	_____	_____	_____
0120	ATTD	412SX20-0012 SUPERSTR. WID./REPAIR STRUCTURAL STEEL REPAIR	18,925.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122213B32

Oversight/State Project No.: 0095-042-793,B632, B633

Order No.: J88

Federal Project No.: BFP-964-4(169)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	ATTD	412SX20-0015 SUPERSTR. WID./REPAIR DECK SLAB CLOSURE (LMC- VE) - PIERS	234.000 SY	_____	_____	_____	_____
0140	ATTD	412SX20-0028 RECONSTR. EXPAN. JOINT (LMC-VE)	352.000 LF	_____	_____	_____	_____
0150	416	416SD20-0003 WATERPROOFING – EPOXY RESIN TYPE EP-3B/EP-3T	264.000 SY	_____	_____	_____	_____
0160	421	421SD20-0007 ELASTOMERIC EXPANS. DAM 2+” TO 3” SPRSTR MAINT	352.000 LF	_____	_____	_____	_____
0170	425	425SD20-0001 REMOVE ASPHALT CONCRETE OVERLAY	80.000 SY	_____	_____	_____	_____
0180	425	425SD20-0003 TYPE A MILLING 1”	2,340.000 SY	_____	_____	_____	_____
0190	425	425SD20-0015 PLACE VERY EARLY MOD.CONC.OVERLAY	2,340.000 SY	_____	_____	_____	_____
0200	425	425SD20-0022 TYPE A HYDRO-DEMOLITION 1/2”	2,340.000 SY	_____	_____	_____	_____
0210	ATTD	425SX20-0004 FURN VERY EARLY LATEX MOD CONC. (1 1/2”)	98.000 CY	_____	_____	_____	_____
0220	426	426SD20-0001 REPLACE BEARING	144.000 EA	_____	_____	_____	_____
0230	426	426SD20-0020 FIELD WELDING - FILLET WELD 5/16”	20.000 LF	_____	_____	_____	_____
0240	426	426SD20-0024 FIELD WLDG.-FULL PENTR.GRV WELD<1” THICK	25.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122213B32

Oversight/State Project No.: 0095-042-793,B632, B633

Order No.: J88

Federal Project No.: BFP-964-4(169)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	426	426SD20-0028 JACKING AND BLOCKING BEAM	144.000 EA	_____	_____	_____	_____
0260	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (VIRGINIA STRUCT. NO 2012)	3.000 DAY	_____	_____	_____	_____
0270	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (VIRGINIA STRUCT. NO 2013)	3.000 DAY	_____	_____	_____	_____
0280	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	1,520.000 LF	_____	_____	_____	_____
0290	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL-3, >=40 MPH	2.000 EA	_____	_____	_____	_____
0300	512	512SD20-0014 TEMPORARY SIGN	1,416.000 SF	_____	_____	_____	_____
0310	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	752.000 HR	_____	_____	_____	_____
0320	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	8,035.000 DAY	_____	_____	_____	_____
0330	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	792.000 HR	_____	_____	_____	_____
0340	512	512SD20-0026 ELECTRONIC ARROW BOARD	648.000 HR	_____	_____	_____	_____
0350	512	512SD20-0054 TEMP. PVMT MRKG TY. E, 6"	10,720.000 LF	_____	_____	_____	_____
0360	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	9,120.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122213B32

Oversight/State Project No.: 0095-042-793,B632, B633

Order No.: J88

Federal Project No.: BFP-964-4(169)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0370	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	16,000.000 LF	_____	_____	_____	_____
0380	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0390	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	2,387.000 SY	_____	_____	_____	_____
0400	515	515SD20-0005 FLEXIBLE PAVE. PLANING ABOVE 2"-4"	5,607.000 SY	_____	_____	_____	_____
0410	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0420	704	704SD20-0026 TYPE B CLASS VI PVMT LINE MRKG 4"	3,057.000 LF	_____	_____	_____	_____
0430	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	2,434.000 LF	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____