

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0002 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONST REC DOCS	LUMP SUM	LUMP SUM		_____.	_____.
0020	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM		_____.	_____.
0030	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	20.000 EA		_____.	_____.	_____.
0040	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM		_____.	_____.
0050	ATTD	302SD20-0002 BEDDING MATL. AGGR. NO. 57	497.000 TON		_____.	_____.	_____.
0060	302	302SD20-0013 ENDWALL EW-12	6.000 EA		_____.	_____.	_____.
0070	302	302SD20-0018 12" PIPE	95.000 LF		_____.	_____.	_____.
0080	302	302SD20-0023 15" PIPE	245.000 LF		_____.	_____.	_____.
0090	302	302SD20-0027 15" STORM SEWER PIPE	475.000 LF		_____.	_____.	_____.
0100	302	302SD20-0028 18" PIPE	185.000 LF		_____.	_____.	_____.
0110	302	302SD20-0030 18" CONC. PIPE	35.000 LF		_____.	_____.	_____.
0120	302	302SD20-0032 18" STORM SEWER PIPE	74.000 LF		_____.	_____.	_____.
0130	302	302SD20-0039 24" CONC. PIPE	43.000 LF		_____.	_____.	_____.

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	302SD20-0041 24" STORM SEWER PIPE	179.000 LF	_____	_____	_____	_____
0150	302	302SD20-0058 36" JACKED & BORED PIPE	76.000 LF	_____	_____	_____	_____
0160	302	302SD20-0059 36" CONC. PIPE	242.000 LF	_____	_____	_____	_____
0170	302	302SD20-0062 42" PIPE	96.000 LF	_____	_____	_____	_____
0180	302	302SD20-0196 12" END SECTION ES-1 OR 2	6.000 EA	_____	_____	_____	_____
0190	302	302SD20-0198 15" END SECTION ES-1 OR 2	7.000 EA	_____	_____	_____	_____
0200	302	302SD20-0200 18" END SECTION ES-1 OR 2	3.000 EA	_____	_____	_____	_____
0210	302	302SD20-0201 18" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0220	302	302SD20-0204 24" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0230	302	302SD20-0205 24" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0240	302	302SD20-0210 36" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0250	302	302SD20-0211 36" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0260	302	302SD20-0245 DROP INLET DI-2B,L=12'	1.000 EA	_____	_____	_____	_____
0270	302	302SD20-0254 DROP INLET DI-2BB,L=12'	1.000 EA	_____	_____	_____	_____
0280	302	302SD20-0262 DROP INLET DI-2C,L=12'	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	302	302SD20-0447 DROP INLET DI-7	1.000 EA	_____	_____	_____	_____
0300	302	302SD20-0448 DROP INLET DI-7A	1.000 EA	_____	_____	_____	_____
0310	302	302SD20-0655 DROP INLET DI-13 TY.I	2.000 EA	_____	_____	_____	_____
0320	302	302SD20-0662 MANHOLE MH-1 OR 2	33.000 LF	_____	_____	_____	_____
0330	302	302SD20-0663 FRAME & COVER MH-1	3.000 EA	_____	_____	_____	_____
0340	302	302SD20-0673 STORMWATER MAN.DRAIN.STR.SWM-1	13.000 LF	_____	_____	_____	_____
0350	303	303SD20-0001 REGULAR EXCAVATION	3,742.000 CY	_____	_____	_____	_____
0360	303	303SD20-0010 EMBANKMENT	621.000 CY	_____	_____	_____	_____
0370	303	303SD20-0015 SETTLEMENT PLATE	3.000 EA	_____	_____	_____	_____
0380	303	303SD20-0018 SLOPE DRAIN	12.000 EA	_____	_____	_____	_____
0390	303	303SD20-0019 EROSION CONTROL MULCH	1,682.000 SY	_____	_____	_____	_____
0400	303	303SD20-0022 CHECK DAM ROCK TY. I	18.000 EA	_____	_____	_____	_____
0410	303	303SD20-0023 CHECK DAM ROCK TY. II	138.000 EA	_____	_____	_____	_____
0420	303	303SD20-0028 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0430	303	303SD20-0029 SILTATION CONTROL EXCAVATION	2,247.000 CY	_____	_____	_____	_____
0440	303	303SD20-0030 INLET PROTECTION TYPE A	2.000 EA	_____	_____	_____	_____
0450	303	303SD20-0031 INLET PROTECTION TYPE B	6.000 EA	_____	_____	_____	_____
0460	303	303SD20-0033 TEMP. SILT FENCE TYPE B	1,824.000 LF	_____	_____	_____	_____
0470	303	303SD20-0034 TEMP. SILT FENCE TYPE A	3,045.000 LF	_____	_____	_____	_____
0480	303	303SD20-0036 STORM WATER MAN. BASIN EXCAV.	3,257.000 CY	_____	_____	_____	_____
0490	ATTD, 303	303SX20-0006 BORROW EXCAVATION BORROW MATERIAL - MIN CBR 10	127,469.000 CY	_____	_____	_____	_____
0500	ATTD	303SX20-0008 GEOTEXTILE HIGH STRENGTH GEOTEXTILE FABRIC	13,559.000 SY	_____	_____	_____	_____
0510	ATTD	303SX20-0020 ROCKFILL	5,499.000 TON	_____	_____	_____	_____
0520	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	10,987.000 SY	_____	_____	_____	_____
0530	305	305SD20-0011 AGGR. MATL. NO. 25 OR 26	479.000 TON	_____	_____	_____	_____
0540	ATTD	305SX20-0006 SELECT MATERIAL TYPE OGB AGGREGATE	849.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0550	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	5,602.000 TON	_____	_____	_____	_____
0560	ATTD	308SX20-0005 COARSE AGGREGATE NO.8	835.000 TON	_____	_____	_____	_____
0570	ATTD 302	309SX20-0001 AGGR. MATERIAL AGGREGATE. MATERIAL SELF-COMPACTING FILL	268.000 TON	_____	_____	_____	_____
0580	315	315SD20-0007 ASPHALT CONCRETE TY. SM-9.5A CONST	882.000 TON	_____	_____	_____	_____
0590	315	315SD20-0010 ASPHALT CONCRETE TY. BM-25.0A CONST	1,526.000 TON	_____	_____	_____	_____
0600	315	315SD20-0018 ASPH.CONC.CURB BACKUP MATL. CONST	4.000 TON	_____	_____	_____	_____
0610	315	315SX20-0011 SAW-CUT ASPH CONC SAWCUT	276.000 LF	_____	_____	_____	_____
0620	401, ATTD	401SX20-0004 BRIDGE SUBSTRUCTURE EXCAVATION W/ PROBING	928.000 CY	_____	_____	_____	_____
0630	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	1,566.000 TON	_____	_____	_____	_____
0640	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	86.000 SY	_____	_____	_____	_____
0650	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	158.000 LF	_____	_____	_____	_____
0660	ATTD	401SX20-0001 BRIDGE CONSTR. (TEMPORARY SHORING)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	403	403SD20-0006 STEEL PILES 12"	6,566.000 LF	_____	_____	_____	_____
0680	403	403SD20-0034 PILE POINT FOR 12" STEEL PILE	132.000 EA	_____	_____	_____	_____
0690	ATTD	403SX20-0001 DYNAMIC PILE TEST END BEARING PILES	4.000 EA	_____	_____	_____	_____
0700	403	403SX20-0016 PREBORING PILE STEEL HP 12X53	180.000 LF	_____	_____	_____	_____
0710	404	404SD20-0007 CONC. CL. A4 MOD. LTWT LOW SHRINK., SPR. STRUCT. CONST.	288.170 CY	_____	_____	_____	_____
0720	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	978.000 SY	_____	_____	_____	_____
0730	404	404SD20-0010 COVER DEPTH SURVEY CONST.	978.000 SY	_____	_____	_____	_____
0740	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	658.100 CY	_____	_____	_____	_____
0750	404	404SX20-0004 CONCRETE CLASS A3 (UNREINFORCED)	20.000 CY	_____	_____	_____	_____
0760	406	406SD20-0003 CR REINF. STEEL CL. I SPR. STRUCT. CONST.	63,320.000 LB	_____	_____	_____	_____
0770	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	77,870.000 LB	_____	_____	_____	_____
0780	407	407SD20-0007 STR.ST.PLATE GIRDER ASTM A709 GR.50W	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0790	410	410SD20-0011 RAILING CPSR 2 RAIL CONST.	449.000 LF	_____	_____	_____	_____
0800	413	413SX20-0002 DISM.& REM. EX. STR. ENTRANCE SIGN STRUCTURES AND LIGHTING FOR D701 AND D702	LUMP SUM	LUMP SUM	_____	_____	_____
0810	413	413SX20-0002 DISM.& REM. EX. STR. ENTRANCE SIGN STRUCTURES WITH D703	LUMP SUM	LUMP SUM	_____	_____	_____
0820	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	112.000 TON	_____	_____	_____	_____
0830	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	68.000 TON	_____	_____	_____	_____
0840	ATTD	414SX20-0003 GROUTED RIPRAP CLASS A1 GROUTED RIP RAP	1,739.000 SY	_____	_____	_____	_____
0850	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (B632)	1.000 DAY	_____	_____	_____	_____
0860	ATTD	432SD20-0001 ELASTIC INCLUSION	15.000 CY	_____	_____	_____	_____
0870	501	501SD20-0002 UNDERDRAIN UD-2	334.000 LF	_____	_____	_____	_____
0880	501	501SD20-0004 UNDERDRAIN UD-4	1,439.000 LF	_____	_____	_____	_____
0890	501	501SD20-0007 CROSSDRAIN CD-2	103.000 LF	_____	_____	_____	_____
0900	501	501SD20-0009 OUTLET PIPE	111.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0910	502	502SD20-0003 PAVED DITCH PG-2A	175.000 SY	_____	_____	_____	_____
0920	502	502SD20-0014 CURB, STD. CG-3	815.000 LF	_____	_____	_____	_____
0930	502	502SD20-0015 CURB, RADIAL CG-3	232.000 LF	_____	_____	_____	_____
0940	502	502SD20-0020 CURB, ASPHALT MC-3B	90.000 LF	_____	_____	_____	_____
0950	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	105.000 CY	_____	_____	_____	_____
0960	504	504SD20-0005 GEOTEXTILE DRAINAGE FABRIC	2,391.000 SY	_____	_____	_____	_____
0970	505	505SD20-0011 GUARDRAIL GR-MGS1	1,913.000 LF	_____	_____	_____	_____
0980	505	505SD20-0014 RADIAL GUARDRAIL GR-MGS1	188.000 LF	_____	_____	_____	_____
0990	505	505SD20-0017 GUARDRAIL TERMINAL GR-MGS2	6.000 EA	_____	_____	_____	_____
1000	505	505SD20-0055 FIXED OBJECT ATTACH. GR-FOA-5	4.000 EA	_____	_____	_____	_____
1010	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	509.000 LF	_____	_____	_____	_____
1020	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	221.000 LF	_____	_____	_____	_____
1030	508	508SD20-0001 OBSCURING ROADWAY	36.900 UNIT	_____	_____	_____	_____



Schedule of Items

Proposal ID: C0000112945C01

Oversight/State Project No.: 0658-093-R13, C501

Order No.: K02

Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1040	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	7,250.000 SY	_____	_____	_____	_____
1050	509	509SD20-0001 FLOWABLE BACKFILL	101.000 CY	_____	_____	_____	_____
1060	ATTD	510SX20-0016 REMOVE EXIST. FENCE EXISTING FENCE	406.000 LF	_____	_____	_____	_____
1070	511	511SD20-0001 ALLAYING DUST	250.000 HR	_____	_____	_____	_____
1080	512	512SD20-0012 TYPE 3 BARRICADE 4'	24.000 EA	_____	_____	_____	_____
1090	512	512SD20-0013 TYPE 3 BARRICADE 8'	13.000 EA	_____	_____	_____	_____
1100	512	512SD20-0014 TEMPORARY SIGN	2,124.000 SF	_____	_____	_____	_____
1110	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	35,025.000 DAY	_____	_____	_____	_____
1120	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	750.000 HR	_____	_____	_____	_____
1130	512	512SD20-0027 FLAGGER SERVICE	2,070.000 HR	_____	_____	_____	_____
1140	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4"	14,448.000 LF	_____	_____	_____	_____
1150	512	512SD20-0065 TEMP. PVMT MRKG TY. D, CL. III, 24"	234.000 LF	_____	_____	_____	_____
1160	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	278.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1170	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM			
1180	514	514SD20-0001 FIELD OFFICE TY.I	21.000 MO				
1190	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	203.000 SY				
1200	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
1210	ATTD	520SX20-0014 UTILITIES TEMPORARY ELECTRIC SERVICE	LUMP SUM	LUMP SUM			
1220	ATTD 414	523SP20-0002 STORM WATER MANAGEMENT IMPERMEABLE LINER	1,682.000 SY				
1230	ATTD	523SP20-0003 STORM WATER MGT. BIORETENTION SOIL MEDIA	750.000 CY				
1240	602	602SX20-0005 TOPSOIL 3" TOPSOIL TYPE B	5.520 ACRE				
1250	603	603SD20-0002 TEMPORARY SEED	763.000 LB				
1260	603	603SD20-0003 REGULAR SEED	2,208.000 LB				
1270	603	603SD20-0004 OVERSEEDING	1,766.000 LB				
1280	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	17,606.000 SY				
1290	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	52,417.000 SY				

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1300	603	603SD20-0010 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	303.000 SY	_____	_____	_____	_____
1310	603	603SD20-0011 SEDIMENT RETENTION ROLL 18" MIN	7,196.000 LF	_____	_____	_____	_____
1320	603	603SD20-0014 FERTILIZER NITROGEN - N	612.000 LB	_____	_____	_____	_____
1330	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	441.000 LB	_____	_____	_____	_____
1340	603	603SD20-0016 FERTILIZER POTASSIUM - K	441.000 LB	_____	_____	_____	_____
1350	603	603SD20-0017 LIME	35.390 TON	_____	_____	_____	_____
1360	ATTD	605SX20-0017 SEED MIXTURE COVER CROP/ SEED ADDITIVES	5.000 LB	_____	_____	_____	_____
1370	ATTD	605SX20-0017 SEED MIXTURE RAIN GARDEN SEED MIX	10.000 LB	_____	_____	_____	_____
1380	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	15,451.000 SY	_____	_____	_____	_____
1390	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	70.000 SY	_____	_____	_____	_____
1400	606	606SD20-0003 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	1,329.000 SY	_____	_____	_____	_____
1410	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	294.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000112945C01      Oversight/State Project No.: 0658-093-R13, C501  
 Order No.: K02      Federal Project No.: STP-093-8(055)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1420	608	608SD20-0001 MOWING	200.000 HR	_____	_____	_____	_____
1430	610	610SD20-0001 GABIONS	92.000 CY	_____	_____	_____	_____
1440	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	5.000 EA	_____	_____	_____	_____
1450	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	1.000 EA	_____	_____	_____	_____
1460	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	86.000 LF	_____	_____	_____	_____
1470	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	36.000 LF	_____	_____	_____	_____
1480	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	11.000 EA	_____	_____	_____	_____
1490	701	701SD20-0001 SIGN PANEL	70.000 SF	_____	_____	_____	_____
1500	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	7,803.000 LF	_____	_____	_____	_____
1510	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	70.000 LF	_____	_____	_____	_____
1520	704	704SD20-0030 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 4"	880.000 LF	_____	_____	_____	_____
1530	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	4.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____

**Total Bid:** \_\_\_\_\_.