

Schedule of Items

Proposal ID: C0000016314C01 Oversight/State Project No.: 0641-099-200, C501
 Order No.: K37 Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0002 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONSTRUCTION RECORD DOCUMENTS	LUMP SUM	LUMP SUM			
0020	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0030	302, 406	302SD20-0005 REINF. STEEL	1,002.000 LB				
0040	302	302SD20-0023 15" PIPE	167.000 LF				
0050	302	302SD20-0027 15" STORM SEWER PIPE	1,095.000 LF				
0060	302	302SD20-0032 18" STORM SEWER PIPE	453.000 LF				
0070	302	302SD20-0041 24" STORM SEWER PIPE	164.000 LF				
0080	302	302SD20-0132 23" X 14" ELLIPTICAL PIPE	124.000 LF				
0090	302	302SD20-0134 30" X 19" ELLIPTICAL PIPE	116.000 LF				
0100	302	302SD20-0198 15" END SECTION ES-1 OR 2	6.000 EA				
0110	302	302SD20-0204 24" END SECTION ES-1 OR 2	1.000 EA				
0120	302	302SD20-0237 DROP INLET DI-1	5.000 EA				
0130	302	302SD20-0239 DROP INLET DI-2A	5.000 EA				
0140	302	302SD20-0241 DROP INLET DI-2B,L=4'	1.000 EA				

Schedule of Items

Proposal ID: C0000016314C01 Oversight/State Project No.: 0641-099-200, C501
 Order No.: K37 Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0242 DROP INLET DI-2B,L=6'	3.000 EA	_____	_____	_____	_____
0160	302	302SD20-0243 DROP INLET DI-2B,L=8'	1.000 EA	_____	_____	_____	_____
0170	302	302SD20-0259 DROP INLET DI-2C,L=6'	3.000 EA	_____	_____	_____	_____
0180	302	302SD20-0262 DROP INLET DI-2C,L=12'	1.000 EA	_____	_____	_____	_____
0190	302	302SD20-0309 DROP INLET DI-3A	4.000 EA	_____	_____	_____	_____
0200	302	302SD20-0311 DROP INLET DI-3B,L=4'	2.000 EA	_____	_____	_____	_____
0210	302	302SD20-0312 DROP INLET DI-3B,L=6'	1.000 EA	_____	_____	_____	_____
0220	302	302SD20-0446 DROP INLET DI-5	4.000 EA	_____	_____	_____	_____
0230	303	303SD20-0001 REGULAR EXCAVATION	3,835.000 CY	_____	_____	_____	_____
0240	303	303SD20-0010 EMBANKMENT	294.000 CY	_____	_____	_____	_____
0250	303	303SD20-0019 EROSION CONTROL MULCH	1,000.000 SY	_____	_____	_____	_____
0260	303	303SD20-0022 CHECK DAM ROCK TY. I	1.000 EA	_____	_____	_____	_____
0270	303	303SD20-0023 CHECK DAM ROCK TY. II	59.000 EA	_____	_____	_____	_____
0280	303	303SD20-0029 SILTATION CONTROL EXCAVATION	1,937.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000016314C01

Oversight/State Project No.: 0641-099-200, C501

Order No.: K37

Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	303	303SD20-0030 INLET PROTECTION TYPE A	10.000 EA	_____	_____	_____	_____
0300	303	303SD20-0031 INLET PROTECTION TYPE B	32.000 EA	_____	_____	_____	_____
0310	303	303SD20-0034 TEMP. SILT FENCE TYPE A	6,099.000 LF	_____	_____	_____	_____
0320	303	303SD20-0035 TEMP. SEDIMENT BASIN EXCAVATION	1,026.000 CY	_____	_____	_____	_____
0330	303	303SD20-0036 STORM WATER MAN. BASIN EXCAV.	269.000 CY	_____	_____	_____	_____
0340	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	8,260.000 SY	_____	_____	_____	_____
0350	305	305SX20-0004 SELECT MATERIAL TYPE II CBR-15	1,669.000 CY	_____	_____	_____	_____
0360	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	4,617.000 TON	_____	_____	_____	_____
0370	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	83.000 TON	_____	_____	_____	_____
0380	315	315SD20-0007 ASPHALT CONCRETE TY. SM- 9.5A CONST	1,298.000 TON	_____	_____	_____	_____
0390	315	315SD20-0010 ASPHALT CONCRETE TY. BM- 25.0A CONST	2,021.000 TON	_____	_____	_____	_____
0400	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	302.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000016314C01 Oversight/State Project No.: 0641-099-200, C501
 Order No.: K37 Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	316	316SD20-0030 CONCRETE ENTRANCE PAVE. 7"	10.000 SY	_____	_____	_____	_____
0420	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	6.500 TON	_____	_____	_____	_____
0430	414	414SD20-0012 DRY RIPRAP CL.I 26"	69.000 TON	_____	_____	_____	_____
0440	502	502SD20-0003 PAVED DITCH PG-2A	125.000 SY	_____	_____	_____	_____
0450	502	502SD20-0024 COMB. CURB & GUTTER, STD. CG-7	2,333.000 LF	_____	_____	_____	_____
0460	502	502SD20-0025 COMB. CURB & GUTTER, RAD. CG-7	593.000 LF	_____	_____	_____	_____
0470	502	502SD20-0029 ENTRANCE GUTTER CG-9D	295.000 SY	_____	_____	_____	_____
0480	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	9.007 CY	_____	_____	_____	_____
0490	507	507SD20-0005 FENCE FE-CL	571.000 LF	_____	_____	_____	_____
0500	507	507SD20-0009 CORNER BRACE UNIT FE-CL	9.000 EA	_____	_____	_____	_____
0510	507	507SD20-0014 GATE FE-CL 14'	1.000 EA	_____	_____	_____	_____
0520	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	248.000 LF	_____	_____	_____	_____
0530	508	508SD20-0001 OBSCURING ROADWAY	6.000 UNIT	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000016314C01 Oversight/State Project No.: 0641-099-200, C501
 Order No.: K37 Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	508	508SD20-0002 DEMO. OF PVMT. COMBINATION	7,668.000 SY	_____	_____	_____	_____
0550	509	509SD20-0001 FLOWABLE BACKFILL	29.000 CY	_____	_____	_____	_____
0560	510	510SD20-0050 ADJUST EXIST FRAME & COVER	1.000 EA	_____	_____	_____	_____
0570	ATTD	510SX20-0039 REMOVE EXIST. RAILS & TIES	52.000 LF	_____	_____	_____	_____
0580	511	511SD20-0001 ALLAYING DUST	400.000 HR	_____	_____	_____	_____
0590	512	512SD20-0013 TYPE 3 BARRICADE 8'	32.000 EA	_____	_____	_____	_____
0600	512	512SD20-0014 TEMPORARY SIGN	985.000 SF	_____	_____	_____	_____
0610	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	50.000 HR	_____	_____	_____	_____
0620	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	4,984.000 DAY	_____	_____	_____	_____
0630	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	6,048.000 HR	_____	_____	_____	_____
0640	512	512SD20-0027 FLAGGER SERVICE	100.000 HR	_____	_____	_____	_____
0650	512	512SD20-0029 WARNING LIGHT TY. B	5,256.000 DAY	_____	_____	_____	_____
0660	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	384.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000016314C01 Oversight/State Project No.: 0641-099-200, C501
 Order No.: K37 Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	1,000.000 LF	_____	_____	_____	_____
0680	512	512SX20-0005 TEMP. PVMT MRKG TY D CL. II, 4"	1,000.000 LF	_____	_____	_____	_____
0690	512	512SX20-0005 TEMP. PVMT MRKG TY. D, CL. II, 24"	100.000 LF	_____	_____	_____	_____
0700	512	512SX20-0006 TEMP. PVMT MRKG TY. D, CL. II, ELONG. ARROW	4.000 EA	_____	_____	_____	_____
0710	ATTD	512SX20-0040 POLICE PATROL LOCAL OFFICERS	162.000 HR	_____	_____	_____	_____
0720	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0730	ATTD, 514	514SX20-0001 FIELD OFFICE TYPE III MODIFIED	20.000 MO	_____	_____	_____	_____
0740	515	515SD20-0014 FLEXIBLE PAVEMENT PLANING ABOVE 2"-4"	629.000 SY	_____	_____	_____	_____
0750	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0760	520	520SD20-0002 3/4" WATER SERVICE LINE	334.000 LF	_____	_____	_____	_____
0770	520	520SD20-0014 6" DI WATER MAIN	17.000 LF	_____	_____	_____	_____
0780	520	520SD20-0024 16" DI WATER MAIN	344.000 LF	_____	_____	_____	_____
0790	520	520SD20-0041 16" BEND	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000016314C01 Oversight/State Project No.: 0641-099-200, C501
 Order No.: K37 Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	520	520SD20-0049 16" BRANCH	2.000 EA	_____	_____	_____	_____
0810	520	520SD20-0057 16" PLUG OR CAP	2.000 EA	_____	_____	_____	_____
0820	520	520SD20-0089 6" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
0830	520	520SD20-0098 16" BUTTERFLY VALVE & BOX	1.000 EA	_____	_____	_____	_____
0840	520	520SD20-0162 FIRE HYDRANT	1.000 EA	_____	_____	_____	_____
0850	520	520SD20-0165 2" AIR RELEASE VALVE & BOX	1.000 EA	_____	_____	_____	_____
0860	520	520SD20-0167 5/8" WATER METER BOX & YOKE	1.000 EA	_____	_____	_____	_____
0870	520	520SD20-0179 4" SANITARY SERVICE LATERAL CONNECTION	260.000 LF	_____	_____	_____	_____
0880	520	520SD20-0185 8" SANITARY SEWER PIPE	897.000 LF	_____	_____	_____	_____
0890	520	520SD20-0272 SANITARY SEWER MANHOLE	35.000 LF	_____	_____	_____	_____
0900	520	520SD20-0273 MANHOLE FRAME & COVER WF & C-1	7.000 EA	_____	_____	_____	_____
0910	520	520SD20-0275 RECONSTRUCT EXISTING SANITARY MANHOLE	13.000 LF	_____	_____	_____	_____
0920	520	520SX20-0005 4" SEWER CLEANOUT	10.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000016314C01 Oversight/State Project No.: 0641-099-200, C501
 Order No.: K37 Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	ATTD	520SX20-0007 SEWER UTILITY CIPP REHABILITATION FOR 8" SANITARY SEWER	400.000 LF	_____	_____	_____	_____
0940	ATTD	520SX20-0086 WATER UTILITY 16" LONG SOLID SLEEVE	5.000 EA	_____	_____	_____	_____
0950	ATTD	523SP20-0002 STORM WATER MANAGEMENT LOW PERMEABILITY LINER	232.000 SY	_____	_____	_____	_____
0960	602	602SD20-0003 TOPSOIL CLASS B 2"	0.700 ACRE	_____	_____	_____	_____
0970	603	603SD20-0002 TEMPORARY SEED	60.000 LB	_____	_____	_____	_____
0980	603	603SD20-0003 REGULAR SEED	203.000 LB	_____	_____	_____	_____
0990	603	603SD20-0004 OVERSEEDING	162.000 LB	_____	_____	_____	_____
1000	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	7,865.000 SY	_____	_____	_____	_____
1010	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	3,207.000 SY	_____	_____	_____	_____
1020	603	603SD20-0014 FERTILIZER NITROGEN - N	115.000 LB	_____	_____	_____	_____
1030	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	149.000 LB	_____	_____	_____	_____
1040	603	603SD20-0016 FERTILIZER POTASSIUM - K	75.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000016314C01 Oversight/State Project No.: 0641-099-200, C501
 Order No.: K37 Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1050	603	603SD20-0017 LIME	5.330 TON	_____	_____	_____	_____
1060	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	16.000 EA	_____	_____	_____	_____
1070	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	92.000 LF	_____	_____	_____	_____
1080	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	60.000 LF	_____	_____	_____	_____
1090	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	48.000 LF	_____	_____	_____	_____
1100	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	4.000 EA	_____	_____	_____	_____
1110	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	5.000 EA	_____	_____	_____	_____
1120	700	700SD20-0041 CONC. FOUND. STP-1, TY. D	9.000 EA	_____	_____	_____	_____
1130	700	700SX20-0029 RELOCATE EXISTING SIGN PANEL TY. SP-1	1.000 EA	_____	_____	_____	_____
1140	701	701SD20-0001 SIGN PANEL	187.000 SF	_____	_____	_____	_____
1150	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	8,700.000 LF	_____	_____	_____	_____
1160	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	280.000 LF	_____	_____	_____	_____
1170	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	450.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000016314C01 Oversight/State Project No.: 0641-099-200, C501
 Order No.: K37 Federal Project No.: STP-5B03(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1180	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	8.000 EA	_____	_____	_____	_____
1190	704	704SD20-0101 SYMB MRKG HELMETED BICYCLIST TY B CL I	10.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____