

Schedule of Items

Proposal ID: C0000122470N01B Oversight/State Project No.: 9999-964-668,N501

Order No.: J62

Federal Project No.: STP-TS04(300)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0002 CLEARING AND GRUBBING	5.000 ACRE	_____	_____	_____	_____
0020	303	303SD20-0034 TEMP. SILT FENCE TYPE A	1,000.000 LF	_____	_____	_____	_____
0030	305	305SD20-0012 AGGR.BASE MAT.TY. I NO.21A OR 21B	20.000 TON	_____	_____	_____	_____
0040	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	20.000 TON	_____	_____	_____	_____
0050	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	10.000 CY	_____	_____	_____	_____
0060	504	504SD20-0014 HANDRAIL HR-1 TYPE II	100.000 LF	_____	_____	_____	_____
0070	505	505SD20-0011 GUARDRAIL GR-MGS1	275.000 LF	_____	_____	_____	_____
0080	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	250.000 LF	_____	_____	_____	_____
0090	505	505SD20-0017 GUARDRAIL TERMINAL GR-MGS2	2.000 EA	_____	_____	_____	_____
0100	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	2.000 EA	_____	_____	_____	_____
0110	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	2.000 EA	_____	_____	_____	_____
0120	505	505SD20-0039 GUARDRAIL TER.SITE PREPARATION	2.000 EA	_____	_____	_____	_____
0130	505	505SD20-0045 FIXED OBJECT ATTACH. GR-FOA-1 TY. I	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122470N01B Oversight/State Project No.: 9999-964-668,N501

Order No.: J62

Federal Project No.: STP-TS04(300)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	250.000 LF	_____	_____	_____	_____
0150	ATTD	510SX20-0035 RECONSTRUCT EXIST. UTILITY TEST HOLE (NON PAVED AREA)	20.000 EA	_____	_____	_____	_____
0160	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	800.000 HR	_____	_____	_____	_____
0170	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	2,500.000 DAY	_____	_____	_____	_____
0180	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	100.000 HR	_____	_____	_____	_____
0190	512	512SD20-0026 ELECTRONIC ARROW BOARD	800.000 HR	_____	_____	_____	_____
0200	ATTD	513SX20-0001 MOBILIZATION ASHLAND OVER \$1,000,000	1.000 EA	_____	_____	_____	_____
0210	ATTD	513SX20-0001 MOBILIZATION FRANKLIN OVER \$1,000,000	1.000 EA	_____	_____	_____	_____
0220	ATTD	513SX20-0001 MOBILIZATION FREDERICKSBURG OVER \$1,000,000	1.000 EA	_____	_____	_____	_____
0230	ATTD	513SX20-0001 MOBILIZATION PETERSBURG OVER \$1,000,000	1.000 EA	_____	_____	_____	_____
0240	601	601SD20-0001 SEL TREE REMOVAL TRIM AND CLEAN	0.500 ACRE	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122470N01B Oversight/State Project No.: 9999-964-668,N501

Order No.: J62

Federal Project No.: STP-TS04(300)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	550.000 SY	_____	_____	_____	_____
0260	606	606SD20-0003 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	275.000 SY	_____	_____	_____	_____
0270	700	700SD20-0068 CONC. FOUND. PF-8	100.000 CY	_____	_____	_____	_____
0280	700	700SD20-0134 ELECTRICAL SERVICE SE-4, TY. A	5.000 EA	_____	_____	_____	_____
0290	700	700SD20-0141 2 CONDUCTOR CABLE	16,100.000 LF	_____	_____	_____	_____
0300	700	700SD20-0142 4 CONDUCTOR CABLE	8,510.000 LF	_____	_____	_____	_____
0310	700	700SD20-0143 6 CONDUCTOR CABLE	1,975.000 LF	_____	_____	_____	_____
0320	700	700SD20-0144 8 CONDUCTOR CABLE	1,150.000 LF	_____	_____	_____	_____
0330	700	700SD20-0172 ELECTRICAL SERVICE SE-9, TY. A	1.000 EA	_____	_____	_____	_____
0340	700	700SD20-0174 ELECTRICAL SERVICE WORK PAD	16.000 EA	_____	_____	_____	_____
0350	700	700SD20-0178 JUNCTION BOX JB-S2	45.000 EA	_____	_____	_____	_____
0360	700	700SD20-0179 JUNCTION BOX JB-S3	27.000 EA	_____	_____	_____	_____
0370	700	700SD20-0180 JUNCTION BOX JB-S4	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122470N01B Oversight/State Project No.: 9999-964-668,N501

Order No.: J62

Federal Project No.: STP-TS04(300)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	700	700SD20-0181 ELECT. SER. GRD. ELECTRODE 10'	55.000 EA	_____	_____	_____	_____
0390	700	700SD20-0191 BORED CONDUIT 2"	3,045.000 LF	_____	_____	_____	_____
0400	700	700SD20-0192 BORED CONDUIT 3"	150.000 LF	_____	_____	_____	_____
0410	700	700SD20-0194 CONDUIT PVC 2"	18,280.000 LF	_____	_____	_____	_____
0420	700	700SD20-0195 CONDUIT PVC 3"	150.000 LF	_____	_____	_____	_____
0430	700	700SD20-0197 TRENCH EXCAVATION ECI-1	11,360.000 LF	_____	_____	_____	_____
0440	700	700SD20-0199 TEST BORE	14.000 EA	_____	_____	_____	_____
0450	ATTD	700SX20-0007 CONDUCTOR CABLE CAT 6 WATER BLOCKING, SHIELDED, DIRECT BURIED CABLE	800.000 LF	_____	_____	_____	_____
0460	700	700SX20-0010 TRAFFIC SIGNALIZATION ELECTRICAL SERVICE SE-5 (RDO)	5.000 EA	_____	_____	_____	_____
0470	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION SUPPLEMENTAL ELECTRICAL SERVICE DISCONNECT (SE-5)	9.000 EA	_____	_____	_____	_____
0480	801	801SD20-0002 ITS CONTROLLER CABINET POLE MOUNTED	14.000 EA	_____	_____	_____	_____
0490	ATTD	801SX20-0001 COMMUNICATION EQUIP. BURIED CABLE MARKER POST	25.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122470N01B Oversight/State Project No.: 9999-964-668,N501
Order No.: J62 Federal Project No.: STP-TS04(300)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0500	803	801SX20-0001 COMMUNICATION EQUIP. CCTV CAMERA (DIGITAL)	14.000 EA	_____	_____	_____	_____
0510	ATTD	801SX20-0001 COMMUNICATION EQUIP. FIELD ROUTER	14.000 EA	_____	_____	_____	_____
0520	809 ATTD	801SX20-0001 COMMUNICATION EQUIP. MANAGED FIELD ETHERNET SWITCH (GBPS)	14.000 EA	_____	_____	_____	_____
0530	ATTD	801SX20-0001 COMMUNICATION EQUIP. PRE-TERMINATED FIBER PATCH PANEL (LARGE)	14.000 EA	_____	_____	_____	_____
0540	ATTD	801SX20-0001 COMMUNICATION EQUIP. SOLAR POWER ASSEMBLY (CCTV)	1.000 EA	_____	_____	_____	_____
0550	ATTD	801SX20-0001 COMMUNICATION EQUIP. SOLAR POWER POLE	1.000 EA	_____	_____	_____	_____
0560	ATTD	801SX20-0001 COMMUNICATION EQUIP. STEP-DOWN TRANSFORMER (10KVA)	1.000 EA	_____	_____	_____	_____
0570	ATTD	801SX20-0001 COMMUNICATION EQUIP. STEP-DOWN TRANSFORMER (3KVA)	6.000 EA	_____	_____	_____	_____
0580	ATTD	801SX20-0001 COMMUNICATION EQUIP. STEP-UP TRANSFORMER (10KVA)	1.000 EA	_____	_____	_____	_____
0590	ATTD	801SX20-0001 COMMUNICATION EQUIP. STEP-UP TRANSFORMER (25KVA)	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122470N01B Oversight/State Project No.: 9999-964-668,N501

Order No.: J62

Federal Project No.: STP-TS04(300)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0600	808	801SX20-0001 COMMUNICATION EQUIP. UNDERGROUND SPLICE ENCLOSURE	2.000 EA	_____	_____	_____	_____
0610	802	801SX20-0001 COMMUNICATION EQUIP. UNINTERRUPTIBLE POWER SUPPLY ITS-CC	14.000 EA	_____	_____	_____	_____
0620	ATTD	801SX20-0003 COMMUNICATION EQUIP. PRE-TERMINATED FIBER PATCH PANEL CABLE STUB	11,320.000 LF	_____	_____	_____	_____
0630	803	803SD20-0011 CCTV CAMERA POLE W/LOWERING DEVICE 80'	14.000 EA	_____	_____	_____	_____
0640	810	810SD20-0008 SFP MODULE 1 Gbps, LC, LONG HAUL	21.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	