

Schedule of Items

Proposal ID: C0000122797N01 Oversight/State Project No.: HSIP-062-856, N501
 Order No.: K42 Federal Project No.: HSIP-062-3 (154)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	303SX20-0012 UTILITY TEST PIT UNPAVED	28.000 EA	_____	_____	_____	_____
0020	305	305SD20-0001 BORROW EXCAVATION	112.000 CY	_____	_____	_____	_____
0030	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	11,727.000 TON	_____	_____	_____	_____
0040	ATTD	305SP20-0005 MACHINING SHOULDERS	28,493.000 LF	_____	_____	_____	_____
0050	315	315SD20-0002 ASPHALT CONCRETE TY. SM- 12.5D CONST	2,538.000 TON	_____	_____	_____	_____
0060	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	59,014.000 LF	_____	_____	_____	_____
0070	315	315SD20-0016 LIQ.ASPH. RUMBLE STRIP COATING CONST	6,010.000 SY	_____	_____	_____	_____
0080	315	315SD20-0049 ASPH. CONC. TY. BM-25.0A T MAINT	10,413.000 TON	_____	_____	_____	_____
0090	505	505SD20-0009 REMOVE EX. GUARDRAIL TERMINAL	30.000 EA	_____	_____	_____	_____
0100	505	505SD20-0011 GUARDRAIL GR-MGS1	23,188.000 LF	_____	_____	_____	_____
0110	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	3,575.000 LF	_____	_____	_____	_____
0120	505	505SD20-0014 RADIAL GUARDRAIL GR- MGS1	375.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122797N01

Oversight/State Project No.: HSIP-062-856, N501

Order No.: K42

Federal Project No.: HSIP-062-3 (154)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	505	505SD20-0017 GUARDRAIL TERMINAL GR-MGS2	27.000 EA	_____	_____	_____	_____
0140	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	33.000 EA	_____	_____	_____	_____
0150	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	8.000 EA	_____	_____	_____	_____
0160	505	505SD20-0027 GUARDRAIL TERMINAL GR-6 NCHRP 350	12.500 LF	_____	_____	_____	_____
0170	505	505SD20-0030 GUARDRAIL GR-2	112.500 LF	_____	_____	_____	_____
0180	505	505SD20-0034 RAD. GUARDRAIL GR-2	262.500 LF	_____	_____	_____	_____
0190	505	505SD20-0040 GUARDRAIL GR-10	25.000 LF	_____	_____	_____	_____
0200	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	25,198.000 LF	_____	_____	_____	_____
0210	ATTD	505SX20-0001 HAND DIG GUARDRAIL POST HOLE NS	1,398.000 EA	_____	_____	_____	_____
0220	505	505SX20-0003 SALV. EX. GR TERMINAL NS	4.000 EA	_____	_____	_____	_____
0230	505	505SX20-0007 INSTALL SALV GR TERMINAL NS	4.000 EA	_____	_____	_____	_____
0240	505	505SX20-0044 SP. DES. GR.BR.ATTACH BR-GR BRGR-30C	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122797N01

Oversight/State Project No.: HSIP-062-856, N501

Order No.: K42

Federal Project No.: HSIP-062-3 (154)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	505	505SX20-0058 GUARDRAIL GR-MGS2-END TERMINAL SITE PREPARATION, 4' MAJOR	1.000 EA	_____	_____	_____	_____
0260	505	505SX20-0058 GUARDRAIL GR-MGS2-END TERMINAL SITE PREPARATION, 4' MODERATE	27.000 EA	_____	_____	_____	_____
0270	512	512SD20-0014 TEMPORARY SIGN	400.000 SF	_____	_____	_____	_____
0280	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	2,898.000 HR	_____	_____	_____	_____
0290	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	13,140.000 DAY	_____	_____	_____	_____
0300	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	336.000 HR	_____	_____	_____	_____
0310	512	512SD20-0026 ELECTRONIC ARROW BOARD	2,898.000 HR	_____	_____	_____	_____
0320	512	512SD20-0027 FLAGGER SERVICE	80.000 HR	_____	_____	_____	_____
0330	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	100.000 EA	_____	_____	_____	_____
0340	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	59,014.000 LF	_____	_____	_____	_____
0350	512	512SD20-0054 TEMP. PVMT MRKG TY. E, 6"	1,245.000 LF	_____	_____	_____	_____
0360	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	33,980.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122797N01 Oversight/State Project No.: HSIP-062-856, N501
 Order No.: K42 Federal Project No.: HSIP-062-3 (154)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0370	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	1,980.000 LF	_____	_____	_____	_____
0380	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0390	606	606SD20-0003 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	100.000 SY	_____	_____	_____	_____
0400	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	27.000 EA	_____	_____	_____	_____
0410	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	2.000 EA	_____	_____	_____	_____
0420	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	42.000 EA	_____	_____	_____	_____
0430	700	700SD20-0013 RELOCATE EX. 2 POST GRND MOUNT SGN PANEL	6.000 EA	_____	_____	_____	_____
0440	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	171.000 LF	_____	_____	_____	_____
0450	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	18.000 LF	_____	_____	_____	_____
0460	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	63.000 LF	_____	_____	_____	_____
0470	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	66.000 LF	_____	_____	_____	_____
0480	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	28.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122797N01

Oversight/State Project No.: HSIP-062-856, N501

Order No.: K42

Federal Project No.: HSIP-062-3 (154)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0490	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	3.000 EA	_____	_____	_____	_____
0500	700	700SX20-0021 TRAFFIC SIGN RETROREFLECTIVE SIGN POST (YELLOW)	2.000 EA	_____	_____	_____	_____
0510	701	701SD20-0001 SIGN PANEL	3.000 SF	_____	_____	_____	_____
0520	702	702SD20-0003 ROAD EDGE DEL. ED-2	4.000 EA	_____	_____	_____	_____
0530	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	59,014.000 LF	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____