

Schedule of Items

Proposal ID: C0000110000B81

Oversight/State Project No.: 0641-002-951, B681

Order No.: K33

Federal Project No.: BR0S-5104(325)

Contractor: \_\_\_\_\_

SECTION: 100

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	303	303SD20-0028 DEWATERING BASIN EC-8	2.000 EA				
0030	303	303SD20-0029 SILTATION CONTROL EXCAVATION	41.000 CY				
0040	303	303SD20-0034 TEMP. SILT FENCE TYPE A	242.000 LF				
0050	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	65.000 TON				
0060	315	315SD20-0007 ASPHALT CONCRETE TY. SM-9.5A CONST	32.000 TON				
0070	315	315SX20-0011 SAW-CUT ASPH CONC (FULL DEPTH)	31.000 LF				
0080	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	400.000 CY				
0090	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	520.000 TON				
0100	401	401SD20-0007 COFFERDAM	2.000 EA				
0110	403	403SD20-0006 STEEL PILES 12"	470.000 LF				
0120	403	403SX20-0016 PREBORING PILE (12" STEEL PILE)	446.000 LF				
0130	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	86.300 CY				

Schedule of Items

Proposal ID: C0000110000B81      Oversight/State Project No.: 0641-002-951, B681  
 Order No.: K33      Federal Project No.: BR0S-5104(325)

Contractor: \_\_\_\_\_

SECTION: 100      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	4,770.000 LB	_____	_____	_____	_____
0150	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	4,330.000 LB	_____	_____	_____	_____
0160	407	407SD20-0011 STR.STEEL ROLLED BEAM ASTM A709 GRADE50	LUMP SUM	LUMP SUM	_____	_____	_____
0170	410	410SD20-0004 RAILING TEXAS T-6 CONST.	95.000 LF	_____	_____	_____	_____
0180	413	413SX20-0002 DISM.& REM. EX. STR. (VIRGINIA STR. NO. 6042)	LUMP SUM	LUMP SUM	_____	_____	_____
0190	413	413SX20-0003 ENV.& WORKER PROTECT. (VIRGINIA STR. NO. 6042)	LUMP SUM	LUMP SUM	_____	_____	_____
0200	413	413SX20-0004 MATERIAL DISPOSAL (VIRGINIA STR. NO. 6042)	LUMP SUM	LUMP SUM	_____	_____	_____
0210	414	414SD20-0012 DRY RIPRAP CL.I 26"	320.000 TON	_____	_____	_____	_____
0220	418	418SD20-0001 LUMBER TREATED, SPR. STRUCT. CONST.	4.700 MFBM	_____	_____	_____	_____
0230	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	1.000 EA	_____	_____	_____	_____
0240	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	117.000 LF	_____	_____	_____	_____
0250	505	505SX20-0058 GUARDRAIL (SS8-5B TERMINATION)	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110000B81

Oversight/State Project No.: 0641-002-951, B681

Order No.: K33

Federal Project No.: BR0S-5104(325)

Contractor: \_\_\_\_\_

SECTION: 100

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	110.000 SY	_____	_____	_____	_____
0270	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	45.000 LF	_____	_____	_____	_____
0280	512	512SD20-0013 TYPE 3 BARRICADE 8'	6.000 EA	_____	_____	_____	_____
0290	512	512SD20-0014 TEMPORARY SIGN	499.000 SF	_____	_____	_____	_____
0300	512	512SD20-0027 FLAGGER SERVICE	40.000 HR	_____	_____	_____	_____
0310	512	512SD20-0029 WARNING LIGHT TY. B	2,880.000 DAY	_____	_____	_____	_____
0320	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0330	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0340	603	603SD20-0003 REGULAR SEED	9.000 LB	_____	_____	_____	_____
0350	603	603SD20-0004 OVERSEEDING	7.000 LB	_____	_____	_____	_____
0360	603	603SD20-0005 LEGUME SEED	1.000 LB	_____	_____	_____	_____
0370	603	603SD20-0006 LEGUME OVERSEEDING	1.000 LB	_____	_____	_____	_____
0380	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	672.000 SY	_____	_____	_____	_____
0390	603	603SD20-0014 FERTILIZER NITROGEN - N	6.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110000B81

Oversight/State Project No.: 0641-002-951, B681

Order No.: K33

Federal Project No.: BR0S-5104(325)

Contractor: \_\_\_\_\_

SECTION: 100 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	8.000 LB	_____	_____	_____	_____
0410	603	603SD20-0016 FERTILIZER POTASSIUM - K	4.000 LB	_____	_____	_____	_____
0420	603	603SD20-0017 LIME	0.300 TON	_____	_____	_____	_____
0430	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	27.000 LF	_____	_____	_____	_____
0440	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	3.000 EA	_____	_____	_____	_____
0450	701	701SD20-0001 SIGN PANEL	9.000 SF	_____	_____	_____	_____
<b>Section: 100</b>				<b>Total:</b>		_____	
				<b>Total Bid:</b>		_____	