

Schedule of Items

Proposal ID: CM524PMM123987 Oversight/State Project No.: PM5M-047-F24, P401

Order No.: 525

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	303SD20-0030 INLET PROTECTION TYPE A	15.000 EA	_____	_____	_____	_____
0020	ATTD	305SP20-0003 AGR. BASE MAT. TY. I OR II NO. 21A OR 21B	1,268.000 TON	_____	_____	_____	_____
0030	307	307SD20-0001 HYDRAULIC CEMENT	670.000 TON	_____	_____	_____	_____
0040	310	310SD20-0001 TACK COAT	6,797.000 GAL	_____	_____	_____	_____
0050	315	315SD20-0021 ASPH. CONC. TY. SM-4.75A MAINT	1,743.760 TON	_____	_____	_____	_____
0060	315	315SP20-0050 ASPH. CONC. BMD P+VO SM- 12.5A	2,921.030 TON	_____	_____	_____	_____
0070	ATTD	315SX20-0013 FULL DEPTH RECLAMATION 8" COMPACTED	36,095.000 SY	_____	_____	_____	_____
0080	ATTD	510SX20-0038 REMOVE EXIST. AS NEEDED EXCAVATION OF FOULED BASE	11,615.000 SY	_____	_____	_____	_____
0090	ATTD	510SX20-0038 REMOVE EXIST. REMOVE APPROXIMATE 2.5"	32,638.000 SY	_____	_____	_____	_____
0100	ATTD	510SX20-0038 REMOVE EXIST. REMOVE APPROXIMATE 4.5"	3,450.000 SY	_____	_____	_____	_____
0110	512	512SD20-0027 FLAGGER SERVICE	900.000 HR	_____	_____	_____	_____
0120	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	600.000 LF	_____	_____	_____	_____
0130	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	54.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM524PMM123987 Oversight/State Project No.: PM5M-047-F24, P401

Order No.: 525

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MOT	LUMP SUM	LUMP SUM			
0150	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	1,915.480 SY				
0160	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	3,344.000 SY				
0170	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	465.000 LF				
0180	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	27.000 LF				

Section: 0001 Total: _____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0190	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON				

Section: 0002 Total: _____

Total Bid: _____