

Schedule of Items

Proposal ID: C0000123651N01 Oversight/State Project No.: PM9Q-076-F24, N501

Order No.: 935

Federal Project No.: PM09(375)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	303.000 TON	_____	_____	_____	_____
0020	310	310SD20-0001 TACK COAT	29,000.000 GAL	_____	_____	_____	_____
0030	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	43,000.000 LF	_____	_____	_____	_____
0040	315	315SP20-0049 ASPH. CONC. BMD P+VO SM- 9.5D	26,917.810 TON	_____	_____	_____	_____
0050	315	321SD20-0003 ASPH. CONC. TY. BM-25.0 T MAINT	138.340 TON	_____	_____	_____	_____
0060	323	323SD20-0041 SURFACE PREPARATION AND RESTORATION TYPE II	775.000 TON	_____	_____	_____	_____
0070	512	512SD20-0027 FLAGGER SERVICE	2,575.000 HR	_____	_____	_____	_____
0080	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	279,662.000 LF	_____	_____	_____	_____
0090	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	13,998.000 LF	_____	_____	_____	_____
0100	512	512SD20-0048 TEMP. PVMT MRKG TY. A, 8"	3,434.000 LF	_____	_____	_____	_____
0110	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	7,422.000 LF	_____	_____	_____	_____
0120	512	512SD20-0050 TEMP. PVMT MRKG TY. A, 24"	7,486.000 LF	_____	_____	_____	_____
0130	512	512SD20-0051 TEMP. PVMT. SYMB. MRKG THRU ARROW TY. A	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123651N01

Oversight/State Project No.: PM9Q-076-F24, N501

Order No.: 935

Federal Project No.: PM09(375)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	57.000 EA	_____	_____	_____	_____
0150	512	512SP20-0002 MAINTENANCE OF TRAFFIC MOT	LUMP SUM	LUMP SUM	_____	_____	_____
0160	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	290,001.060 SY	_____	_____	_____	_____
0170	700	700SD20-0118 14/1 CONDUCTOR CABLE ENCLOSED	41,732.000 LF	_____	_____	_____	_____
0180	700	700SD20-0183 CONDUIT METAL 1"	392.000 LF	_____	_____	_____	_____
0190	703	703SD20-0042 LOOP SAW CUT 3/8"	13,338.000 LF	_____	_____	_____	_____
0200	703	703SD20-0043 LOOP SAW CUT 5/8"	3,512.000 LF	_____	_____	_____	_____
0210	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	160,323.000 LF	_____	_____	_____	_____
0220	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	6,999.000 LF	_____	_____	_____	_____
0230	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	1,717.000 LF	_____	_____	_____	_____
0240	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	3,711.000 LF	_____	_____	_____	_____
0250	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	9,308.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123651N01

Oversight/State Project No.: PM9Q-076-F24, N501

Order No.: 935

Federal Project No.: PM09(375)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	704	704SD20-0035 PVMT MSG. MARK. "ONLY" TY B, CL. I, 6'	6.000 EA	_____	_____	_____	_____
0270	704	704SD20-0044 PVMT SYMB MRKG THRU ARROW TY B, CL I	4.000 EA	_____	_____	_____	_____
0280	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	255.000 EA	_____	_____	_____	_____
0290	704	704SD20-0049 MRKG DBL TURN ARR. THRU/LT OR RT TY A	4.000 EA	_____	_____	_____	_____
0300	704	704SD20-0050 DBL TURN ARR. THRU/LT OR RT TY B, CL I	6.000 EA	_____	_____	_____	_____
0310	704	704SD20-0058 SYMG MRKG LANE REDUCTION ARROW TY A	1.000 EA	_____	_____	_____	_____
0320	704	704SD20-0059 SYMB MRKG LANE REDUCTION ARR TY B CL I	2.000 EA	_____	_____	_____	_____
0330	704	704SD20-0107 PVMT MSG. MARK. "ONLY" TY B, CL. I, 8'	15.000 EA	_____	_____	_____	_____
0340	704	704SD20-0110 PVMT MSG. MARK. "SCHOOL" TY B, CL I, 8'	1.000 EA	_____	_____	_____	_____

Section: 0001

Total: _____

Schedule of Items

Proposal ID: C0000123651N01

Oversight/State Project No.: PM9Q-076-F24, N501

Order No.: 935

Federal Project No.: PM09(375)

Contractor: _____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0350	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:		_____	_____
				Total Bid:		_____	_____