

Schedule of Items

Proposal ID: C0000111791C01      Oversight/State Project No.: 0171-099-666, C501  
 Order No.: L06      Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	302	302SD20-0013 ENDWALL EW-12	5.000 EA				
0030	302	302SD20-0027 15" STORM SEWER PIPE	202.000 LF				
0040	302	302SD20-0066 42" STORM SEWER PIPE	9.000 LF				
0050	302	302SD20-0311 DROP INLET DI-3B,L=4'	2.000 EA				
0060	302	302SD20-0312 DROP INLET DI-3B,L=6'	2.000 EA				
0070	302	302SD20-0330 DROP INLET DI-3C,L=8'	1.000 EA				
0080	303	303SD20-0001 REGULAR EXCAVATION	2,444.000 CY				
0090	303	303SD20-0021 TEMPORARY DIVERSION DIKE	300.000 LF				
0100	303	303SD20-0023 CHECK DAM ROCK TY. II	18.000 EA				
0110	303	303SD20-0028 DEWATERING BASIN EC-8	1.000 EA				
0120	303	303SD20-0029 SILTATION CONTROL EXCAVATION	608.000 CY				
0130	303	303SD20-0030 INLET PROTECTION TYPE A	3.000 EA				
0140	303	303SD20-0031 INLET PROTECTION TYPE B	5.000 EA				

Schedule of Items

Proposal ID: C0000111791C01 Oversight/State Project No.: 0171-099-666, C501

Order No.: L06

Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	303	303SD20-0033 TEMP. SILT FENCE TYPE B	186.000 LF	_____	_____	_____	_____
0160	303	303SD20-0034 TEMP. SILT FENCE TYPE A	2,595.000 LF	_____	_____	_____	_____
0170	303	303SX20-0006 BORROW EXCAVATION MIN. CBR-15	800.000 CY	_____	_____	_____	_____
0180	306	306SD20-0001 LIME	4.950 TON	_____	_____	_____	_____
0190	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	2,122.000 TON	_____	_____	_____	_____
0200	315	315SD20-0002 ASPHALT CONCRETE TY. SM-12.5D CONST	942.000 TON	_____	_____	_____	_____
0210	315	315SD20-0005 ASPHALT CONCRETE TY. IM-19.0D CONST	420.000 TON	_____	_____	_____	_____
0220	315	315SD20-0010 ASPHALT CONCRETE BM-25.0A CONST	931.000 TON	_____	_____	_____	_____
0230	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE	3,044.000 LF	_____	_____	_____	_____
0240	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	961.000 LF	_____	_____	_____	_____
0250	401	401SD20-0007 COFFERDAM	1.000 EA	_____	_____	_____	_____
0260	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	3.200 TON	_____	_____	_____	_____
0270	501	501SD20-0002 UNDERDRAIN UD-2	175.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111791C01      Oversight/State Project No.: 0171-099-666, C501  
 Order No.: L06      Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	501	501SD20-0004 UNDERDRAIN UD-4	1,791.000 LF	_____	_____	_____	_____
0290	501	501SD20-0009 OUTLET PIPE	47.000 LF	_____	_____	_____	_____
0300	502	502SD20-0014 CURB, STD. CG-3	131.000 LF	_____	_____	_____	_____
0310	502	502SD20-0024 COMB. CURB & GUTTER, STD. CG-7	1,569.000 LF	_____	_____	_____	_____
0320	502	502SD20-0025 COMB. CURB & GUTTER, RAD. CG-7	115.000 LF	_____	_____	_____	_____
0330	502	502SD20-0056 MEDIAN STRIP MS-1A	194.000 SY	_____	_____	_____	_____
0340	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	5.000 CY	_____	_____	_____	_____
0350	505	505SD20-0011 GUARDRAIL GR-MGS1	305.000 LF	_____	_____	_____	_____
0360	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	1.000 EA	_____	_____	_____	_____
0370	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	1.000 EA	_____	_____	_____	_____
0380	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	202.000 LF	_____	_____	_____	_____
0390	507	507SD20-0005 FENCE FE-CL	1,359.000 LF	_____	_____	_____	_____
0400	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	1,969.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111791C01      Oversight/State Project No.: 0171-099-666, C501  
 Order No.: L06      Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	509	509SD20-0001 FLOWABLE BACKFILL	6.000 CY	_____	_____	_____	_____
0420	ATTD	510SX20-0016 REMOVE EXIST. FENCE (L/A FENCE & D-901)	1,885.000 LF	_____	_____	_____	_____
0430	ATTD	510SX20-0028 REMOVE EXIST. ENDWALL FES	1.000 EA	_____	_____	_____	_____
0440	ATTD	510SX20-0031 MODIFY EXIST. CONTROLLER	2.000 EA	_____	_____	_____	_____
0450	ATTD	510SX20-0031 MODIFY EXIST. DROP INLET	1.000 EA	_____	_____	_____	_____
0460	ATTD	510SX20-0038 REMOVE EXIST. MS-1A	117.000 SY	_____	_____	_____	_____
0470	ATTD	510SX20-0039 REMOVE EXIST. FIBER OPTIC CABLE	728.000 LF	_____	_____	_____	_____
0480	ATTD	510SX20-0039 REMOVE EXIST. STORM PIPE	278.000 LF	_____	_____	_____	_____
0490	511	511SD20-0001 ALLAYING DUST	44.000 HR	_____	_____	_____	_____
0500	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL- 3, >=40 MPH	2.000 EA	_____	_____	_____	_____
0510	512	512SD20-0013 TYPE 3 BARRICADE 8'	3.000 EA	_____	_____	_____	_____
0520	512	512SD20-0014 TEMPORARY SIGN	1,148.000 SF	_____	_____	_____	_____
0530	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	338.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111791C01      Oversight/State Project No.: 0171-099-666, C501  
 Order No.: L06      Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	5,475.000 DAY	_____	_____	_____	_____
0550	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	480.000 HR	_____	_____	_____	_____
0560	512	512SD20-0026 ELECTRONIC ARROW BOARD	288.000 HR	_____	_____	_____	_____
0570	512	512SD20-0027 FLAGGER SERVICE	120.000 HR	_____	_____	_____	_____
0580	512	512SD20-0029 WARNING LIGHT TY. B	360.000 DAY	_____	_____	_____	_____
0590	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	1,578.000 LF	_____	_____	_____	_____
0600	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	1,450.000 LF	_____	_____	_____	_____
0610	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	200.000 SF	_____	_____	_____	_____
0620	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	44.000 EA	_____	_____	_____	_____
0630	ATTD	512SX20-0005 TEMP. PVMT MRKG TY. A, 24"	36.000 LF	_____	_____	_____	_____
0640	ATTD	512SX20-0005 TEMP. PVMT MRKG TY. A, 6"	4,225.000 LF	_____	_____	_____	_____
0650	ATTD	512SX20-0006 TEMP. PVMT MRKG SNGL TURN ARROW TY. A	2.000 EA	_____	_____	_____	_____
0660	ATTD	512SX20-0006 TEMP. PVMT MRKG THRU ARROW TY. A	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111791C01      Oversight/State Project No.: 0171-099-666, C501  
 Order No.: L06      Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	ATTD	512SX20-0040 POLICE PATROL POLICE PATROL	32.000 HR	_____	_____	_____	_____
0680	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0690	514	514SD20-0003 FIELD OFFICE TY.III	12.000 MO	_____	_____	_____	_____
0700	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	720.000 SY	_____	_____	_____	_____
0710	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0720	602	602SD20-0003 TOPSOIL CLASS B 2"	0.900 ACRE	_____	_____	_____	_____
0730	603	603SD20-0002 TEMPORARY SEED	90.000 LB	_____	_____	_____	_____
0740	603	603SD20-0003 REGULAR SEED	203.000 LB	_____	_____	_____	_____
0750	603	603SD20-0004 OVERSEEDING	162.000 LB	_____	_____	_____	_____
0760	603	603SD20-0007 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	3,739.000 SY	_____	_____	_____	_____
0770	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	7,478.000 SY	_____	_____	_____	_____
0780	603	603SD20-0014 FERTILIZER NITROGEN - N	137.000 LB	_____	_____	_____	_____
0790	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	63.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111791C01      Oversight/State Project No.: 0171-099-666, C501  
 Order No.: L06      Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	603	603SD20-0016 FERTILIZER POTASSIUM - K	63.000 LB	_____	_____	_____	_____
0810	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	2,556.000 SY	_____	_____	_____	_____
0820	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	9.000 EA	_____	_____	_____	_____
0830	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	1.000 EA	_____	_____	_____	_____
0840	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	149.600 LF	_____	_____	_____	_____
0850	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	20.000 LF	_____	_____	_____	_____
0860	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	8.000 EA	_____	_____	_____	_____
0870	700	700SD20-0042 CONC. FOUND. STP-1, TY. E	2.000 EA	_____	_____	_____	_____
0880	700	700SD20-0068 CONC. FOUND. PF-8	24.000 CY	_____	_____	_____	_____
0890	700	700SD20-0095 SIGNAL MAST ARM POLE MP- 3, TY. E1	2.000 EA	_____	_____	_____	_____
0900	700	700SD20-0102 MAST ARM 65'	1.000 EA	_____	_____	_____	_____
0910	700	700SD20-0107 8/2 CONDUCTOR CABLE	1,156.000 LF	_____	_____	_____	_____
0920	700	700SD20-0114 14/7 CONDUCTOR CABLE	1,554.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111791C01      Oversight/State Project No.: 0171-099-666, C501  
 Order No.: L06      Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	700	700SD20-0118 14/1 CONDUCTOR CABLE ENCLOSED	1,980.000 LF	_____	_____	_____	_____
0940	700	700SD20-0120 14/2 CONDUCTOR CABLE SHIELDED	556.000 LF	_____	_____	_____	_____
0950	700	700SD20-0148 8 CONDUCTOR CABLE EGC	1,391.000 LF	_____	_____	_____	_____
0960	700	700SD20-0178 JUNCTION BOX JB-S2	6.000 EA	_____	_____	_____	_____
0970	700	700SD20-0182 CONDUIT PVC 1"	15.000 LF	_____	_____	_____	_____
0980	700	700SD20-0191 BORED CONDUIT 2"	463.000 LF	_____	_____	_____	_____
0990	700	700SD20-0192 BORED CONDUIT 3"	790.000 LF	_____	_____	_____	_____
1000	700	700SD20-0194 CONDUIT PVC 2"	485.000 LF	_____	_____	_____	_____
1010	700	700SD20-0195 CONDUIT PVC 3"	28.000 LF	_____	_____	_____	_____
1020	700	700SD20-0197 TRENCH EXCAVATION ECI-1	83.000 LF	_____	_____	_____	_____
1030	700	700SD20-0199 TEST BORE	2.000 EA	_____	_____	_____	_____
1040	700	700SD20-0225 LUMINAIRE ARM 18'	2.000 EA	_____	_____	_____	_____
1050	ATTD	700SX20-0025 MAST ARM 75', CASE 1 LOADING	1.000 EA	_____	_____	_____	_____
1060	701	701SD20-0001 SIGN PANEL	249.900 SF	_____	_____	_____	_____



Schedule of Items

Proposal ID: C0000111791C01      Oversight/State Project No.: 0171-099-666, C501  
 Order No.: L06      Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1070	703	703SD20-0007 TRAF. SIG. HEAD SECT. 12" HVS BACKPLATE	27.000 EA	_____	_____	_____	_____
1080	703	703SD20-0020 EVP DETECTION SYSTEM 1- WAY	2.000 EA	_____	_____	_____	_____
1090	703	703SD20-0024 EVP DETECTOR CABLE	623.000 LF	_____	_____	_____	_____
1100	703	703SD20-0026 LOOP DETECTOR AMPLIFIER	5.000 EA	_____	_____	_____	_____
1110	703	703SD20-0034 HANGER ASSEMBLY SM-3, ONE WAY	9.000 EA	_____	_____	_____	_____
1120	703	703SD20-0042 LOOP SAW CUT 3/8"	660.000 LF	_____	_____	_____	_____
1130	703	703SD20-0043 LOOP SAW CUT 5/8"	72.000 LF	_____	_____	_____	_____
1140	703	703SD20-0044 REMOVE EXISTING POLE	2.000 EA	_____	_____	_____	_____
1150	703	703SD20-0045 REMOVE EXISTING FOUNDATION	2.000 EA	_____	_____	_____	_____
1160	703	703SD20-0046 REMOVE EXISTING SIGNAL HEAD	8.000 EA	_____	_____	_____	_____
1170	703	703SD20-0048 REMOVE EXISTING MANHOLE/JUNCTION BOX	6.000 EA	_____	_____	_____	_____
1180	ATTD	703SX20-0003 DETECTOR TEMP. DETECTION VIDEO SYSTEM AT 2 LOCATIONS	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111791C01

Oversight/State Project No.: 0171-099-666, C501

Order No.: L06

Federal Project No.: STP-5B03(122)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1190	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	3,571.000 LF	_____	_____	_____	_____
1200	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	94.000 LF	_____	_____	_____	_____
1210	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	74.000 LF	_____	_____	_____	_____
1220	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	46.000 EA	_____	_____	_____	_____
1230	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	13.000 EA	_____	_____	_____	_____
1240	704	704SD20-0108 PVMT MSG. MARK. "ONLY" TY B, CL II, 8'	2.000 EA	_____	_____	_____	_____
1250	ATTD	801SX20-0002 COMMUNICATION EQUIP. FIBER OPTIC SPLICE	LUMP SUM	LUMP SUM	_____	_____	_____
1260	812	812SD20-0002 BORED ITS CONDUIT HDPE 2"	124.000 LF	_____	_____	_____	_____

Section: 0001

Total: \_\_\_\_\_

Total Bid: \_\_\_\_\_