

Schedule of Items

Proposal ID: C0000113852B44

Oversight/State Project No.: 0638-016-640, B644, M501

Order No.: L10

Federal Project No.: STP-016-6(073)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	303	303SD20-0001 REGULAR EXCAVATION	415.000 CY				
0030	303	303SD20-0007 BORROW EXCAVATION	100.000 CY				
0040	303	303SD20-0013 GEOTEXTILE EMBANKMENT STAB.	1,040.000 SY				
0050	303	303SD20-0026 CHECK DAM ROCK TYPE I TEMPORARY	1.000 EA				
0060	303	303SD20-0028 DEWATERING BASIN EC-8	2.000 EA				
0070	303	303SD20-0029 SILTATION CONTROL EXCAVATION	70.000 CY				
0080	303	303SD20-0034 TEMP. SILT FENCE TYPE A	370.000 LF				
0090	305	305SX20-0002 AGGR. MATL NO. 3	250.000 TON				
0100	309	309SD20-0010 AGGR. BASE MATL. TY. I NO. 21B	390.000 TON				
0110	315	315SD20-0001 ASPHALT CONCRETE TY. SM-12.5A CONST	110.000 TON				
0120	315	315SD20-0004 ASPHALT CONCRETE TY. IM-19.0A CONST	100.000 TON				
0130	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	37.000 LF				

Schedule of Items

Proposal ID: C0000113852B44

Oversight/State Project No.: 0638-016-640, B644, M501

Order No.: L10

Federal Project No.: STP-016-6(073)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	855.000 CY	_____	_____	_____	_____
0150	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	727.000 TON	_____	_____	_____	_____
0160	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	52.000 SY	_____	_____	_____	_____
0170	401	401SD20-0007 COFFERDAM	2.000 EA	_____	_____	_____	_____
0180	403	403SD20-0004 DYNAMIC PILE TEST	3.000 EA	_____	_____	_____	_____
0190	403	403SD20-0014 PRESTRESSED CONCRETE STEEL STRAND PILES 18"	990.000 LF	_____	_____	_____	_____
0200	403	403SD20-0016 PRESTRESSED CONCRETE STEEL STRAND PILES 24"	240.000 LF	_____	_____	_____	_____
0210	403	403SD20-0044 DRIVING TEST FOR 18" PRESTR. CONC. PILE	130.000 LF	_____	_____	_____	_____
0220	403	403SD20-0051 DRIVING TEST FOR 24" PRESTR. CONC. PILE	70.000 LF	_____	_____	_____	_____
0230	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST.	70.000 CY	_____	_____	_____	_____
0240	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	343.000 SY	_____	_____	_____	_____
0250	404	404SD20-0010 COVER DEPTH SURVEY CONST.	343.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113852B44      Oversight/State Project No.: 0638-016-640, B644, M501  
 Order No.: L10      Federal Project No.: STP-016-6(073)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	117.000 CY	_____	_____	_____	_____
0270	ATTD, 404	404SP20-0003 VA ADJACENT MEMBER CONN. BLOCK-OUTS	174.000 CF	_____	_____	_____	_____
0280	405	405SD20-0016 PREST. CONC. SLAB 3' X 21" X(+50'-55')	4.000 EA	_____	_____	_____	_____
0290	405	405SD20-0212 PREST. CONC. SLAB 4' X 21" X(+50'-55')	12.000 EA	_____	_____	_____	_____
0300	406	406SD20-0003 CR REINF. STEEL CL. I SPR. STRUCT. CONST.	6,340.000 LB	_____	_____	_____	_____
0310	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	15,020.000 LB	_____	_____	_____	_____
0320	410	410SD20-0011 RAILING CPSR 2 RAIL CONST.	220.000 LF	_____	_____	_____	_____
0330	413	413SX20-0002 DISM.& REM. EX. STR. NS DISM. & REM. EXIST. STR.	LUMP SUM	LUMP SUM	_____	_____	_____
0340	414	414SD20-0012 DRY RIPRAP CL.I 26"	525.000 TON	_____	_____	_____	_____
0350	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE B640	1.000 DAY	_____	_____	_____	_____
0360	502	502SD20-0014 CURB, STD. CG-3	50.000 LF	_____	_____	_____	_____
0370	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	175.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113852B44

Oversight/State Project No.: 0638-016-640, B644, M501

Order No.: L10

Federal Project No.: STP-016-6(073)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	505	505SD20-0017 GUARDRAIL TERMINAL GR-MGS2	2.000 EA	_____	_____	_____	_____
0390	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	2.000 EA	_____	_____	_____	_____
0400	505	505SD20-0055 FIXED OBJECT ATTACH. GR-FOA-5	4.000 EA	_____	_____	_____	_____
0410	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	542.000 LF	_____	_____	_____	_____
0420	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	630.000 SY	_____	_____	_____	_____
0430	512	512SD20-0013 TYPE 3 BARRICADE 8'	8.000 EA	_____	_____	_____	_____
0440	512	512SD20-0014 TEMPORARY SIGN	1,250.000 SF	_____	_____	_____	_____
0450	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	48.000 LF	_____	_____	_____	_____
0460	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0470	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0480	602	602SD20-0003 TOPSOIL CLASS B 2"	0.100 ACRE	_____	_____	_____	_____
0490	603	603SD20-0002 TEMPORARY SEED	15.000 LB	_____	_____	_____	_____
0500	603	603SD20-0003 REGULAR SEED	28.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113852B44      Oversight/State Project No.: 0638-016-640, B644, M501  
 Order No.: L10      Federal Project No.: STP-016-6(073)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	603	603SD20-0004 OVERSEEDING	23.000 LB	_____	_____	_____	_____
0520	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	726.000 SY	_____	_____	_____	_____
0530	603	603SD20-0010 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	908.000 SY	_____	_____	_____	_____
0540	603	603SD20-0014 FERTILIZER NITROGEN - N	23.000 LB	_____	_____	_____	_____
0550	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	11.000 LB	_____	_____	_____	_____
0560	603	603SD20-0016 FERTILIZER POTASSIUM - K	11.000 LB	_____	_____	_____	_____
0570	603	603SD20-0017 LIME	0.800 TON	_____	_____	_____	_____
0580	ATTD	605SX20-0017 SEED MIXTURE WETLAND SEEDING	10.000 LB	_____	_____	_____	_____
0590	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	35.000 SY	_____	_____	_____	_____
0600	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	265.000 SY	_____	_____	_____	_____
0610	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	20.000 LF	_____	_____	_____	_____
0620	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	2.000 EA	_____	_____	_____	_____
0630	701	701SD20-0001 SIGN PANEL	7.500 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113852B44

Oversight/State Project No.: 0638-016-640, B644, M501

Order No.: L10

Federal Project No.: STP-016-6(073)

Contractor: \_\_\_\_\_

Section: 0001

Total: \_\_\_\_\_

Total Bid: \_\_\_\_\_