

Schedule of Items

Proposal ID: C0000118375C01B Oversight/State Project No.: 0058-133-459,C501,B616

Order No.: K61

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	25.000 EA				
0030	ATTD	109SX20-0030 MONITORING (VIBRATING WIRE PIEZOMETERS)	5.000 EA				
0040	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0050	302, 406	302SD20-0005 REINF. STEEL	1,657.000 LB				
0060	302	302SD20-0013 ENDWALL EW-12	15.000 EA				
0070	302	302SD20-0025 15" CONC. PIPE	58.000 LF				
0080	302	302SD20-0027 15" STORM SEWER PIPE	77.000 LF				
0090	302	302SD20-0039 24" CONC. PIPE	79.000 LF				
0100	302	302SD20-0059 36" CONC. PIPE	112.000 LF				
0110	302	302SD20-0064 42" CONC. PIPE	138.000 LF				
0120	302	302SD20-0069 48" CONC. PIPE	54.000 LF				
0130	302	302SD20-0081 60" CONC. PIPE	519.000 LF				
0140	302	302SD20-0237 DROP INLET DI-1	2.000 EA				

Schedule of Items

Proposal ID: C0000118375C01B    Oversight/State Project No.: 0058-133-459,C501,B616  
 Order No.: K61    Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0458 DROP INLET DI-10H TY. I,L=14'	1.000 EA	_____	_____	_____	_____
0160	302	302SD20-0500 DROP INLET DI-10K TY. II,L=6'	1.000 EA	_____	_____	_____	_____
0170	302	302SD20-0655 DROP INLET DI-13 TY.I	2.000 EA	_____	_____	_____	_____
0180	302	302SD20-0656 DROP INLET DI-13 TY.II	1.000 EA	_____	_____	_____	_____
0190	302	302SD20-0662 MANHOLE MH-1 OR 2	8.000 LF	_____	_____	_____	_____
0200	302	302SD20-0663 FRAME & COVER MH-1	1.000 EA	_____	_____	_____	_____
0210	303	303SD20-0001 REGULAR EXCAVATION	10,183.000 CY	_____	_____	_____	_____
0220	303	303SD20-0015 SETTLEMENT PLATE	6.000 EA	_____	_____	_____	_____
0230	303	303SD20-0016 MINOR STR. EXCAV. PIPE CULVERT	985.000 CY	_____	_____	_____	_____
0240	303	303SD20-0022 CHECK DAM ROCK TY. I	20.000 EA	_____	_____	_____	_____
0250	303	303SD20-0028 DEWATERING BASIN EC-8	17.000 EA	_____	_____	_____	_____
0260	303	303SD20-0029 SILTATION CONTROL EXCAVATION	2,094.000 CY	_____	_____	_____	_____
0270	303	303SD20-0030 INLET PROTECTION TYPE A	2.000 EA	_____	_____	_____	_____
0280	303	303SD20-0031 INLET PROTECTION TYPE B	8.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B Oversight/State Project No.: 0058-133-459,C501,B616

Order No.: K61

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	303	303SD20-0034 TEMP. SILT FENCE TYPE A	10,147.000 LF	_____	_____	_____	_____
0300	ATTD	303SX20-0003 EXCAVATION TEMP. DIVERSION CHANNEL EXCAVATION	467.000 CY	_____	_____	_____	_____
0310	303	303SX20-0003 EXCAVATION UNDERCUT EXCAVATION	5,169.000 CY	_____	_____	_____	_____
0320	ATTD	303SX20-0008 GEOTEXTILE (GASOLINE RESISTANT GEOMEMBRANE)	5,800.000 SY	_____	_____	_____	_____
0330	305	303SX20-0008 GEOTEXTILE (GEOGRID)	2,000.000 SY	_____	_____	_____	_____
0340	305	305SD20-0001 BORROW EXCAVATION	44,979.000 CY	_____	_____	_____	_____
0350	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	7,622.000 SY	_____	_____	_____	_____
0360	ATTD	305SX20-0004 SELECT MATERIAL (EXPANDED POLYSTYRENE (EPS) GEOFOAM BLOCK FILL)	9,100.000 CY	_____	_____	_____	_____
0370	ATTD	305SX20-0006 SELECT MATERIAL (GRANULAR FILL)	20,500.000 TON	_____	_____	_____	_____
0380	307	307SD20-0004 CEM. STAB. AGGR. BASE. MATL. TY. I NO. 21A	5,917.000 TON	_____	_____	_____	_____
0390	312	312SD20-0006 COVER MATL. AGGR. NO. 8	56.000 TON	_____	_____	_____	_____
0400	313	313SD20-0001 ASPH-STAB. OPEN-GRADED MATERIAL	1,143.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B    Oversight/State Project No.: 0058-133-459,C501,B616  
 Order No.: K61    Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	315	315SD20-0003 ASPHALT CONCRETE TY. SM-12.5E CONST	994.000 TON	_____	_____	_____	_____
0420	315	315SD20-0011 ASPHALT CONCRETE TY. BM-25.0D CONST	6,528.000 TON	_____	_____	_____	_____
0430	315	315SD20-0018 ASPH.CONC.CURB BACKUP MATL. CONST	27.000 TON	_____	_____	_____	_____
0440	315	315SX20-0011 SAW-CUT ASPH CONC (FULL DEPTH)	5,531.000 LF	_____	_____	_____	_____
0450	317, 315	317SD20-0004 STONE MATRIX ASPH. SMA-12.5 64E-22	4,235.000 TON	_____	_____	_____	_____
0460	317, 315	317SD20-0006 STONE MATRIX ASPH. SMA-19.0 64E-22	1,894.000 TON	_____	_____	_____	_____
0470	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	1,104.000 CY	_____	_____	_____	_____
0480	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	120.000 LF	_____	_____	_____	_____
0490	401	401SD20-0007 COFFERDAM	16.000 EA	_____	_____	_____	_____
0500	402	402SD20-0004 TEMPORARY SHEET PILING	3,254.000 SF	_____	_____	_____	_____
0510	403	403SD20-0004 DYNAMIC PILE TEST	5.000 EA	_____	_____	_____	_____
0520	403	403SD20-0014 PRESTRESSED CONCRETE STEEL STRAND PILES 18"	5,455.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B    Oversight/State Project No.: 0058-133-459,C501,B616  
 Order No.: K61    Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	403	403SD20-0044 DRIVING TEST FOR 18" PRESTR. CONC. PILE	336.000 LF	_____	_____	_____	_____
0540	404	404SD20-0003 CONCRETE CLASS A3, SPR. STRUCT. CONST. - LOAD DISTRIBUTION SLAB	556.300 CY	_____	_____	_____	_____
0550	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST.	694.800 CY	_____	_____	_____	_____
0560	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	2,264.000 SY	_____	_____	_____	_____
0570	404	404SD20-0010 COVER DEPTH SURVEY CONST.	2,500.000 SY	_____	_____	_____	_____
0580	404	404SD20-0012 CONCRETE CLASS A4, SUBSTRUCT. CONST.	946.800 CY	_____	_____	_____	_____
0590	406	406SD20-0001 REINFORCING STEEL SPR. STRUCT. CONST. - LOAD DISTRIBUTION SLAB	82,860.000 LB	_____	_____	_____	_____
0600	406	406SD20-0003 CR REINF. STEEL CL. I SPR. STRUCT. CONST.	183,540.000 LB	_____	_____	_____	_____
0610	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	95,930.000 LB	_____	_____	_____	_____
0620	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	50,320.000 LB	_____	_____	_____	_____
0630	407	407SD20-0007 STR.ST.PLATE GIRDER ASTM A709 GR.50W	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B Oversight/State Project No.: 0058-133-459,C501,B616

Order No.: K61

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	410	410SD20-0006 CONCRETE PARAPET 42" CONST.	1,281.000 LF	_____	_____	_____	_____
0650	ATTD	410SX20-0011 PIER PROTECTION SYSTEM 54", CONST	281.000 LF	_____	_____	_____	_____
0660	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	211.000 TON	_____	_____	_____	_____
0670	415	415SD20-0004 CONC. SLAB SLOPE PROTECTION 4"	231.000 SY	_____	_____	_____	_____
0680	416	416SD20-0003 WATERPROOFING – EPOXY RESIN TYPE EP-3B/EP-3T	213.000 SY	_____	_____	_____	_____
0690	419	419SX20-0008 BRG. CONDUIT SYSTEM STR. NO. 8074	LUMP SUM	LUMP SUM	_____	_____	_____
0700	423	423SD20-0003 TOOTH EXP.JT. ASSEMBLY 2" CONST.	71.000 LF	_____	_____	_____	_____
0710	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE STR. NO. 8074	2.000 DAY	_____	_____	_____	_____
0720	501	501SD20-0004 UNDERDRAIN UD-4	4,823.000 LF	_____	_____	_____	_____
0730	501	501SD20-0009 OUTLET PIPE	148.000 LF	_____	_____	_____	_____
0740	502	502SD20-0014 CURB, STD. CG-3	136.000 LF	_____	_____	_____	_____
0750	502	502SD20-0020 CURB, ASPHALT MC-3B	657.000 LF	_____	_____	_____	_____
0760	502	502SD20-0037 MEDIAN BARRIER MB-7E	100.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B Oversight/State Project No.: 0058-133-459,C501,B616

Order No.: K61

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0770	502	502SD20-0038 MEDIAN BARRIER MB-7F	381.000 LF	_____	_____	_____	_____
0780	502	502SD20-0044 MEDIAN BARRIER MB-8A TYPE I	22.000 LF	_____	_____	_____	_____
0790	ATTD	502SX20-0002 MEDIAN BARRIER (F-SHAPED PARAPET WITH MOMENT SLAB)	456.000 LF	_____	_____	_____	_____
0800	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	91.000 CY	_____	_____	_____	_____
0810	505	505SD20-0011 GUARDRAIL GR-MGS1	4,895.000 LF	_____	_____	_____	_____
0820	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	1.000 EA	_____	_____	_____	_____
0830	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	3.000 EA	_____	_____	_____	_____
0840	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	9.000 EA	_____	_____	_____	_____
0850	505	505SD20-0039 GUARDRAIL TER.SITE PREPARATION	1.000 EA	_____	_____	_____	_____
0860	505	505SD20-0040 GUARDRAIL GR-10	150.000 LF	_____	_____	_____	_____
0870	505	505SD20-0053 FIXED OBJECT ATTACH. GR- FOA-2 TY. I	1.000 EA	_____	_____	_____	_____
0880	505	505SD20-0055 FIXED OBJECT ATTACH. GR- FOA-5	5.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B    Oversight/State Project No.: 0058-133-459,C501,B616  
 Order No.: K61    Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0890	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	933.000 LF	_____	_____	_____	_____
0900	ATTD	506SX20-0006 RETAINING WALL TILT-UP WALL	4,722.000 SF	_____	_____	_____	_____
0910	507	507SD20-0001 FENCE FE-W1	2,122.000 LF	_____	_____	_____	_____
0920	507	507SD20-0003 LINE BRACE UNIT FE-W1 OR FE-W2	1.000 EA	_____	_____	_____	_____
0930	507	507SD20-0004 CORNER BRACE UNIT FE-W1 OR FE-W2	9.000 EA	_____	_____	_____	_____
0940	508	508SD20-0001 OBSCURING ROADWAY	21.000 UNIT	_____	_____	_____	_____
0950	508	508SD20-0003 DEMO. OF PAVEMENT RIGID	84.000 SY	_____	_____	_____	_____
0960	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	6,070.000 SY	_____	_____	_____	_____
0970	509	509SD20-0001 FLOWABLE BACKFILL	11.000 CY	_____	_____	_____	_____
0980	ATTD	510SX20-0016 REMOVE EXIST. FENCE REMOVE EXIST. FENCE	1,645.000 LF	_____	_____	_____	_____
0990	ATTD	510SX20-0029 RESET EXIST. (REMOVE AND RESET GATE)	1.000 EA	_____	_____	_____	_____
1000	ATTD	510SX20-0039 REMOVE EXIST. CONDUCTORS	6,900.000 LF	_____	_____	_____	_____



Schedule of Items

Proposal ID: C0000118375C01B Oversight/State Project No.: 0058-133-459,C501,B616

Order No.: K61

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1010	ATTD	510SX20-0040 REMOVE EXIST. ELECTRICAL SERVICE	1.000 EA	_____	_____	_____	_____
1020	ATTD	510SX20-0040 REMOVE EXIST. FLASHING BEACON ASSEMBLY	4.000 EA	_____	_____	_____	_____
1030	ATTD	510SX20-0042 RELOCATE EXISTING LIGHT POLE	8.000 EA	_____	_____	_____	_____
1040	ATTD	510SX20-0048 INSTALL VALVE & BOX 36" BUTTERFLY VALVE & BOX	2.000 EA	_____	_____	_____	_____
1050	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL-3, >=40 MPH	6.000 EA	_____	_____	_____	_____
1060	512	512SD20-0012 TYPE 3 BARRICADE 4'	8.000 EA	_____	_____	_____	_____
1070	512	512SD20-0013 TYPE 3 BARRICADE 8'	8.000 EA	_____	_____	_____	_____
1080	512	512SD20-0014 TEMPORARY SIGN	5,674.000 SF	_____	_____	_____	_____
1090	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	5,440.000 HR	_____	_____	_____	_____
1100	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	50,542.000 DAY	_____	_____	_____	_____
1110	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	3,616.000 HR	_____	_____	_____	_____
1120	512	512SD20-0026 ELECTRONIC ARROW BOARD	6,512.000 HR	_____	_____	_____	_____
1130	512	512SD20-0029 WARNING LIGHT TY. B	15.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B    Oversight/State Project No.: 0058-133-459,C501,B616  
 Order No.: K61    Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1140	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	11,912.000 LF	_____	_____	_____	_____
1150	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	555.000 LF	_____	_____	_____	_____
1160	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	400.000 LF	_____	_____	_____	_____
1170	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	100.000 EA	_____	_____	_____	_____
1180	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	8,049.000 LF	_____	_____	_____	_____
1190	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	3,788.000 LF	_____	_____	_____	_____
1200	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
1210	514	514SD20-0001 FIELD OFFICE TY.I	25.000 MO	_____	_____	_____	_____
1220	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	15,630.000 SY	_____	_____	_____	_____
1230	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM		_____	_____
1240	520	520SD20-0313 54" STEEL JACKED ENCASEMENT PIPE	161.000 LF	_____	_____	_____	_____
1250	602	602SX20-0005 TOPSOIL (CLASS B 3" DEPTH)	10.000 ACRE	_____	_____	_____	_____
1260	603	603SD20-0002 TEMPORARY SEED	1,000.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B    Oversight/State Project No.: 0058-133-459,C501,B616  
 Order No.: K61    Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1270	603	603SD20-0003 REGULAR SEED	1,750.000 LB	_____	_____	_____	_____
1280	603	603SD20-0004 OVERSEEDING	1,400.000 LB	_____	_____	_____	_____
1290	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	42,350.000 SY	_____	_____	_____	_____
1300	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	66,550.000 SY	_____	_____	_____	_____
1310	603	603SD20-0011 SEDIMENT RETENTION ROLL 18" MIN	625.000 LF	_____	_____	_____	_____
1320	603	603SD20-0014 FERTILIZER NITROGEN - N	956.000 LB	_____	_____	_____	_____
1330	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	1,313.000 LB	_____	_____	_____	_____
1340	603	603SD20-0016 FERTILIZER POTASSIUM - K	656.000 LB	_____	_____	_____	_____
1350	603	603SD20-0017 LIME	45.000 TON	_____	_____	_____	_____
1360	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	5,160.000 SY	_____	_____	_____	_____
1370	606	606SD20-0007 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	5.000 SY	_____	_____	_____	_____
1380	608	608SD20-0001 MOWING	100.000 HR	_____	_____	_____	_____
1390	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	13.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B Oversight/State Project No.: 0058-133-459,C501,B616

Order No.: K61

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1400	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	3.000 EA	_____	_____	_____	_____
1410	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	5.000 EA	_____	_____	_____	_____
1420	700	700SD20-0018 VA SIGN POST W4 X 13	11.000 LF	_____	_____	_____	_____
1430	700	700SD20-0019 VA SIGN POST W6 X 12	86.000 LF	_____	_____	_____	_____
1440	700	700SD20-0024 VIA SIGN POST W14 X 22	40.000 LF	_____	_____	_____	_____
1450	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	90.000 LF	_____	_____	_____	_____
1460	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	48.000 LF	_____	_____	_____	_____
1470	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	171.000 LF	_____	_____	_____	_____
1480	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	28.000 LF	_____	_____	_____	_____
1490	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	11.000 EA	_____	_____	_____	_____
1500	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	12.000 EA	_____	_____	_____	_____
1510	700	700SD20-0045 CONC. FOUND. SSP-VA, 2'6" DIA. X 7' DEEP	1.000 EA	_____	_____	_____	_____
1520	700	700SD20-0046 CONC. FOUND. SSP-VA, 1'9" DIA. X 4'6" DEEP	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118375C01B Oversight/State Project No.: 0058-133-459,C501,B616

Order No.: K61

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1530	700	700SD20-0047 CONC. FOUND. SSP-VA, 2'6" DIA. X 6' DEEP	6.000 EA	_____	_____	_____	_____
1540	700	700SD20-0049 CONC. FOUND. SSP-VIA, 3' DIA. X 7' DEEP	2.000 EA	_____	_____	_____	_____
1550	700	700SD20-0056 CONC. FOUND. O/H SIGN STRUCTURE	10.200 CY	_____	_____	_____	_____
1560	700	700SD20-0131 ELECTRICAL SERVICE SE-2, TY. B	1.000 EA	_____	_____	_____	_____
1570	700	700SD20-0143 6 CONDUCTOR CABLE	3,750.000 LF	_____	_____	_____	_____
1580	700	700SD20-0149 CONC. FOUND. LF-1, TY. A	8.000 EA	_____	_____	_____	_____
1590	700	700SD20-0177 JUNCTION BOX JB-S1	4.000 EA	_____	_____	_____	_____
1600	700	700SD20-0191 BORED CONDUIT 2"	160.000 LF	_____	_____	_____	_____
1610	700	700SD20-0194 CONDUIT PVC 2"	1,120.000 LF	_____	_____	_____	_____
1620	700	700SD20-0197 TRENCH EXCAVATION ECI-1	1,120.000 LF	_____	_____	_____	_____
1630	700	700SD20-0199 TEST BORE	1.000 EA	_____	_____	_____	_____
1640	700	700SX20-0003 SIGN STRUCTURE, OVERHEAD CANT. OVERHEAD CANTILEVER	1.000 EA	_____	_____	_____	_____

Proposal ID: C0000118375C01B    Oversight/State Project No.: 0058-133-459,C501,B616  
 Order No.: K61    Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1650	700	700SX20-0017 REMOVE EXIST. OVERHEAD SIGN STRUCTURE OVERHEAD SIGN STRUCTURE	1.000 EA	_____	_____	_____	_____
1660	ATTD	700SX20-0021 TRAFFIC SIGN (MOUNT SIGN PANEL TO MEDIAN BARRIER)	6.000 EA	_____	_____	_____	_____
1670	701	701SD20-0001 SIGN PANEL	798.000 SF	_____	_____	_____	_____
1680	703	703SD20-0048 REMOVE EXISTING MANHOLE/JUNCTION BOX	4.000 EA	_____	_____	_____	_____
1690	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	22,419.000 LF	_____	_____	_____	_____
1700	704	704SD20-0028 TYPE B CLASS VI PVMT LINE MRKG 8"	1,735.000 LF	_____	_____	_____	_____
1710	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	2,055.000 LF	_____	_____	_____	_____
1720	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	233.000 EA	_____	_____	_____	_____
1730	705	705SD20-0003 CONTROL CENTER CCW-1 TYPE C	1.000 EA	_____	_____	_____	_____
1740	ATTD	705SX20-0002 LIGHTING PHOTOCELL REMOVAL	18.000 EA	_____	_____	_____	_____

Section: 0001    Total: \_\_\_\_\_

Total Bid: \_\_\_\_\_